




P.O. Box 21017 1601 Lewis Avenue Building Billings, Montana 59104 (406) 259-7860

June 18, 1992



DIVISION OF OIL GAS & MINING

-- VIA FEDERAL EXPRESS --

State of Utah Division of Oil, Gas & Mining 355 West North Temple Salt Lake City, UT 84180

Gentlemen:

Enclosed are Applications for Permit to Drill the following wells in Duchesne County, Utah:

Balcron Monument Federal #11-6 NW NW Section 6, T9S, R17E

Balcron Monument Federal #33-6 NW SE Section 6, T9S, R17E

Balcron Monument Federal #42-6 SE NE Section 6, T9S, R17E

Balcron Monument Federal #24-6 SE SW Section 6, T9S, R17E

We have submitted these APDs to the Bureau of Land Management and will provide a copy of the approved Federal APDs when we have received them.

We request that the status of these wells be held tight for the maximum period allowed by State regulations.

If you have any questions or need further information, please let me know.

Sincerely,

Bobbie Schuman

Coordinator of Operations,

lue Alhuman

Environmental and Regulatory Affairs

/rs

Enclosures

Form 3160-3 (November 1983) Form approved.

Expires August 31, 1985

SUBMIT IN TRIPLICATE® Budget Bureau No. 1004-0136 (Other instructions on UNITED STATES reverse side) (formerly 9-331C) DEPARTMENT OF THE INTERIOR 5. LEASE DESIGNATION AND SERIAL NO. BUREAU OF LAND MANAGEMENT U-020252A 6. IF INDIAN, ALLOTTER OR TRIBE NAME APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK n/a 1a. TYPE OF WORK 7. UNIT AGREEMENT NAME DEEPEN [PLUG BACK DRILL X b. TYPE OF WELL MULTIPLE Zone SINGLE ZONE 8. FARM OR LEASE NAME WELL X 2. NAME OF OPERATOR Balcron Monument Federal 9. WELL NO. **EQUITABLE RESOURCES ENERGY COMPANY** 3. ADDRESS OF OPERATOR 33-6 10. FIELD AND POOL, OR WILDCAT P.O. Box 21017; Billings, MT 59104 4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.*) Monument Butte Masatch At surface 11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA 1832' FSL 1829' FEL At proposed prod. zone NW SESec. 6, T9S, R17E 12. COUNTY OR PARISH | 13. STATE 14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE® UTAH 10 miles southeast of Myton, Utah Duchesne 15. DISTANCE FROM PROPUSED* 17. NO. OF ACRES ASSIGNED TO THIS WELL 16. NO. OF ACRES IN LEASE DISTANCE PROM FROM TO SEARCH TO SEARCH TO SEARCH TO SEARCH TO SEARCH LINE, FT. (Also to nearest drig, unit line, if any) 20. ROTARY OR CABLE TOOLS 18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT. 19. PROPOSED DEPTH 5,580' Rotary 22. APPROX. DATE WORK WILL START* 21. ELEVATIONS (Show whether DF, RT, GR, etc.) 8/21/92 5,267.7' PROPOSED CASING AND CEMENTING PROGRAM QUANTITY OF CEMENT SETTING DEPTH WEIGHT PER FOOT SIZE OF HOLE SIZE OF CASING 260 <u>12-1/4"</u> 8-5/8" 24# 250 See EXHIBAT 15.5# 5.580 7-7/8" EXHIBITS ATTACHED JUN 1 9 1992 ARCHEOLOGY REPORT "A"

PROPOSED DRILLING PROGRAM "B"

RIG LAYOUT PROPOSED SURFACE USE PROGRAM "H" BOPE SCHEMATIC

"C" GEOLOGIC PROGNOSIS " T " "D" DRILLING PROGRAM

"E" EVIDENCE OF BOND COVERAGE "G"

DIVISION OF LOCATION SITE AND ELEVATION LIGAS & MINING

EXISTING ROADS/PLANNED ACCESS (MAPS A & B) " ໆ "

"K" EXISTING WELLS (MAP C)

"L" DRILL PAD LAYOUT


SELF CERTIFICATION: I hereby certify that I am authorized, by proper lease interest owner, to conduct these operations associated with the application. Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Equitable Resources Energy Company as principal and Safeco Insurance Company of America as surety under BLM Bond No. MT 0576 (Nationwide Oil & Gas Bond #5547188) who will be responsible for compliance with all of the terms and conditions of that portion of the lease associated with this application.

IN ABOVE SPACE DESCRIBE PROFOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive sone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout

preventer program, if any.		
SIGNED Dobbie Schuman	Coordinator of Environment and Regulatory Affairs	al June 18, 1992
(This space for Federal or State office use)		. V
PERMIT NO.	APPROVAL DATE	
APPROVED BY	TITLE	DATE

T9S, R17E, S.L.B. & M.

N 89°58' E (GLO)



N 89°55' E (GLO)

X = SECTION CORNERS LOCATED
BASIS OF BEARINGS; G.L.O. PLAT 1911
BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (MYTON SOUTHEAST)

EQUITABLE RESOURCES ENERGY CO.

WELL LOCATION, BALCRON MONUMENT FED. 33-6, LOCATED AS SHOWN IN THE NW 1/4 SE 1/4 OF SECTION 6, T9S, R17E, S.L.B. & M, DUCHESNE COUNTY UTAH.



TRI STATE LAND SURVEYING & CONSULTING 38 EAST 100 NORTH, VERNAL, UTAH 84078 (801) 781-2501

SCALE:	1" = 1000'	SURVEYED BY: SS KH
DATE:	4/3/92	WEATHER: CLEAR & HOT
NOTES:		FAC # #33-6

EXHIBIT "A"
Proposed Drilling Program
Page 1

EQUITABLE RESOURCES ENERGY COMPANY
Balcron Oil Division
Balcron Monument Federal #33-6
NW SE Section 6-T9S-R17E
Duchesne County, Utah

In accordance with requirements outlined in 43 CFR 3162-3.1 (d):

1. ESTIMATED IMPORTANT GEOLOGICAL MARKERS:

See Geologic Prognosis (EXHIBIT "C")

2. ESTIMATED DEPTHS OF ANTICIPATED OIL, GAS OR WATER:

See Geologic Prognosis (EXHIBIT "C)

- 3. OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:
 - a. EXHIBIT "H" is a schematic of the BOP equipment and choke manifold. A 2M system will be used. The BOPE will be installed after setting 8-5/8" casing at 260'. The blind rams and pipe rams will be tested to 1500 psi. The annular preventer will be tested to 500 psi. Pipe rams will be operationally checked each 24-hour period and blind rams each time pipe is pulled out of the hole.
 - b. The BOPE will be tested to 1500 psi when initially installed, whenever any seal subject to test pressure is broken, and following related repairs. The pipe and blind rams will be activated at least weekly and on every trip the pipe and blind rams will be activated.
 - c. An accumulator of sufficient capacity to open the hydraulically-controlled choke valve lines (if so equipped), close all rams plus the annular preventer, and retain a minimum of 200 psi above precharge on the closing manifold without the use of the closing unit pumps will be installed during the drilling of this well.
 - d. An upper kelly cock will be used during the drilling of this well.
 - e. Visual mud monitoring equipment will be used to detect volume changes indicating loss or gain in circulating fluid volume.
 - f. Sufficient quantities of mud materials will be maintained or readily accessible for the purpose of assuring well control.

EXHIBIT "A"
Proposed Drilling Program
Page 2

4. PROPOSED CASING AND CEMENTING PROGRAM:

- a. Surface casing will be set in the Duchesne River formation to approximately 260' and cemented to surface.
- b. All potentially productive hydrocarbon zones will be isolated.
- c. Casing designs are based on factors of burst: 1.25, collapse: 1.125, and joint strength: 1.8.
- d. All casing strings will be pressure tested to 0.22 psi/ft. of casing string length or 1500 psi whichever is greater (not to exceed 70% of yield).
- E. For details of casing, cement program, drilling fluid program, and proposed mud program, see the following two attachments:

Drilling Program (EXHIBIT "D")
Geologic Prognosis (EXHIBIT "C")

5. HAZARDOUS PRESSURES, TEMPERATURES, FLUIDS/GASSES EXPECTED:

- a. Expected bottom hole temperature is 125 degrees F. Expected bottom hole pressure is 1500 psi.
- b. No abnormal pressures or temperatures have been noted or reported in wells drilled to the Green River formation in this area.
- c. No dangerous levels of hydrogen sulfide, hazardous fluids, or gasses have been found, reported, or known to exist at the depth to be drilled in this well, in this area.

6. ANTICIPATED STARTING DATE AND DURATION OF OPERATIONS:

- a. The drilling operations for this well will begin as soon as the BLM approves all requirements included in this APD.
- b. These drilling operations should be completed within 12 days after spudding the well depending on weather conditions.
- c. If the well is productive, a sundry notice and plat showing exact installed facilities will be submitted.
- d. If this well is non-productive, a sundry notice will be filed with the BLM District Office within 30 days following completion of the well for abandonment.

SURFACE USE PROGRAM

EQUITABLE RESOURCES ENERGY COMPANY
Balcron Oil Division
Balcron Monument Federal #33-6
NW SE Section 6, T9S, R17E
Duchesne County, Utah

In accordance with requirements outlined in 43 CFR 3162.3-1 (d):

1. EXISTING ROADS:

- a. From Myton, Utah, take Highway #40 west out of town 1.6 miles to the Sand Wash road. Go south on the Sand Wash road for 10.4 miles. Turn right onto lease road and go 0.2 miles. Turn left on lease road and go 0.9 miles to tee. Turn right at the tee and go 0.3 miles to the location.
- b. Existing roadways need no improvements for these drilling operations.
- c. All existing roads used by these drilling operations will be maintained in the same or better condition as were existing prior to entry.
- d. See EXHIBIT "J" Maps A and B for access route.

2. PLANNED ACCESS ROADS: See EXHIBIT "J" Maps A & B

- a. Length: Approximately 0.25 miles of new access road will be required.
- b. Width: Maximum 30' overall right-of-way with an 18' running surface.
- c. Maximum grade: 2%
- d. Turnouts: None
- e. Drainage design: This will be a barrow ditch on cut side.
- f. No culverts or bridges will be required. There are no cuts and/or fills on or along the proposed access road route.
- g. Surface materials: Any surface materials which are required will be native materials from the location and/or access site.
- h. No gates, cattleguards, or fence cuts and/or modifications to existing facilities will be required.
- i. Access road route has been centerline-flagged.

- j. All travel will be confined to location and access routes.
- k. All access roads and surface disturbing activities will conform to the standards outlined in the Bureau of Land Management and Forest Service publication: <u>Surface Operating Standards for Oil and Gas Exploration and Development</u>, (1989).

The road shall be constructed/upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. This shall include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well-constructed safe road. If necessary prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Road drainage crossings will be of the typical dry creek draining Crossings, if necessary, will be designed so crossing type. they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means Upgrading will not be done during muddy cutouts. Should mud holes develop, they will be filled in conditions. and detours around them will be avoided.

1. No right-of-way applications are needed for this road.

3. LOCATION OF EXISTING WELLS:

See EXHIBIT "K" Map C.

- a. Water wells: none
- b. Abandoned wells: one
- c. Temporarily abandoned wells: none
- d. Disposal wells: none
- e. Drilling wells: none
- f. Producing wells: twenty one
- g. Shut-in wells: one
 - . Injection wells: none

4. LOCATION OF EXISTING AND/OR PROPOSED PRODUCTION FACILITIES:

- a. Upon completion, a sundry notice and plat showing exact production facilities will be submitted. Production tanks and treaters will be located off of the wellpad and out of the flood plain.
- b. All above-ground facilities will be painted earthtone color Desert Brown #10Y/R in accordance with the Munsell Soil Color chart within six months of the well completion unless prior written approval to proceed with another alternative has been granted via Sundry Notice.

5. LOCATION AND TYPE OF WATER SUPPLY:

- a. The drilling water source will be obtained from a private pond in Pleasant Valley owned by Keith Hickens, Myton, Utah.
- b. The drilling water will be hauled by truck to the location site by Dalbo.

6. CONSTRUCTION ROAD/LOCATION MATERIALS:

- a. Any construction materials which are required will be native materials from the location and/or access site.
- b. Additional construction material needed for erosion control (rip-rap) will be hauled in from an outside source.
- c. Reasonable precautions will be taken to protect all lands.

7. METHODS FOR HANDLING WASTE MATERIALS AND DISPOSAL:

- a. Garbage will be stored in a dumpster and disposed of according to local and state regulations, at an approved facility. Disposal will not be allowed on location. No trash will be disposed of in the reserve pit.
- b. Fluids produced during the completion operation will be collected in test tanks. Any spills of oil, gas, salt water or other noxious fluids will be cleaned up and hauled to an approved disposal site. Burning will not be allowed.
- c. The reserve pit will be lined. Plastic nylon reinforced liner will be torn and perforated before backfilling of the reserve pit.
- d. Saltwater or testing tanks will be located and/or diked so that any spilled fluids will flow into the reserve pit. Saltwater tanks will not be placed on topsoil stockpiles.
- e. Any produced water will be contained on site for a period not to exceed 90 days.
- f. Sewage will be disposed of according to county and state requirements. Sealed chemical portable toilets will be on location during these drilling operations. Waste and chemicals will not be disposed of on location.
- q. Cuttings will be deposited in the reserve pit.

8. ANCILLARY FACILITIES:

None anticipated.

9. LOCATION SITE LAYOUT:

- a. The proposed location site and elevation plat is shown on EXHIBIT "I".
- b. The drill pad layout, showing elevations, orientation, and access to the pad is shown on EXHIBIT "L".
- c. The drilling rig facilities layout is shown on EXHIBIT "G". No permanent living facilities are planned. There will be two or three trailers on location during drilling operations.
- d. The reserve pit and the blooie pit will be constructed as a combination pit capable of holding 12,000 bbls of fluid. The size of the pit will be approximately equivalent to four times the TD hole volume. The blooie pit might be used for testing, but only after the drilling is completed and the drilling equipment and personnel are off the location.
- e. The reserve pit will be located on the NW side of the location. It will be constructed long and narrow for topographic reasons.
- f. Flare pit will be located downwind of the prevailing wind directions at pit corner C a minimum of 100' from the wellhead and 30' from the reserve pit fence.
- g. Stockpiled topsoil (first 6 inches) will be stored on the SW between Corner #2 and Corner #3.
- h. Access to the wellpad will be from the NE between Corner #7 and Corner #8.
- i. Diversion ditch(es) shall be constructed on the SW and NW sides of the location between the reserve pit and existing drainage.
- j. The drainage(s) shall be diverted around the west side around corner A.
- k. All pits will be fenced according to the following minimum standards:
 - a. 39-inch net wire will be used with at least one strand of barbed wire on top of the net wire unless pipe or some type of reinforcement rod is attached to the top of the entire fence.
 - b. The net wire shall be no more than 2 inches above the ground. If barbed wire it shall be 3 inches above the net wire. Total height of fence will be at least 42 inches.
 - c. Corner posts will be cemented and/or braced in such a manner to keep the fence tight at all times. Standard steel, wood, or pipe posts will be used between the corner braces. Maximum distance between any two posts will be no greater than 16'.

d. All wire will be stretched before it is attached to the corner posts.

The reserve pit will be fenced on three sides during drilling operations and on the fourth side when the rig moves off locations. Pits will be fenced and maintained until clean-up.

10. PLANS FOR RECLAMATION OF LOCATION SITE:

The BLM will be contacted prior to commencement of any reclamation operations.

Producing location:

- a. Immediately upon well completion, the location and surrounding areas will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.
- b. Immediately upon well completion, any hydrocarbons in the pit will be removed in accordance with 43 CFR 3162.7-1.
- c. If a plastic nylon reinforced liner is used, it will be torn and perforated before backfilling of the reserve pit.
- d. The reserve pit and that portion of the location not needed for production facilities or operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion. Before any dirt work takes place, the reserve pit will have all fluids and hydrocarbons removed and all trash will be removed.

Dry hole/abandoned location:

At such time as the well is plugged and abandoned, operator will submit a subsequent report of abandonment and BLM will attach the appropriate surface rehabilitation conditions of approval.

11. SURFACE OWNERSHIP:

Bureau of Land Management Vernal District Office 170 South 500 East Vernal, UT 84078

12. OTHER INFORMATION:

- a. See EXHIBIT "F" which is the Archeology Survey.
- b. If unexpected cultural resources are observed during construction or reclamation operations, Equitable Resources Energy Company's Balcron Oil division will suspend operations in the vicinity of the discovery and immediately report the finding to the BLM District Office.

- c. Evidence of bond coverage is included in this report, see EXHIBIT "E".
- d. Operator will have on site a copy of the Surface Use Program and a copy of the supplemental conditions.
- e. Drilling operations will be conducted in accordance with the Bureau of Land Management conditions of approval when received.

13. OPERATOR'S REPRESENTATIVES:

Balcron Oil, a division of Equitable Resources Energy Company 1601 Lewis Avenue P.O. Box 21017 Billings, Montana 59104 (8:00 a.m. to 5:00 p.m.) (406) 259-7860 FAX: (406) 245-1361

Dave McCoskery, Drilling Engineer Home: (406) 248-3864

Mike Perius, Operations Supervisor Home: (406) 656-9719

14. CERTIFICATION:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which presently exist; that any statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Balcron Oil, a division of Equitable Resources Energy Company, and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

June 18, 1992

Bobbie Schuman

Coordinator of Environmental and

Regulatory Affairs

BALCRON OIL division of Equitable

Resources Energy Company

EXPLORATORY____

BALCRON OIL COMPANY

Geologic Prognosis

		3 1100 1							DEVE	-OPHENT	X
WELL HAME:	Federa	a⊥ #33−6 ===~~~	71 - 22 -		. •	PROSPECT.	/FIELD:	Monumer	it Butte		
FOCULTOH:	1034	FSL, 182	7 FEL			SECTION	NMZE 6	TOUNSHIP	95	RANGE	_1ZE_
י ציזאטמט:	Duches	sne	STATE:	_UT	.GL_(Ung)	:5268!	EST KB	5279.'	TOTAL	DEPIH	5580!
ronm. Tops	:		•					•			
	१।.०वै।	10515	Sumple	Top.	Criti Wi	•	Prog	2 2011	'Sample	Τ'ο ρ	Cnll
Formalion	Death	Datum	Depth.	Datum	Datum	Formallo	n Depth	Datum	Deolh	Datum	Dali
KE	_5219				5337_						
ochesne reen River											
uchesne	_Suri.										- ` <u>-</u>
reen kiver	1414	7861-			3837_			,			
lorseshoe Ben Yay #1	1CU7717	1007			3037_						
ay_#1	74174	1981			- TOTY-						
ouglas Creek	7567	821			DUY-	w) () ten tra pa pa au					
Pay.#2 Pay_#3	_4D2L_	<i>D</i>									
ay_#3 ay_#4	· 4824	455			425						
ay_#4 ay_#5	5144	135			105_						
lasatch_Tongu	e_5500_	221			NDE_						
.D	5580										
CONTROL WE	LL: Alle	n Federa	1 #32-6	alr/oli	SWNE	Section	6	ם ורוצרושם ד	9s	Range	17E
				•				•		-	
'shier de .						1.344					
SAMPLÉS:				, ,,		LUGS:					
	الفدي							(i' o ni		' ()	
	' -san	mpiezi		, 10				. (rom		' la '	
	' 51	aples, aples,		1 10				. tran		14. 1.	
	, zan	orales.		1 10						. 10	
	, Rui	uples,		1 10				(IOM)		' (o	
Garage Carrel								from		1 10	
								from		1 10	
							•				
CORESI	•					DRILL ST	CU YCSYG.			•	
None						None					
										4;	•
						~~~~~~					
											•
HUD LOGGER						WELLSITE	6E0L0615	:T:	•		
Required:	(40	(のがくる)	Yes			From		' · la ·			
	One Man					Mame:			Tele. B:	()	
•					•	Address					
COMMENTS:			•			•					
			•								
คนต่องนัยดี ถ	Υ:	Ste	ve W. Var	Delinde	r and		•	DATE: .	5-7-92		
R			en K. Rei					יחובי ,	بروس الله الله الله الله الله الله الله الل		
									-		

# BALCRON OIL - DRILLING PROGRAM

WELL NAME: Balcron Monument Butte PROSPECT/FIELD: Monument Butte

Federal # 33-6

LOCATION: NW SE Sec 6 Twn 9S Rge 17E

COUNTY: Duchesne STATE: Utah

TOTAL DEPTH: 5580'

HOLE SIZE INTERVAL

12 1/4" Surf to 260' 7 7/8" 260' to 5580'

CASING	INTER	VAL 	CA:	CASING								
STRING TYPE	FROM	TO	SIZE	WEIGHT	GRADE							
Surface	0′	260′	8 5/8"	24 #/FT	J-55							
Production	0′	5580′	5 1/2"	15.50#/Ft	J-55							
CEMENT PROGRAM		_	l be ST&C,									
Surface	250 sacks class "G" with 3% CaCl. (Note: Volumes are 100% excess.)											
Production	250 sacks Haliburton Hifill with 10 #/SK Gilsonite tailed with 180 sacks 50/50 Poz with 0.3% CFR-3, 1/4 #/Sk Flocele, 0.5% Halad-24, and 10% salt. (Note: Actual volumes will be calculated from caliper log.)											

## PRELIMINARY

DRILLING FLUID PROGRAM

TYPE	FROM	TO	WEIGHT	PLAS. VIS	YIELD POINT
Fresh Gel/Native Mud	Surf	260	8.5	NA	NA
Fresh Gel (LSND)	260'	5580′	8.7-8.9	10-12	12-14

#### COMMENTS

1.) No cores or DSTs are planned .

DMM 5/14/92



# United States Department of the Interior



BUREAU OF LAND MANAGEMENT MONTANA STATE OFFICE 222 NORTH 32ND STREET P.O. BOX 36800 BILLINGS, MONTANA 59107-6800

IN REPLY TO:

MTM 12619-A et al BLM BOND NO. MT0576 (922.31)

April 25, 1989

#### NOTICE

Equitable Resources Energy Company P. O. Box 21017 Billings, Montana 59104

OIL AND GAS

CORPORATE MERGER RECOGNIZED
RIDER TO NATIONWIDE BOND ACCEPTED

Acceptable evidence has been filed in this office concerning the merger of Balcron Oil Company into Equitable Resources Energy Company, the surviving corporation. Information provided shows that Balcron Oil Company merged into Equitable Resources Energy Company, changing the former entity's name to Balcron Oil, a Division of Equitable Resources Energy Company: Please note that Divisions cannot hold leases, therefore, after consultation with Balcron Oil, this office is recognizing only the merger action.

A rider was filed on April 20, 1989, to be made a part of \$150,000 Nationwide Oil and Gas Bond No. 5547188 (BLM Bond No. MT0576) with Balcron Oil Company as principal and Safeco Insurance Company of America as surety. By means of this rider, the surety consents to changing the name on the bond from Balcron Oil Company to Equitable Resources Energy Company. The rider is accepted effective April 20, 1989.

For our purposes, the merger is recognized effective April 20, 1989.

The oil and gas lease files and communitization agreement files identified on the enclosed Exhibit A have been noted as to the merger. Other lease interests will be transferred by assignments from Ballard & Cronoble to Equitable Resources Energy Company.

Cynthia L. Embretson, Chief Flydds Adjudication Section

1 Enclosure 1-Exhibit Λ

cc: (w/encl.)

AFS, Denver (1)

All DMs (1 ea.)

RMO Section (1)

Regional Forester, Lakewood (2)

Regional Forester, Missoula (2)

Bureau of Reclamation (1)

Form 3104-8 (July 1984)


#### UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

#### STATE, NATIONWIDE, OR NATIONAL PETROLEUM RESERVE IN ALASKA OIL AND GAS BOND

Act of February 25, 1920 (30 U.S.C. Sec. 181) Act of August 7, 1947 (30 U.S.C. Sec. 351)

Department of the Interior Appropriations Act, Fiscal Year 1981 (P.L. 96-514)

Other Oil and Gas Leasing Authorities as Applicable



KNOW ALL MEN BY THESE PRESENTS. That we BALCRON OIL COMPANY

1601 Lewis Avenue, Billings, MT 59104 of

as principal, and

SAFECO INSURANCE COMPANY OF AMERICA

111 Presidential Blvd., Suite 231, Bala Cynwyd, PA

as surety, are held and firmly bound unto the United States of America in the sum of ONE HUNDRED FIFTY THOUSAND AND 00/100-----dollars (\$ 150,000.00 of the United States, which sum may be increased or decreased by a rider hereto executed in the same manner as this bond, for the use and benefit of (1) the United States; (2) the owner of any of the land subject to the coverage of this bond, who has a-

statutory right to compensation in connection with a reservation of the oil and gas deposits to the United States; and (3) any lessee or permittee under a lease or permit issued by the United States prior to the issuance of an oil and gas lease for the same land subject to this bond, covering the use of the surface or the prospecting for, or development of, other mineral deposits in any portion of such land, to be paid to the United States. For such payment, well and truly to be made, we bind ourselves,

and each of our heirs, executors, administrators, and successors, jointly and severally.

The coverage of this bond shall extend to all of the principal's holdings of federal oil and gas	s leases in the United States,
including Alaska, issued or acquired under the Acts cited in Schedule A.	

.The coverage of this bond extends only to the principal's holdings of federal oil and gas leases issued or acquired under the Acts cited and in the States named in Schedule A and to any other State or States that may be named in a rider attached hereto by the lessor with the consent of the surety.

<u></u> :							
]	The coverage of this bond extends only to the principal's h	roldings of	federal	oil and gas	leases	within the	National Petro-
	leum Reserve in Alaska.	•.		•			. •

## SCHEDULE A

Mineral Leasing Act of February 25, 1920 (30 U.S.C. Sec. 181), Acquired Lands Leasing Act of August 7, 1947 (30 U.S.C. Sec. 351), and other oil and gas leasing authorities as applicable.

NAMES OF STATES

ALL STATES

The conditions of the foregoing obligations are such that. whereas the said principal has an interest in oil and gas leases issued under the Acts cited in this bond: (1) as lessee; (2) as the approved holder of operating rights in all or part of the lands covered by such leases under operating agreements with the lessees; or (3) as designated operator or agent under such leases pending approval of an assignment or operating agreement; and

WHEREAS the principal is authorized to drill for, mine, ex-

tract, remove, and dispose of oil and gas deposits in or under the lands covered by the leases, operating agreements or designations and is obligated to comply with certain covenants and agreements set forth in such instruments; and

WHEREAS the principal and surety agree that without notice to the surety the coverage of this bond, in addition to the present holdings of the principal, shall extend to and include:



## SURETY RIDER

SAFECO INSURANCE COMPANY OF AMERICA GENERAL INSURANCE COMPANY OF AMERICA FIRST NATIONAL INSURANCE COMPANY OF AMERICA HOME OFFICE: SAFECO PLAZA SEATTLE, WASHINGTON 98185

To be attached to and f	
. Type of Bond: .	Nationwide Oil and Gas Lease Bond
Bond No.	EE 47100 (PIM Bond No. MT0576)
dated effective	9/8/88
	(MONTH, DAY, YEAR)  BALCRON OIL COMPANY, as Principa
	IDDINCIPALI
in favor of	UNITED STATES DEPARTMENT OF THE INTERIOR, BUREAU OF LAND (OBLIGEE) MANAGEMENT
In consideration of the	mutual agreements herein contained the Principal and the Surety hereby consent to changing
	The name of the Principal
From:	BALCRON OIL COMPANY
To:	EQUITABLE RESOURCES ENERGY COMPANY
	ned shall vary, alter or extend any provision or condition of this bond except as herein expressly stated.
This rider is effective	(MONTH, DAY, YEAR)
Signed and Sealed	4/10/89  (MONTH, DAY, YEAR)  EOUITABLE RESOURCES ENERGY COMPANY  PRINCIPAL
Ву:	SAFFEO INSURANCE COMPANY OF AMERICA
ву:	R. Ceorge Voinghet ATTORNEY-IN-FACT





S CO INSURANCE COMPANY OF AMERICA GENERAL INSURANCE COMPANY OF AMERICA HOME OFFICE: SAFECO PLAZA SEATTLE, WASHINGTON 98185

3798

That SAFECO INSURANCE COMPANY OF AMERICA and GENERAL INSURANCE COMPANY OF AMERICA, each a Washington corporation, does each hereby appoint  THOMAS L. VEHAR; R. GEORGE VOINCHET, Pittsburgh, Pennsylvania.  THOMAS L. VEHAR; R. GEORGE VOINCHET, Pittsburgh, Pennsylvania.  Its true and lawful attorney(s)-in-fact, with full authority to execute on its behalf fidelity and surety bonds or undertakings and other documents of a similar character issued in the course of its business, and to bind the respective company thereby.  IN WITNESS WHEREOF, SAFECO INSURANCE COMPANY OF AMERICA and GENERAL INSURANCE COMPANY OF AMERICA have each executed and attested these presents    Ath	•				NO.			
a Washington corporation, does each hereby appoint	KNOW ALL BY THESE PRESENTS:							
its true and lawful attorney(s)-in-fact, with full authority to execute on its behalf fidelity and surety bonds or undertakings and other documents of a similar character issued in the course of its business, and to bind the respective company thereby.  IN WITNESS WHEREOF, SAFECO INSURANCE COMPANY OF AMERICA and GENERAL INSURANCE COMPANY OF AMERICA have each executed and attested these presents  this 4th day of September 1, 19 87.  CERTIFICATE  Extract from the By-Laws of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA.  "Article V, Section 13.— FIDELITY AND SURETY BONDS the President, any Vice President, the Secretary, and any Assistant Vice President appointed for that purpose by the officer in charge of surety operations, shall each have authority to appoint individuals as attorneys-in-fact or under other appropriate titles with authority to execute on behalf of the company fidelity and surety bonds and other documents of similar character issued by the company in the course of its business On any instrument making or evidencing such appointment, the signatures may be affixed by facsimile. On any instrument conferring such authority or on any bond or undertaking of the company, the seal, or a facsimile thereof, may be impressed or affixed or in any other manner reproduced; provided, however, that the seal shall not be necessary to the validity of any such instrument or undertaking.  Extract from a Resolution of the Board of Directors of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA adopted July 28, 1970.  "On any certificate executed by the Secretary or an assistant secretary of the Company setting out, (i) The provisions of Article V, Section 13 of the By-Laws, and (iii) Certifying that said power-of-attorney appointment, executed pursuant thereto, and (iii) Certifying that said power-of-attorney appointment, executed pursuant thereto, and of GENERAL INSURANCE COMPANY OF AMERICA, do hereby certify that the foregoing extracts of the By	That SAFECO INSURANCE COMPANY OF All a Washington corporation, does each hereby app	MERICA point	and GENERA	AL INSUR	ANCE	COMPANY C	F AMERICA,	each.
IN WITNESS WHEREOF, SAFECO INSURANCE COMPANY OF AMERICA and GENERAL INSURANCE COMPANY OF AMERICA have each executed and attested these presents  this 4th day of September , 19 87,  CERTIFICATE  Extract from the By-Laws of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA:  "Article V, Section 13. — FIDELITY AND SURETY BONDS the President, any Vice President, the Secretary, and any Assistant Vice President appointed for that purpose by the officer in charge of surety operations, shall each have authority to appoint individuals as attorneys-in-fact or under other appropriate titles with authority to execute on behalf of the company fidelity and surety bonds and other documents of similar character issued by the company in the course of its business On any instrument making or evidencing such appointment, the signatures may affixed by facisinile. On any instrument conferring such authority or on any bond or undertaking of the company, the seal, or a facisimile thereof, may be impressed or affixed or in any other manner reproduced; provided, however, that the seal shall not be necessary to the validity of any such instrument or undertaking.  Extract from a Resolution of the Board of Directors of SAFECO INSURANCE COMPANY OF AMERICA adopted July 28, 1970.  "On any certificate executed by the Secretary or an assistant secretary of the Company setting out,  (ii) The provisions of Article V, Section 13 of the By-Laws, and  (iii) Certifying that said power-of-attorney appointment is in full force and effect,  the signature of the certifying officer may be by facsimile, and the seal of the Company may be a facsimile thereof."  I, Boh A. Dickey, Secretary of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA, do hereby certify that the foregoing extracts of the By-Laws and of a Resolution of the Board of Directors of these corporations, and of a Power of Attorney are still in full force and effect.  IN WITNESS WHERE	THOMAS L. VEHAR; R. GE	CORGE V	OINCHET,	Pittsbu	rgh, P	'ennsylvar	i1a	
CERTIFICATE  Extract from the By-Laws of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA:  "Article V, Section 13. — FIDELITY AND SURETY BONDS the President, any Vice President, the Secretary, and any Assistant Vice President appointed for that purpose by the officer in charge of surety operations, shall each have authority to appoint individuals as attorneys-in-fact or under other appropriate titles with authority to execute on behalf of the company fidelity and surety bonds and other documents of similar character issued by the company in the course of its business On any instrument making or evidencing such appointment, the signatures may be affixed by facsimile. On any instrument conferring such authority or on any bond or undertaking of the company, the seal, or a facsimile thereof, may be impressed or affixed or in any other manner reproduced; provided, however, that the seal shall not be necessary to the validity of any such instrument or undertaking."  Extract from a Resolution of the Board of Directors of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA adopted July 28, 1970.  "On any certificate executed by the Secretary or an assistant secretary of the Company setting out,  (ii) A copy of the power-of-attorney appointment, executed pursuant thereto, and  (iii) Certifying that said power-of-attorney appointment is in full force and effect, the signature of the certifying officer may be by facsimile, and the seal of the Company may be a facsimile thereof."  I, Boh A. Dickey, Secretary of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA, do hereby certify that the foregoing extracts of the By-Laws and of a Resolution of the Board of Directors of these corporations, and of a Power of Attorney issued pursuant thereto, are true and correct, and that both the By-Laws, the Resolution and the Power of Attorney are still in full force and effect.	its true and lawful attorney(s)-in-fact, with full a and other documents of a similar character issued	uthority to d in the co	o execute on ourse of its bu	its behalf siness, an	fidelity a d to bind	nd surety boi the respectiv	nds or underta e company the	kings ereby.
Extract from the By-Laws of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA:  "Article V, Section 13. — FIDELITY AND SURETY BONDS the President, any Vice President, the Secretary, and any Assistant Vice President appointed for that purpose by the officer in charge of surety operations, shall each have authority to appoint individuals as attorneys-in-fact or under other appropriate titles with authority to execute on behalf of the company fidelity and surety bonds and other documents of similar character issued by the company in the course of its business On any instrument making or evidencing such appointment, the signatures may be affixed by facsimile. On any instrument conferring such authority or on any bond or undertaking of the company, the seal, or a facsimile thereof, may be impressed or affixed or in any other manner reproduced; provided, however, that the seal shall not be necessary to the validity of any such instrument or undertaking."  Extract from a Resolution of the Board of Directors of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA adopted July 28, 1970.  "On any certificate executed by the Secretary or an assistant secretary of the Company setting out,  (i) The provisions of Article V, Section 13 of the By-Laws, and  (ii) A copy of the power-of-attorney appointment, executed pursuant thereto, and  (iii) Certifying that said power-of-attorney appointment is in full force and effect,  Ithe signature of the certifying officer may be by facsimile, and the seal of the Company may be a facsimile thereof."  I, Boh A, Dickey, Secretary of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA, do hereby certify that the foregoing extracts of the By-Laws and of a Resolution of the Board of Directors of these corporations, and of a Power of Attorney issued pursuant thereto, are true and correct, and that both the By-Laws, the Resolution and the Power of Attorney are still in full force and effect.	IN WITNESS WHEREOF, SAFECO INSURANO OF AMERICA have each executed and attested	CE COMI these pre	PANY OF AM	IERICA a	nd GENI	ERAL INSU _, R	ANCE COMP	YNA
Extract from the By-Laws of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA:  "Article V, Section 13. — FIDELITY AND SURETY BONDS the President, any Vice President, the Secretary, and any Assistant Vice President appointed for that purpose by the officer in charge of surety operations, shall each have authority to appoint individuals as attorneys-in-fact or under other appropriate titles with authority to execute on behalf of the company fidelity and surety bonds and other documents of similar character issued by the company in the course of its business On any instrument making or evidencing such appointment, the signatures may be affixed by facsimile. On any instrument or such authority or on any bond or undertaking of the company, the seal, or a facsimile thereof, may be impressed or affixed or in any other manner reproduced; provided, however, that the seal shall not be necessary to the validity of any such instrument or undertaking."  Extract from a Resolution of the Board of Directors of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA adopted July 28, 1970.  "On any certificate executed by the Secretary or an assistant secretary of the Company setting out,  (i) The provisions of Article V, Section 13 of the By-Laws, and  (ii) A copy of the power-of-attorney appointment, executed pursuant thereto, and  (iii) Certifying that said power-of-attorney appointment, executed pursuant thereto, and  (iii) Certifying that said power-of-attorney appointment is in full force and effect,  the signature of the certifying officer may be by facsimile, and the seal of the Company may be a facsimile thereof."  I, Boh A. Dickey, Secretary of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA, do hereby certify that the foregoing extracts of the By-Laws and of a Resolution of the Board of Directors of these corporations, and of a Power of Attorney issued pursuant thereto, are true and correct, and that both the By-Laws, the Reso	this	4th		day of	Septe	ember	, 19_	<u>87</u>
"Article V, Section 13. — FIDELITY AND SURETY BONDS the President, any Vice President, the Secretary, and any Assistant Vice President appointed for that purpose by the officer in charge of surety operations, shall each have authority to appoint individuals as attorneys-in-fact or under other appropriate titles with authority to execute on behalf of the company fidelity and surety bonds and other documents of similar character issued by the company in the course of its business On any instrument making or evidencing such appointment, the signatures may be affixed by facsimile. On any instrument conferring such authority or on any bond or undertaking of the company, the seal, or a facsimile thereof, may be impressed or affixed or in any other manner reproduced; provided, however, that the seal shall not be necessary to the validity of any such instrument or undertaking."  Extract from a Resolution of the Board of Directors of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA adopted July 28, 1970.  "On any certificate executed by the Secretary or an assistant secretary of the Company setting out,  (i) The provisions of Article V, Section 13 of the By-Laws, and  (ii) A copy of the power-of-attorney appointment, executed pursuant thereto, and  (iii) Certifying that said power-of-attorney appointment is in full force and effect, the signature of the certifying officer may be by facsimile, and the seal of the Company may be a facsimile thereof."  I, Boh A. Dickey, Secretary of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA, do hereby certify that the foregoing extracts of the By-Laws and of a Resolution of the Board of Directors of these corporations, and of a Power of Attorney issued pursuant thereto, are true and correct, and that both the By-Laws, the Resolution and the Power of Attorney are still in full force and effect.		CE	RTIFICATE					
Assistant Vice President appointed for that purpose by the officer in charge of surety operations, shall each rave authority to appoint individuals as attorneys-in-fact or under other appropriate titles with authority to execute on behalf of the company fidelity and surety bonds and other documents of similar character issued by the company in the course of its business On any instrument making or evidencing such appointment, the signatures may be affixed by facsimile. On any instrument conferring such authority or on any bond or undertaking of the company, the seal, or a facsimile thereof, may be impressed or affixed or in any other manner reproduced; provided, however, that the seal shall not be necessary to the validity of any such instrument or undertaking."  Extract from a Resolution of the Board of Directors of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA adopted July 28, 1970.  "On any certificate executed by the Secretary or an assistant secretary of the Company setting out,  (ii) The provisions of Article V, Section 13 of the By-Laws, and  (iii) A copy of the power-of-attorney appointment, executed pursuant thereto, and  (iii) Certifying that said power-of-attorney appointment is in full force and effect, the signature of the certifying officer may be by facsimile, and the seal of the Company may be a facsimile thereof."  I, Boh A. Dickey, Secretary of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA, do hereby certify that the foregoing extracts of the By-Laws and of a Resolution of the Board of Directors of these corporations, and of a Power of Attorney issued pursuant thereto, are true and correct, and that both the By-Laws, the Resolution and the Power of Attorney are still in full force and effect.  IN WITNESS WHEREOF, I have hereunto set my hand and affixed the facsimile seal of said corporation	Extract from the By-Laws o and of GENERAL	SAFEC	O INSURAN	CE COMP	ANY O	F AMERICA CA:		
"On any certificate executed by the Secretary or an assistant secretary of the Company setting out,  (i) The provisions of Article V, Section 13 of the By-Laws, and  (ii) A copy of the power-of-attorney appointment, executed pursuant thereto, and  (iii) Certifying that said power-of-attorney appointment is in full force and effect, the signature of the certifying officer may be by facsimile, and the seal of the Company may be a facsimile thereof."  I, Boh A. Dickey, Secretary of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA, do hereby certify that the foregoing extracts of the By-Laws and of a Resolution of the Board of Directors of these corporations, and of a Power of Attorney issued pursuant thereto, are true and correct, and that both the By-Laws, the Resolution and the Power of Attorney are still in full force and effect.  IN WITNESS WHEREOF, I have hereunto set my hand and affixed the facsimile seal of said corporation	Assistant Vice President appointed for that purp to appoint individuals as attorneys-in-fact or a company fidelity and surety bonds and other d business On any instrument making or evide instrument conferring such authority or on any l impressed or affixed or in any other manner of validity of any such instrument or undertaking.	oose by thunder oth ocuments ncing such or ure produced.	e officer in cher appropriate of similar chappointmen adertaking of the provided, h	arge of su e titles w haracter is at, the sign the compa owever, th	irety ope ith auth ssued by actures n any, the s hat the s	rations, shall ority to exect the company hay be affixed seal, or a facsional shall not	te on behalf in the course by facsimile. ( mile thereof, rebe necessary	of the of its On any
<ul> <li>(i) The provisions of Article V, Section 13 of the By-Laws, and</li> <li>(ii) A copy of the power-of-attorney appointment, executed pursuant thereto, and</li> <li>(iii) Certifying that said power-of-attorney appointment is in full force and effect,</li> <li>the signature of the certifying officer may be by facsimile, and the seal of the Company may be a facsimile thereof."</li> <li>I, Boh A. Dickey, Secretary of SAFECO INSURANCE COMPANY OF AMERICA and of GENERAL INSURANCE COMPANY OF AMERICA, do hereby certify that the foregoing extracts of the By-Laws and of a Resolution of the Board of Directors of these corporations, and of a Power of Attorney issued pursuant thereto, are true and correct, and that both the By-Laws, the Resolution and the Power of Attorney are still in full force and effect.</li> <li>IN WITNESS WHEREOF, I have hereunto set my hand and affixed the facsimile seal of said corporation</li> </ul>	Extract from a Resolution of the Board of GENERAL INSURAL	of Directo NCE CON	rs of SAFECO	O INSURA MERICA	ANCE C adopted	OMPANY O July 28, 197	F AMERICA O.	
COMPANY OF AMERICA, do hereby certify that the foregoing extracts of the By-Laws and of a Resolution of the Board of Directors of these corporations, and of a Power of Attorney issued pursuant thereto, are true and correct, and that both the By-Laws, the Resolution and the Power of Attorney are still in full force and effect.  IN WITNESS WHEREOF, I have hereunto set my hand and affixed the facsimile seal of said corporation	(i) The provisions of Article V, Section 1 (ii) A copy of the power-of-attorney appo (iii) Certifying that said power-of-attorney the signature of the certifying officer may be by	3 of the B intment, of y appointry y facsimile	y-Laws, and executed pursment is in full e, and the sea	suant ther force and I of the Co	eto, and effect, ompany i	may be a facs		
	COMPANY OF AMERICA, do hereby certify the Directors of these corporations, and of a Power	hat the for of Attorn	regoing extrac ey issued pur	its of the E suant the	By-Laws reto, are	and of a Reso	inflou of the p	oard or
this <u>lOth</u> day of <u>April</u> , 19 <u>89</u> .	IN WITNESS WHEREOF, I have hereunto set	my hand	and affixed th	ne facsimil	le seal o	f said corpora	tion	
	•	this	10th_	da	y of	April	, 19	<u>৪9</u>



# ARCHEOLOGICAL - ENVIRONMENTAL RESEARCH CORPORATION

P. O. Box 853 Bountiful, Utah 84011-0853 Tel: (801) 292-7061, 292-9668

May 26, 1992

Subject:

CULTURAL RESOURCE EVALUATIONS OF FOUR PROPOSED

WELL LOCATIONS IN THE CASTLE PEAK DRAW LOCALITY

OF DUCHESNE COUNTY, UTAH

Project:

BALCRON OIL CO. -- 1992 Development

Program for Units 11-6, 24-6, 33-6, and 42-6

Project No.:

BLCR-92-2

Permit No.:

Dept. of Interior -- UT-92-54937

Utah State Project No.: UT-92-AF- 228 b

To:

Ms. Bobbie Schuman, Balcron Oil Co., P.O. Box 21017,

Billings Montana 59104

Mr. David Little, District Manager, Bureau of Land

Management, 170 South 500 East, Vernal, Utah 84078

Info:

Antiquities Section, Division of State History, 300 Rio

Grande, Salt Lake City, Utah 84101

CULTURAL RESOURCE EVALUATIONS

OF FOUR PROPOSED WELL LOCATIONS

(UNITS 11-6, 24-6, 33-6, and 42-6)

IN THE CASTLE PEAK DRAW LOCALITY OF

DUCHESNE COUNTY, UTAH

REPORT PREPARED FOR BALCRON OIL COMPANY

Dept. of Interior Permit No.: UT-92-54937 Utah State Project No.: UT-92-AF-228b AERC PROJECT 1324 (BLCR-92-2)

Principal Investigator & Author of Report F. Richard Hauck, Ph.D.



Report Prepared by the

ARCHEOLOGICAL-ENVIRONMENTAL RESEARCH

CORPORATION (AERC)

P.O. Box 853
Bountiful, Utah 84011-0853

May 26, 1992

#### ABSTRACT

Intensive cultural resource evaluations have been conducted for Balcron Oil Company on the proposed Federal Well locations 11-6, 24-6, 33-6, and 42-6 in the Castle Peak Draw locality of Duchesne County, Utah. This series of well locations involved 10 acre survey areas. Access route corridors were also evaluated measuring ca. 30 meters in width for a total of ca. .87 mile in length. Thus, ca. 50.5 acres of public lands in the locality were examined by R. Beaty of AERC on May 21 and 22, 1992.

One significant cultural resource activity locus was identified and recorded during the examination. This site has been designated as 42DC 732 (AERC 1324B/1) and consists of an open occupation which can be avoided by realigning the access route into Unit 11-6.

One non-diagnostic isolated biface fragment of Tiger Chert was observed in the vicinity of Unit 24-6 but not collected.

The variety of known sites in Section 6 including 42DC 349, 42DC 350, 42DC 351, 42DC 352, AND 42DC 353 will be avoided by the proposed developments. No previously recorded significant or National Register eligible cultural resources will be adversely affected by the proposed developments.

AERC recommends cultural resource clearance with the stipulation that the access route into Unit 11-6 should be moved to the south in order to avoid any disturbance to Site 42DC 732.

## TABLE OF CONTENTS

	page	
Abstract	i	ii
Table of Contents	i	11:
List of Maps of the Project Area	i	Lv
General Information	1	l
Project Location	1	1
Environmental Description		3
Previous Research in the Locality	у	3
File Search		3
Prehistory and History of th	he Cultural Region	3
Site Potential in the Projec	ct Development Zone	1
Field Evaluations		4
Methodology		ŧ
Site Significance Criteria		5
Results of Inventory .		5
Conclusion and Recommendations		7
Dadawanaa	S	Q

## LIST OF MAPS OF THE PROJECT AREA

MAP:	Cultural Resource Survey of				p	age
	Four Proposed Well Locations in the					
	Castle Peak Draw Locality, Duchesne Count	y,	Utah	•	•	2

#### GENERAL INFORMATION

On May 21 and 22, 1992, AERC archaeologist Richard Beaty, M.A. conducted intensive cultural resource evaluations for Balcron Oil Company of Billings, Montana. These examinations involved four proposed well units (Federal Units 11-6, 24-6, 33-6, and 42-6) in the Castle Peak Draw locality of Duchesne County, Utah (see Map).

This project is situated on federal lands administered by the Split Mountain Resource Area of the Vernal District of the Bureau of Land Management.

The purpose of the field study and this report is to identify and document cultural site presence and assess National Register significance relative to established criteria (cf., 36 CFR 60.6). assessments regulations require archeological potentially endangered cultural resources in order to identify and preserve significant artifacts and cultural material, strata, features, or monuments that are susceptible to disturbance being situated in the immediate development zone. These excavations and site assessments were conducted in compliance with the Antiquities Act of 1906; the Historic Sites Act of 1935; Section 106 of the National Historic Preservation Act of 1966, as amended; the National Environmental Policy Act of 1969; the Federal Land Policy and Management Act of 1979; the Archaeological Resources Protection Act of 1979; the Native American Religious Freedom Act of 1978; the Historic Preservation Act of 1980; and Executive Order 11593.


#### Project Location


<u>Unit 11-6</u>: This location is in the NW 1/4 of the NW 1/4 of Section 6 of Township 9 South, Range 17 East. The location is associated with an  $800^{\circ}$  access route leading from the existing roadway to the east of the location.

Unit 24-6: This location is in the SE 1/4 of the SW 1/4 of Section 6 of Township 9 South, Range 17 East. The location is associated with a 2100'access route that approaches from the north as shown on the map.

<u>Unit 33-6</u>: This location is in the NW 1/4 of the SE 1/4 of Section 6 of Township 9 South, Range 17 East. The location is associated with a short access route (800') that approaches from an existing well location to the east.

Unit 42-6: This location is in the SE 1/4 of the NE 1/4 of Section 6 of Township 9 South, Range 17 East. The location is associated with a 900' access route that approaches from an existing well location to the west of Unit 42-6.





Project: Scale: 1:24000
BLCR-92-2

Series:
Uinta Basin
6-26-92

Access
Route
(original)

Cultural
Site
Isolated
Artifact

Legend:

10 Acre

Well Center A

#### Environmental Description

The project area is situated within the 5250 to 5400 foot elevation zone above sea level. Open rangeland and shallow canyon/arroyo terrain surfaces are associated with all these locations.

The vegetation in the project area includes <u>Chrysothamnus</u> spp., <u>Ephedra viridis</u>, <u>Atriplex canescens</u>, <u>Artemesia tridentata</u>, <u>Opuntia polyacantha</u>, <u>Sarcobatus vermiculatus</u>, and <u>Bromus tectorum</u>.

The geological associations within the project area consist of fluvial lake deposits which correlate with the Uinta Formation which is of Tertiary age.

PREVIOUS RESEARCH IN THE LOCALITY

#### File Search

Records searches of the site files and maps at the Antiquities Section of the State Historic Preservation Office in Salt Lake City were conducted on May 26, 1992. A similar search was conducted in the Vernal District Office of the BLM on May 20. The National Register of Historic Places has been consulted and no registered historic or prehistoric properties will be affected by the proposed developments.

A few known cultural sites are situated in the Castle Peak Draw locality. Most of these prehistoric resources including Sites 42DC 349. 42DC 350, 42DC 351, 42DC 352, and 42DC 353 were identified and recorded during various archaeological inventories conducted by AERC in 1981 (Hauck 1981).

## Prehistory and History of the Cultural Region

Currently available information indicates that the Northern Colorado Plateau Cultural Region has been occupied by a variety of cultures beginning perhaps as early as 10,000 B.C. These cultures, as identified by their material remains, demonstrate a cultural developmental process that begins with the earliest identified Paleoindian peoples (10,000 - 7,000 B.C.) and extends through the Archaic (ca. 7,000 B.C. - A.D. 300), and Formative (ca. A.D. 400 - 1100 ) Stages, and the Late Prehistoric-Protohistoric periods (ca. A.D. 1200 - 1850) to conclude in the Historic-Modern period which was initiated with the incursion of the Euro-American trappers, explorers, and settlers. Basically, each cultural stage - with the exception of the Late Prehistoric hunting and gathering Shoshonean bands - features a more complex life-way and social order than occurred during the earlier stage of development (Hauck 1991:53).

For a more comprehensive treatment of the prehistory and history of this region see <u>Archaeological Evaluations in the Northern Colorado Plateau Cultural Area</u> (Hauck 1991).

## Site Potential in the Project Development Zone:

Previous archaeological evaluations in the general project area have resulted in the identification and recording of a variety of cultural resource sites having eligibility for potential nomination to the National Register of Historic Places (NRHP). The majority of these sites are lithic scatters including Sites 42DC 349, 42DC 350, and 42DC 353. Open occupations have also been identified in this locality (42DC 352). Site 42DC 351 is a rock shelter. Site 42DC 353 apparently has a Paleoindian component based on the recovery of a Folsom point from that site. Sites in this locality generally appear to have been occupied during the Archaic Stage and the Late Prehistoric Period (Numa) with occasional indications of Paleoindian activity based on the recovery of isolated Folsom and Plano style projectile points.

The site density of this locality appears to range from six to above ten sites per square mile which is a moderate to high density for this region (see Hauck 1991:45-54 for comparable site density associations in other localities on the Northern Colorado Plateau).

#### FIELD EVALUATIONS

#### Methodology

Intensive evaluations consisted of the archaeologist walking 10 to 20 meter wide transects within the well location areas and along the proposed access corridors. This series of well locations involved 10 acre survey areas. Access route corridors were evaluated measuring ca. 30 meters in width for a total of ca. .87 mile in length. Thus, ca. 50.5 acres of public lands in the locality were examined by R. Beaty of AERC on May 21 and 22, 1992.

Observation of cultural materials results in intensive examinations to determine the nature of the resource (isolate or activity locus). The analysis of each specific cultural site involves its subsequently being sketched, photographed, and appropriately recorded on standard IMACS forms. The determination of site significance is also established during the examination and evaluation of the cultural resources.

#### Site Significance Criteria

Prehistoric and historic cultural sites which can be considered as eligible for nomination to the National Register of Historic Places have been outlined as follows in the National Register's Criteria for Evaluation as established in Title 36 CFR 60.6:

The quality of significance in American ... archaeology ... and culture is present in ... sites ... that possess integrity of location, design, setting, materials, workmanship, feeling, and association and:

- a. That are associated with events that have made a significant contribution to the broad patterns of our history; or
- b. that are associated with the lives of persons significant in our past; or
- c. that embody the distinctive characteristics of a type, period, or method of construction ...; or
- d. that have yielded, or may be likely to yield, information important in prehistory or history.

In addition to satisfying one or more of these general conditions, a significant cultural resource site in Utah will generally be considered as being eligible for inclusion in the National Register if it should advance our current state of knowledge relating to chronology, cultural relationships, origins, and cultural life ways of prehistoric or historic groups in the area.

In a final review of any site's cultural significance, the site must possess integrity and at least one of the above criteria to be considered eligible for nomination to the National Record of Historic Places.

#### Results of the Inventory

One newly identified prehistoric cultural resource activity loci was observed and recorded during these archaeological evaluations. This site has been designated as 42DC 732 (AERC 1324B/1) and consists of an extensive lithic scatter and open occupation containing several deflated hearths. The site is ca. 30 x 40 meters in size and contains a variety of lithic material with the siltstone from the Parachute Creek Member of the Green River Formation being most dominant on the site. The site offers two separate units in association with an ephemeral drainage channel

and a low stabilized dune complex. Several scrapers were observed on the site as was a ground stone tool. No artifacts were collected from this site.

Site 42DC 732 meets the requirements of criterion d of Title 36 CFR 60.6 in that it contains the potential for providing pertinent information and materials relative to the prehistory of the locality and region. In addition, this site has contextual integrity.

The original access route into Unit 11-6 passes along the southern periphery of this site (see Map). In order to avoid any disturbance to this significant resource, AERC recommends that a new access road be planned that will be ca. 100 to 200 feet to the south of the original access route as shown on Map.

No previously recorded cultural sites will be adversely affected by the proposed developments.

One isolated artifact was observed during the evaluations. This artifact consists of a biface fragment of Tiger Chert that was observed in the vicinity of Unit 24-6. This isolate was not collected.

#### CONCLUSION AND RECOMMENDATIONS:

AERC recommends that a cultural resource clearance be granted to Balcron Oil Company relative to the development of the proposed units as noted above based upon adherence to the following stipulations:

- 1. In order to avoid any disturbance to Site 42DC 732, AERC recommends that a new access road into Unit 11-6 be developed that will pass ca. 100 to 200 feet to the south of the original access route as shown on Map.
- 2. All vehicular traffic, personnel movement, construction and restoration operations should be confined to the flagged areas and corridors examined as referenced in this report, and to the existing roadways and/or evaluated access routes.
- 3. All personnel should refrain from collecting artifacts and from disturbing any significant cultural resources in the area.
- 4. The authorized official should be consulted should cultural remains from subsurface deposits be exposed during construction work or if the need arises to relocate or otherwise alter the location of the exploration area.

F. Richard Hauck, Ph.D. President and Principal

Investigator

#### REFERENCES

#### Hauck, F. Richard

- 1981 CULTURAL RESOURCE INVENTORY OF NINE PROPOSED WELL LOCATIONS AND ACCESS ROADS IN THE COYOTE BASIN LOCALITY OF UINTAH COUNTY, UTAH AND IN THE CASTLE PEAK DRAW LOCALITY OF DUCHESNE COUNTY, UTAH. AERC Report prepared for Diamond Shamrock Exploration (DS-81-2), Bountiful.
- 1991 ARCHAEOLOGICAL EVALUATIONS ON THE NORTHERN COLORADO PLATEAU CULTURAL AREA, <u>AERC PAPER No. 45</u>, Archeological-Environmental Research Corporation, Bountiful.

Department of t Bureau of Land Management Utah State Office (AERC FORMAT)

Summary Report of Inspection for Cultural Resources |

Report Acceptable Yes __ No __

Mitigation Acceptable Yes __ No __ Comments:

C	A	S	Т	Ī.	E	P	E	A	K	D	R	Α	W	L	0	C	Α	Т	Ι	0	N	S
U	n		-		u		ш	**	41	D	•	21	•••		•	•	••	-		_	••	~

BALCRON OIL CO. UNITS 11-6, 24-6, 33-6, AND 42-6

2. Development Company UT-92-54937 5 26 1 9 9 2

4. Antiquities Permit No. 3. Report Date

A E R C B L C R - 9 2 - 2

6. Fieldwork

Location: TWN . . . . RNG . . . . . 

Resource TWN . . . . . RNG . . . . . Section. . . | . . . | . . . | <u>Area</u>

.S.M. 

8. Description of Examination Procedures: The archeologist, Richard Beaty, intensively examined these proposed locations and access corridors by walking a series of 10 to 20 meter-wide transects within the well parcels and flanking the flagged centerlines. This series of well locations involved 10 acre survey parcels on all four locations.

1 . 4 2 . . . . . . <u>10. Inventory Type</u> . .

9. Linear Miles Surveyed and/or

Definable Acres Surveyed

and/or

Legally Undefinable

Acres Surveyed

R = Reconnaissance

I = Intensive

S = Statistical Sample

11. Description of Findings:

12. Number Sites Found .1. . . . . One cultural resource site was identified (No sites = 0) during the survey. No isolated artifacts 13. Collection: Y. were observed, recorded, or collected. (Y = Yes, N = No)

This site (42DC 732) consists of an (continued on page 2)

14. Actual/Potential National Register Properties Affected:

The National Register of Historic Places (NRHP) has been consulted and no registered properties will be affected by the proposed development.

15. Literature Search, Location/ Date: Utah SHPO 5-26-92

Vernal District Office Records 5-20-92

16. Conclusion/ Recommendations:

AERC recommends that a cultural resource clearance be granted to Balcron Oil Company for these proposed developments based on the following stipulations: (see page 2).

17. Signature of Administrator & Field Supervisor

Administrator

UT 8100-3 (2/85) Supervisor

#### 11. continued:

open occupation and lithic scatter that is adjacent to the original access route into Unit 11-6. The access route was subsequently moved in order to avoid any disturbance to this significant resource.


#### 16. continued:

- 1. All vehicular traffic, personnel movement, construction and restoration operations should be confined to the corridors examined as referenced in this report, and to the existing roadways and/or evaluated access routes.
- 2. All personnel should refrain from collecting artifacts and from disturbing any significant cultural resources in the area.
- 3. The authorized official should be consulted should cultural remains from subsurface deposits be exposed during construction work or if the need arises to relocate or otherwise alter the location of the exploration area.
- 4. The original access route into Unit 11-6 should be shifted to the south into the corridor shown on map in order to avoid Site 42DC 732.

#### ROTARY DRILLING W. I MUD & AIR SINCE 1966



Main Office 1910 N. Loop Ave. P.O. Box 2440 Casper, Wyoming 82602 (307) 235-8609 Billings Office 2047 E. Maln Billings, Montana 59103 (406) 245-3511 Havre, Montana Yard 4 mi. W. Hwy 2




9" Bore - 2000 PSI Blowout Preventer Stack


## **ROTARY DRILLING WITH MUD & AIR SINCE 1966**



Main Office 1910 N. Loop Ave. P.O. Box 2440 Casper, Wyoming 82602 (307) 235-8609 Billings Office 2047 E. Main Billings, Montana 59103 (406) 245-3511

Havre, Montana Yard 4 mi. W. Hwy 2





9" Bore-1000 PSI Blowout Preventer Stack








EXHIBIT "G'









		TE OF UTAH -				
	DIVISION OF C	OIL, GAS AND N	MINING	<b></b>	5. Lease Designation a	al Sadal Na
					ed. #U-02025	
APPLICATION I	OR PERMIT TO	O DRILL, DEE	PEN, OR PLUG E	3ACK	o. Il Indian, Allocted	or tring Name
. Type of Work	œ				7. Unit Agreement Nar	
DRILL . Type of Well		DEEPEN	PLUG BA	ck 🗌		
Oil Gas Well Well	Other		Single X Mult Zone Zone		s. Farm or Lease Nun	ne
Name of Operator			20114 — 20114		Balcron Monum	nent Feder
BALCRON OIL				[ ·	. Well No.	
Address of Operator					33-6	
P.O. Box 21017 Location of Well (Report	<u>; Billings, M</u>	T 59104			10. Field and Pool, or	
At surres			nte requirements.*)		Monument Buti	
1	832' FSL, 1829	' FEL			<ol> <li>QQ, Sec., T., R., M. and Survey or Area</li> </ol>	, er six.
At proposed prod. zone				/		
. Distance in miles and dir	ection from neurest town	or nor office!			NW SE Sec.	
	east of Myton			i_		
. Distance from proposed			No. of acres in lease		ouchesne assigned	UTAH
location to nearest property or lease line, ft.	•	•••	and be noted in tenant	to this		
(Also to nearest drig. line Distance from proposed in	. if any)	19	Proposed depth	20 Passess	or cable tools	
to nearest well, drilling, or applied for, on this lea	completed.	<b>,</b> ,,,				
Elevations (Show whether		<del></del>	5,580' WSTC	KUI	22. Approx. date wor	ek will starts
GL 5,267.7'					8-21-9	_
uL 3,207.7					0-21-1	~
	r	ROPUSED CASING A	ND CEMENTING PROGRAM	/( 		
Size of Hole	Size of Casing	Weight per Foot	Setting Depth		Quantity of Cemer	
12-1/4"	8-5/8"	24#	260'		250 sx "G'	
7-7/8"	5-1/2"	15.5#	5,580	·····	See EXHIBIT	"D"
			ordance with the			
			of the permit w	ill be s	sent to the S	State
of Utah, Divis	ion of Oil, Ga	is and Mining	•			
	•				E CIRTY	នាកា
<b>( )</b>	ONFIC			()	Dame II	
U i	JINHII	) レハー	Λ:	13 500		70
		LIVII	[4]		JUN 1 9 199	2
			/ IL			
			•		DIVISION OF	
						•
				\.#(	II. GAS & MINII	NG
ABOVE SPACE DESCRI ctive zone. If proposal is eventer program, if any.	BE PROPOSED PROGR. to drill or deepen directi	AM: If proposal is to conally, give pertinent o	deepen or plug back, give didata on subsurface locations	nta on presen and measured	t productive zone and d and true vertical de	proposed new propo
I hereby certify that	this report is true and	complete to the best	of my knowledge. Coordinator of Er	winonno	ntal	
Signed Doblie	Dchuman		.oordinator of Er -and-Regulatory-/		•	ne 18, 1992
Bobbie	Schuman	41116	and regulatory /			
fama sluce for telletal of	r State office use)	. 1				HE STAT
API HO. 13-	<u> 013-313U</u>	<u> </u>	Approval Date	O۶	UTAH DIVI	SION OF

*See Instructions On Reverse Side

Revised & substitute 19/92

EXHIBIT "B"
Surface Use Program
Page 1

### SURFACE USE PROGRAM

EQUITABLE RESOURCES ENERGY COMPANY

Balcron Oil Division

Balcron Monument Federal #33-6

NW SE Section 6, T9S, R17E

Duchesne County, Utah

In accordance with requirements outlined in 43 CFR 3162.3-1 (d):

#### 1. EXISTING ROADS:

- a. From Myton, Utah, take Highway #40 west out of town 1.6 miles to the Sand Wash road. Go south on the Sand Wash road for 10.4 miles. Turn right onto lease road and go 0.2 miles. Turn left on lease road and go 0.9 miles to tee. Turn right at the tee and go 0.3 miles to the location.
- b. Existing roadways need no improvements for these drilling operations.
- c. All existing roads used by these drilling operations will be maintained in the same or better condition as were existing prior to entry.
- d. See EXHIBIT "J" Maps A and B for access route.

# 2. PLANNED ACCESS ROADS: See EXHIBIT "J" Maps A and B

- a. Length: Approximately 0.27 miles of new access road will be required.
- b. Width: Maximum 30' overall right-of-way with an 18' running surface.
- c. Maximum grade: 2%
- d. Turnouts: none
- e. Drainage design: This will be a barrow ditch on cut side.
- f. No culverts or bridges will be required. There are no cuts and/or fills on or along the proposed access road route.
- g. Surface materials: Any surface materials which are required will be native materials from the location and/or access site.
- h. No gates, cattleguards, or fence cuts and/or modifications to existing facilities will be required.
- i. Access road route has been centerline-flagged.

EXHIBIT "B"
Surface Use Program
Page 2

- j. All travel will be confined to location and access routes.
- k. All access roads and surface disturbing activities will conform to the standards outlined in the Bureau of Land Management and Forest Service publication: <u>Surface Operating Standards for Oil and Gas Exploration and Development</u>, (1989).

The road shall be constructed/upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. This shall include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well-constructed safe road. If necessary prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Road drainage crossings will be of the typical dry creek draining crossing type. Crossings, if necessary, will be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading will not be done during muddy conditions. Should mud holes develop, they will be filled in and detours around them will be avoided.

1. No right-of-way applications are needed for this road.


#### 3. LOCATION OF EXISTING WELLS:


See EXHIBIT "K" Map C.


- a. Water wells: none
- b. Abandoned wells: one
- c. Temporarily abandoned wells: none
- d. Disposal wells: none
- e. Drilling wells: none
- f. Producing wells: twenty one
- g. Shut-in wells: one
- h. Injection wells: none

# 4. LOCATION OF EXISTING AND/OR PROPOSED PRODUCTION FACILITIES:

- a. Upon completion, a sundry notice and plat showing exact production facilities will be submitted.
- b. All above-ground facilities will be painted earthtone color Desert Brown #10Y/R in accordance with the Munsell Soil Color chart within six months of the well completion unless prior written approval to proceed with another alternative has been granted via Sundry Notice.







- Marchan - Amarchan	J 890 . DATE 15-01-90
LL NAME Baleron Money	mont tuchial 33-4
C NUSE UT 45.	R MF COUNTY Dichesine.
	· · · · · · · · · · · · · · · · · · ·
43:013-31361	tedual (1)
API NUMBER	CONFIDENTIA
ECK OFF:	•
PLAT	BOND NEAREST WELL
LEASE	FIELD POTASH OR OTL SHALE
OCESSING COMMENTS:	111 Main de le
water Primit	
	•
PPROVAL LETTER:	Ru45-3-~)
PACING: R615-2-3	NA RS15-3-2
	CAUSE NO. & DATE . R615-3-3
TIPULATIÓNS:	
1- water Primit	·
1 LUBULA ALUIU	CONFIDENTIAL
	EXPIGED ON 1:1945



Dee C. Hansen Executive Director Dianne R. Nielson, Ph.D. Division Director

355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340

June 25, 1992

Balcron Oil P.O. Box 21017 Billings, Montana 59104

#### Gentlemen:

Re: Balcron Monument Federal 33-6 Well, 1832 feet from the south line, 1829 feet from the east line, NW 1/4 SE 1/4, Section 6, Township 9 South, Range 17 East, Duchesne County, Utah

Pursuant to Utah Admin. R. 649-3-2 and Utah Admin. R. 649-3-4, approval to drill the referenced well is hereby granted.

In addition, the following specific actions are necessary to fully comply with this approval:

- 1. Submittal to the Division of evidence providing assurance of an adequate and approved supply of water as required by Utah Code Ann. § 73-3, Appropriations, prior to commencing drilling operations.
- 2. Compliance with the requirements of Utah Admin. R. 649-1 et seq., Oil and Gas Conservation General Rules.
- Notification within 24 hours after drilling operations commence.
- 4. Submittal of Entity Action Form, Form 6, within five working days following commencement of drilling operations and whenever a change in operations or interests necessitates an entity status change.
- 5. Submittal of the Report of Water Encountered During Drilling, Form 7.
- 6. Prompt notification prior to commencing operations, if necessary, to plug and abandon the well. Notify Frank R. Matthews, Petroleum Engineer, (Office) (801)538-5340, (Home) (801)476-8613, or R.J. Firth, Associate Director, (Home) (801)571-6068.

Page 2 Balcron Oil Balcron Monument Federal 33-6 Well June 25, 1992

7. Compliance with the requirements of Utah Admin. R. 649-3-20, Gas Flaring or Venting, if the well is completed for production.

Trash and sanitary waste should be properly contained and transported to approved disposal locations, not retained in or disposed of in pits on location or downhole. Prior to the commencement of drilling operations, the operator should consult the local/county sanitarian and/or the Department of Environmental Quality, Division of Drinking Water/Sanitation, regarding appropriate disposal of sanitary waste.

This approval shall expire one year after date of issuance unless substantial and continuous operation is underway or a request for an extension is made prior to the approval expiration date. The API number assigned to this well is 43-013-31361.

Sincerely,

R.J. Fifth

Associate Director, Oil and Gas

(

ldc

Enclosures

CC:


Bureau of Land Management

J.L. Thompson

WOI1



P.O. Box 21017 1601 Lewis Avenue Building Billings, Montana 59104 (406) 259-7860



August 10, 1992

-- VIA FEDERAL EXPRESS --

Bureau of Land Management 170 South 500 East Vernal, UT 84078

Gentlemen:

Enclosed is the addendum (three copies for each of the wells) to the Cultural Resource Evaluations which were done on the following wells:

Balcron Monument Federal #11-6 NW NW Section 6, T9S, R17E

Balcron Monument Federal #24-6 SE SW Section 6, T9S, R17E

Balcron Monument Federal #33-6 43-013-31361 NW SE Section 6, T9S, R17E

This should complete the requirements for the APDs on those wells. We realize that the Balcron Monument Federal #24-6 APD had to be posted for an additional 30 days since the location was moved more than 660'. That posting period began August 3.

If you have any questions or need further information, please let me know.

Sincerely,

Bobbie Schuman

Coordinator of Operations,

Environmental and Regulatory Affairs

/rs

Enclosures


cc: State of Utah; Division of Oil, Gas and Mining



# ARCHEOLOGICAL - ENVIRONMENTAL RESEARCH CORPORATION

P. O. Box 853 Bountiful, Utah 84011-0853 Tel: (801) 292-7061, 292-9668

August 8, 1992



Subject:

Addendum to CULTURAL RESOURCE EVALUATIONS OF FOUR PROPOSED WELL LOCATIONS IN THE CASTLE

PEAK DRAW LOCALITY OF DUCHESNE COUNTY, UTAH

Project:

BALCRON OIL CO. -- 1992 Development Program for Unit 33-5

Project No.:

**BLCR-92-4** 

Permit No.:

Dept. of Interior -- UT-92-54937

Utah Project No.:

UT-92-AF-228b

To:

Ms. Bobbie Schuman, Balcron Oil Co., P.O. Box 21017,

Billings Montana 59104

Mr. David Little, District Manager, Bureau of Land Management, 170 South 500 East, Vernal, Utah 84078

Info:

Antiquities Section, Division of State History, 300 Rio

Grande, Salt Lake City, Utah 84101

Department of the Interior
Bureau of Land Mandement
Utah State Office
(AERC FORMAT)

Summary Report of Inspection for Cultural Resources

Authorization .U.9.2	2.A.F.2.2.8.b.
Report Acceptable Ye	es No
Mitigation Acceptable Comments:	Yes No

Inspection for Cultural Resources
CASTLE PEAK DRAW UNITS ADDENDUM  1. Report Title
BALCRON OIL CO. UNITS 11-6, 24-6, AND 33-6  2. Development Company
8 8 1 9 9 2 UT-92-54937  3. Report Date 4. Antiquities Permit No.
A E R C B L C R - 9 2 - 4 Duchesne  5. Responsible Institution
6. Fieldwork  0 9 S 1 7 0 6  Location: TWN RNG Section        7. Resource Area TWN RNG Section          D.M.
8. Description of Examination Procedures: The archeologist, F.R. Hauck, intensively examined the relocation for these wells and new access corridors (as shown on the attached map) by walking a series of 10 to 20 meter-wide transects flanking the flagged centerline and within the flagged well pad. New well locations for 11-6 and 24-6 are outside the 10 acre parcel evaluated by AERC in May. Minor access route changes were involved with all three locations.
9. Linear Miles Surveyed 10. Inventory Type
and/or  Definable Acres Surveyed
11. Description of Findings:  No cultural resource sites were identified  during the survey. One isolated artifact 13. Collection: .Y.  was observed in association with the access (Y = Yes, N = No)  route into Unit 11-6. This artifact consists of a bifacially prepared chopper which was manufactured from a smooth nodule of Parachute Creek chert.

^{14.} Actual/Potential National Register Properties Affected:
The National Register of Historic Places (NRHP) has been consulted and no registered properties will be affected by the proposed development.

15. Literature Search, Location/ Date: Utah SHPO 5-26-92

Vernal District Office Records 5-20-92

# 16. Conclusion/ Recommendations:

AERC recommends that a cultural resource clearance be granted to Balcron Oil Company for these proposed developments based on the following stipulations:

- 1. All vehicular traffic, personnel movement, construction and restoration operations should be confined to the corridor examined as referenced in this report, and to the existing roadways and/or evaluated access routes.
- 2. All personnel should refrain from collecting artifacts and from disturbing any significant cultural resources in the area.
- 3. The authorized official should be consulted should cultural remains from subsurface deposits be exposed during construction work or if the need arises to relocate or otherwise alter the location of the exploration area.


17. Signature of Administrator & Field Supervisor

UT 8100-3 (2/85)

Administrator

Field Supervisor

AK



T. 8 & 9 S. R. 16 & 17 E. Meridian: SL Quad: Myton SE, Utah	MAP  Cultural Resource Survey  of Relocated Well Pads &  Access Routes in the  Castle Peak Draw Locality	Legend:  10 Acre Survey Area*  New Pad Area
Project: Series:	Scole: 1:24000 -92-4 a Basin	New Access / Route / Isolated × Artifact

Form 3160-3 (November 1983) (formerly 9-331C)

# UNITED STATES DEPARTMENT OF THE INTERIOR

SUBMIT IN TRIBLEATES
(Other instructions on reverse side)

Form approved.
Budget Bureau No. 1004-0136
Expires August 31, 1985

	•	F LAND MANA		T	٠	U-020252A	and serial no.
APPLICATIO				N, OR PLUG B	ACK	6. IF INDIAN, ALLOTTEE	OR TRIBE NAME
1a. TYPE OF WORK						n/a	
	RILL 🖾	DEEPEN		PLUG BAC	<b>к</b> Ц		
	GAS OTHER		811 20	NGLE . MULTIPE	·* 🗀	S. FARM OR LEASE NAM	(B
2. NAME OF OPERATOR	W 200			CUUEIUEU	ТІДІ	Balcron Monum	ent Federal
EQUITABLE RE	SOURCES ENERGY	COMPANY			IIIL	9. WELL NO.	
3. ADDRESS OF OPERATOR		T 50104				33-6	E WILDCAT
P.U. BOX 21U	17; Billings, Market Benefit Processing Approximation Clearly as	11 59104 nd in accordance wi	th any S	tate requirements.*)		Monument Butt	
At surface	_					11. SEC., T., R., M., OR I AND SURVEY OR AB	
18 At proposed prod. zo	832' FSL 1829	FEL		, e.			
	43-0	18-31861	1	Mr. 3.35		NW SESec. 6,	
14. DISTANCE IN MILES			T OFFICE	•	<u> </u>	12. COUNTY OR PARISH Duchesne	UTAH
10 miles sou	utheast of Myto	n, utan	16. NO	. OF ACRES IN LEASE	17. NO.	DE ACRES ASSIGNED	[ UIAII
LOCATION TO NEARES PROPERTY OR LEASE	at Line, FT.	,			TO T	HIS WELL	
18. DISTANCE FROM PRO	rig. unit line, if any)	i	19. PR	OPOSED DEPTH	20. ROTA	RY OR CABLE TOOLS	
TO NEAREST WELL, OR APPLIED FOR, ON T	DRILLING, COMPLETED, HIS LEASE, FT.			5,580	Ro	otary	
21. ELEVATIONS (Show w	hether DF, RT, GR, etc.)					22. APPROX. DATE WO	RK WILL START*
	267.7 <b>'</b>					8/21/92	
23.	•	PROPOSED CASI	NG AND	CEMENTING PROGRA	M		
SIZE OF HOLE	SIZE OF CASING	WEIGHT PER P	T00T	SETTING DEPTH		QUANTITY OF CEME	<b>4.</b>
12-1/4"	8-5/8"	24#		260'		SX "G" EXHIBIT D(S)	ATWART .
7-7/8"	5-1/2"	15.5#		5,580	. see	EXHIDITY DIST.	
EXHIBITS ATTA	CHED					AUG 3	5 1 1992
	DRILLING PROGE		"F'		PORT		
	SURFACE USE PR	ROGRAM	"G'				ION OF
	PROGNOSIS	•	"H' "I'	BOPE SCHEMAT	. VND t	ELEVATION PLATS	& MINING
	PROGRAM OF BOND COVERA	\CF	"J"			NED ACCESS (MAR	
E EVIDENCE	OF BUND COVERA	NGL	"K"	EXISTING WELL			3 A & D)
			"Ľ"			<b>0</b> ,	
SELE CERTIFICATION	N· I hereby certif	fy that I am aud	thoriza	d, by proper lease	interes	taumer to conduc	t these
				e pursuant to 43 CF			
being provided by	Equitable Resource	es Energy Compar	ny as p	rincipal and Safeco	Insura	nce Company of Ame	rica as
surety under BLM E	Bond No. MT 0576 (N	lationwide 0il 8	& Gas B	ond #5547188) who v	vill be	responsible for co	mpliance
with all of the te	erms and conditions	of that portion	on of t	he lease associated	d with t	his application.	ed new productive
zone. If proposal is to	o drill or deepen direction	onally, give pertinen	t data o	n subsurface locations ar	d measure	ed and true vertical dept	hs. Give blowout
preventer program, if a	iny.			Coordinator of E	Enviro	nmental (	
Dald	40 Shume	221	,	and Regulatory		, ,	18.1992
BIGNED Bobbie	Schuman	V/(TI	TLE	and negation j		DATE X V/	
(This space for Fed	deral or State office use)	_				•	
PERMIT NO.	e ma	<del>- +</del>		APPROVAL DATE	<del></del>		
	and the town	mas		ASSISTANT DISTRICT		DATE AUG 2	£ 1000
APPROVED BY CONDITIONS OF APPRO	OVAL, IF ANY:	TI	TLE	MANAGER MINERALS		DATE AVEL A	<del>~ +33<u>८</u> − −</del>
				CONDI	בייים כ	AND TO TO TO THE STATE OF THE S	ACHED
NOTICE OF	APPROVAL			<b>55,1</b> 51	Τ.	V= 1.1.1/	AOI ILD

*See Instructions On Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United Stores any false ficitious or fraudulent statements or representations as to any matter within its diction.

# CONDITIONS OF APPROVAL APPLICATION FOR PERMIT TO DRILL

Company/Operator: <u>Equitable Resources Energy Company</u>

Well Name & Number: <u>Balcron Monument Federal 33-6</u>

Lease Number: U-020252-A

Location: NWSE Sec. 6 T. 9S R. 17E

Surface Ownership: Federal Lands administered by BLM

#### **NOTIFICATION REQUIREMENTS**

Location Construction -

at least forty-eight (48) hours prior to construction of location and

access roads.

**Location Completion** 

prior to moving on the drilling rig.

**Spud Notice** 

at least twenty-four (24) hours prior to spudding the well.

Casing String and

Cementing

at least twenty-four (24) hours prior to running casing and

cementing all casing strings.

BOP and Related

**Equipment Tests** 

at least twenty-four (24) hours prior to initiating pressure tests.

First Production

Notice

within five (5) business days after new well begins, or production

resumes after well has been off production for more than ninety (90)

days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

### CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Orders, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

#### A. DRILLING PROGRAM

1. <u>Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected</u> to be Encountered

Report <u>ALL</u> water shows and water-bearing sands to Tim Ingwell of this office. Copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

#### 2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

If an air compressor is on location and is being utilized to provide air for the drilling medium while drilling, the special drilling requirements in Onshore Oil and Gas Order No. 2, regarding air or gas drilling shall be adhered to. If a mist system is being utilized then the requirement for a deduster shall be waived.

The Vernal District Office shall be notified, at least 24 hours prior to initiating the pressure tests, in order to have a BLM representative on location during pressure testing.

#### 3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

As a minimum, the usable water and oil shale resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the top of the Mahogany oil shale, identified at  $\pm$  2,900 ft. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

The Vernal District Office shall be notified at least 24 hours prior to the running and cementing of all casing strings, in order to have a BLM representative on location while running and cementing all casing strings.

#### 4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

#### 5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vaporproof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

A cement bond log (CBL) shall be utilized to determine the <u>top</u> of cement (TOC) and bond quality for the production casing.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

#### 6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

The Vernal District Office shall be notified, during regular work hours (7:45 a.m.-4:30 p.m., Monday through Friday except holidays), at least 24 hours **prior** to spudding the well.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

<u>Immediate Report:</u> Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-2, 3162.7-3, and 3162.7-4 shall be submitted to the appropriate District Office within thirty (30) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-4.

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

#### 7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling onlease or off-lease will have prior written approval from the AO.

Gas meter runs for each well will be located within 500 feet of the wellhead. The gas flowline will be buried or anchored down from the wellhead to the meter and within 500

feet downstream of the meter run or any production facilities. Meter runs will be housed and/or fenced.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted monthly for the first three months on new meter installations and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, please contact one of the following individuals:

Gerald E. Kenczka

(801) 781-1190

Petroleum Engineer

(801) 789-7077

Petroleum Engineer

Ed Forsman

(801) 789-3634

BLM FAX Machine

#### FPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

Unused fracturing fluids or acids

Gas plant cooling tower cleaning wastes

Painting wastes

Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spend solvents, spilled chemicals, and waste acids

Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste

Refinery wastes

Liquid and solid wastes generated by crude oil and tank bottom reclaimers

Used equipment lubrication oils

Waste compressor oil, filters, and blowdown

Used hydraulic fluids

Waste solvents

Waste in transportation pipeline-related pits

Caustic or acid cleaners

Boiler cleaning wastes

Boiler refractory bricks

Incinerator ash

Laboratory wastes

Sanitary wastes

Pesticide wastes

Radioactive tracer wastes

Drums, insulation and miscellaneous solids.

#### B. SURFACE USE PROGRAM

#### 1. Well Site Layout

To protect the flood plain, if the well is a producer, facilities such as storage tanks, heater treaters, etc. will be constructed off the well pad to the southeast. A dike will be constructed around the facilities area adequate to contain the contents of all tanks. Production will be a closed system with no pits. The facilities area must be approved via Sundry Notice, prior to construction.

The stockpiled topsoil will be stored on the south side near point 2.

Access to the well pad will be from the southeast side near Point 1.

A rip-rapped dike will be placed on the southwest end of the well pad between Points A and 2. Native rock rubble may be used from near the well pad.

The pipeline from the wellhead to the tank battery will be constructed with a check valve, within the facilities area, so if the pipeline were to break, oil flow would shut off without draining any tanks.

#### 2. Plans for Restoration of Surface

Reclamation of unused disturbed areas on the well pad/access road no longer needed for operations, such as cut slopes, and fill areas will be accomplished by grading, leveling and seeding as recommended by the Authorized Officer. The following seed mixture will be used:

Pure Live Seed (PLS) <u>lbs./acre</u>	Seed Mix
1	Forage Kochia (Kochia prostrata)
5	Ephriam Crested Wheatgrass (Agropyron cristatum Ephriam)
4	Russian Wildrye (Elymus junceus)
2	Fourwing Saltbush (Atriplex canescens)

#### 3. Additional Information

- a. The operator is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator is to immediately stop work that might further disturb such materials, and contact the authorized officer (AO). Within five working days the AO will inform the operator as to:
  - -whether the materials appear eligible for the National Register of Historic Places;
  - -the mitigation measures the operator will likely have to undertake before the site can be used (assuming in situ preservation is not necessary); and
  - -a time frame for the AO to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are correct and that mitigation is appropriate.

If the operator wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the AO will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, the operator will be responsible for mitigation costs. The AO will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the AO that required mitigation has been completed, the operator will then be allowed to resume construction.

- b. The operator will control noxious weeds along rights-of-way for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds may be obtained from the BLM, or the appropriate County Extension Office. On BLM administered land it is required that a Pesticide Use Proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.
- c. Drilling rigs and/or equipment used during drilling operations on this wellsite will not be stacked or stored on Federal Lands after the conclusion of drilling operations.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

A complete copy of the approved APD and ROW grant, if applicable, shall be on location during construction of the location and drilling activities.

The operator or his/her contractor shall contact the BLM Office at (801) 789-1362 forty-eight (48) hours prior to construction activities.

The BLM Office shall be notified upon site completion prior to moving on the drilling rig.

# DIVISION OF OIL, GAS AND MINING

# SPUDDING INFORMATION

	43-01	<u>3-31361</u>	h	
MC	LEN			
_				
<del> </del>				
····		w	-	
· · ·				
			-	
QT/	יאירה		TT.P	
	FEDERAL 9S MC	PEDERAL 3  9S Range  MOLEN	FEDERAL 33-6  9S Range 17E  MOLEN	



P.O. Box 21017 1601 Lewis Avenue Building Billings, Montana 59104 (406) 259-7860

October 28, 1992

State of Utah Division of Oil, Gas & Mining 355 West North Temple Salt Lake City, UT 84180 007 5 0 1992

001 3 0 1772

DIVIGION OF Oil gas a minimo

Gentlemen:

RE: Balcron Monument Federal #33-6 NW SE Section 6, T9S, R17E Duchesne County, Utah

Enclosed is a copy of our Federal sundry notice providing written notification of spud on the referenced well. Also enclosed is our Entity Action form.

Sincerely,

Bobbie Schuman

Coordinator of Operations,

Environmental and Regulatory Affairs

/rs

**Enclosures** 

Form 3160-5 (June 1990)

12.

X Subsequent Report

Final Abandonment Notice

# UNITED STATES DEPARTMENT OF THE INTERIOR

BUREAU OF LAND MANAGEMENT

FORM	APPR	OVED
Budget Bure	au No.	. 1004–0135
Expires:		

	Expires:	March	31, 177	' >
Lease	Designat	ion and	Serial	No.

U-020252-A	

SUNDRY NOTICES AND REPORTS OF TILLES
Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
" for such proposals

SUNDRY NOTICES AND REPORTS ON WELLS 6. If Indian, Allottee or Tribe Name n/a Use "APPLICATION FOR PERMIT—" for such proposals 7. If Unit or CA, Agreement Designation SUBMIT IN TRIPLICATE n/a 1. Type of Well Well Name and No. X Oil Well Balcron Monument Fed. #33-6 Other 2. Name of Operator 9. API Well No. 43-013- 31361 EQUITABLE RESOURCES ENERGY COMPANY 3. Address and Telephone No. 10. Field and Pool, or Exploratory Area P.O. Box 21017; Billings, MT 59104 (406) 259-7860 Monument Butte/Green River 4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 11. County or Parish, State NW SE Section 6, T9S, R17E 1832' FSL, 1829' FEL Duchesne County, UTAH CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA TYPE OF ACTION TYPE OF SUBMISSION Change of Plans Abandonment Notice of Intent New Construction Recompletion

Completion or Recompletion Report and Log form.) 13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*


Plugging Back

Casing Repair

Altering Casing

Other Report of spud

This well was spud October 24, 1992, by Parker Air Drilling.



Non-Routine Fracturing

Conversion to Injection

(Note: Report results of multiple completion on Well

Water Shut-Off

Dispose Water

OIL GAS & MINIMG

14. I hereby certify that the foregoing is true and correct Signed Daniel SCRUMAN	Coordinator of Environmental Title and Regulatory Affairs	Date
(This space for Federal or State office use)  Approved by Conditions of approval, if any:	Title	Date

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

TATE OF	DE DIF.	GAS A	РΝ	иійій	G
ENTITY	ACTION	FOR	۱ _	FORM	6

OPERATOR	Balcron Oil	
ADDRESS _	P.O. Box 21017	
_	Billings, MT 59104	

OPERATOR ACCT. NO. H 9890

												<del>,</del>	
ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NA	ME		QQ	SC	WELL I	OCATION RG	COUNTY	SPUD DATE	EFFECTIVE DATE
А	99999	11438	43-013-31361	Balcron Monument	Federal	#33-6	NW SE	6	9\$	17E	Duchesne	10/24/92	10/24/92
WELL 1 C	OMMENTS:		r til., ala	1.1 11-3-92		•							
	Spud o	f new wel	1.	hed 11-3-92. Fue									·
					· .								
WELL 2 C	OMMENTS:	· · · · ·	<u> </u>	<u> </u>	,	<del></del>	<u> </u>			·	•		•
WELL 3 C	OMMENTS:		<u>'</u>									,¢	
													:
WELL 4 C	OMMENTS:		·				<del> </del>						
								•					
	·				İ								
WELL 5 C	OMMENTS:	· · · · · · · · · · · · · · · · · · ·	· · · · · · · · · · · · · · · · · · ·						•				
				,. <del>c.</del>				NEVE/M	F-1				

ACTION CODES (See instructions on back of form)

A - Establish new entity for new well (single well only)

B - Add new well to existing entity (group or unit well)

C - Re-assign well from one existing entity to another existing entity

D - Re-assign well from one existing entity to a new entity

E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

DIVISION OF OIL GAS & MINING

GGT 5 0 1992

human

Coordinator of Environmental and 10/28/92 Date

Phone No. (406 ) 259-7860

(3/89)

Form 3160-5 (June 1990)

# UNITED STATES

DEPART	MENT	OF THE	INTERIOR	
BUREAU	OF LA	nd Mài	NAGEMENT	

FORM	LAPPK	ンタピロ	
Budget Bur	cau No.	1004-013	3:
Expires:			
 		* * * * * *	_

3.	Lease	Designation	and	Serial	No.
		20252			

5.	Lease	Designation and	1 Serial	No
	11-0	20252-4		

BUREAU OF I	LAND MANAGEMENT	U-020252-A				
SUNDRY NOTICES	6. If Indian, Allottee or Tribe Name					
Do not use this form for proposals to dri Use "APPLICATION FOR	Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.  Use "APPLICATION FOR PERMIT—" for such proposals					
•	IN TRIPLICATE CONFIDENTIAL	7. If Unit or CA, Agreement Designation n/a				
I. Type of Well    X Oil   Gas   Other		8. Well Name and No. Balcron Monument Fed. #33-6				
2. Name of Operator EQUITABLE RESOURCES ENERGY CO	MPANY	9. API Well No. 43-013- 31361				
P.O. Box 21017; Billings, MT  4. Location of Well (Footage, Sec., T., R., M., or Survey D  NW SE Section 6, T9S, R1	escription)	10. Field and Pool, or Exploratory Area Monument Butte/Green Rive 11. County or Parish, State				
1832' FSL, 1829' FEL		Duchesne County, UTAH				
12. CHECK APPROPRIATE BOX(	s) TO INDICATE NATURE OF NOTICE, REPOR	T, OR OTHER DATA				
TYPE OF SUBMISSION	TYPE OF ACTION					
Notice of Intent  Subsequent Report  Final Abandonment Notice	Abandonment  Recompletion  Plugging Back  Casing Repair  Altering Casing  Other Change in total depth	Change of Plans  New Construction  Non-Routine Fracturing  Water Shut-Off  Conversion to Injection  Dispose Water				
13. Describe Proposed or Completed Operations (Clearly state a give subsurface locations and measured and true vertically states and true vertically states are stated as a state of the st	Il pertinent details, and give pertinent dates, including estimated date of starting cal depths for all markers and zones pertinent to this work.)*	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)				

This well was permitted to a depth of 5,580'. drill this well to a total depth of 5,800'. Operator requests approval to

NOV 0 4 1992

DIVIGION OF OIL GAS & MINING

	MPEU	
14. I hereby certify that the foregoing of true and correct  Signed Dobbie Schuman	Coordinator of Environmental Tile_and_Regulatory_Affairs	Date November 2, 1992
(This space for Federal or State office use)  Approved by Conditions of approval, if any:	Title	Date

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

#### DAILY OPERATING REPORT

BALCRON MONUMENT #33-6

Location: NW SE Section 6, T98, R17E

Duchesne County, Utah

--TIGHT HOLE--

1829' FEL 1832' FSL

PTD: 6,200' Formation: Top of Wasatch

Green River Prospect Elevations: 5267.7' GL Contractor: Molen Rig #1 Operator: Balcron Oil

Spud: 10-24-92 @ 1 p.m. Casing: 8-5/8" @ 256' GL

- 10-14-92 Move pipe line over to West side of location.
- 10-16-92 Start location.
- 10-20-92 Finish location.
- 10-23-92 MI Parker Air Drilling rig.
- 10~24-92 Spud @ 1 p.m. 10~24-92 & start drilling. Made 130' in 8" hole.
- 10-25-92 Drill to 260' w/8" bit. POOH & get ready to ream 12-1/4".

  DC: \$10,495 CC: \$10,495
- 10-26-92 Got 12-1/4" hole reamed to 140'.
- 10-27-92 Reamed 12-1/4" hole to 260'.
- 10-28-92 Pull drill stem & lay it down. Run 6 jts 8-5/8" csg & cmt w/Dowell. 3 centralizers & wood plug. Csg set @ 256' GL. Cmt w/161 sxs 75-25% w/2% CCL & 1/4#/sx Celoflake. 10 bbls cmt back & did not fall down hole. Plug down @ 2 p.m. 10-28-92. DC: \$7,880 CC: \$18,375
- 10-30-92 Drill rat hole & mouse hole. RD Parker air drilling & move off.
- 11-1-92 Present Operation: Prepare to move rotary on.
  Put pit liner in pit & start hauling wtr.
  DC: \$3,700 CC: \$22,075

Post-It™ brand fax transmittal r	nemo 76 <b>7</b> 1	# of pages >
State of Utah	From	ly Consad
Dept.	co. Bal	Cron Oil
Env.#	4010-	259-1860
Fax #	Fax Ann	216 1241

# DAILY OPERATING REPORT

BALCRON MONUMENT #33-6

Location: NW SE Section 6, T98, R17E

Duchesne County, Utah

--TIGHT HOLE--

TD: 306' (35') Day 1 11-3-92

Formation: Duchesne

MW fresh wtr

Present Operation: Drilling

MIRU, weld on csg head & NU BOP. Test BOP & manifold to 2000#. Test csg to 1500# - OK. PU drill collars & drill

cmt. Drill new hole.

DC: \$4,327 CC: \$22,702

TD: 1,337' (1,031') Day 2 11-4-92

Formation: Duchesne MW 8.4 VIS 26 pH 9.7

Present Operation: Drilling Drill, survey, & clean on rig.

DC: \$14,756 CC: \$37,458


#### DAILY OPERATING REPORT

# BALCRON MONUMENT #33-6

Location: NW SE Section 6, T9S, R17E Duchesne County, Utah

--TIGHT HOLE--

- 11-7-92 TD: 2,912' (197') Day 5
  Formation: Green River
  MW 8.5 VIS 26 pH 10.2
  Present Operation: Trip
  Drill w/15000# on bit & 85-90 RPM. Drill & survey. Trip
  to remove TBS @ 2912', making dog leg.
  DC: \$4,293 CC: \$62,213
- TD: 3,481' (569') Day 6
  Formation: Green River
  MW 8.5 VIS 26 pH 10.2
  Present Operation: Run survey.
  Finish trip & start to drill w/25000# weight & 65-70 RPM,
  survey, clean & paint on rig. Increase weight to 35000#.
  Background Gas 30-50 units. Connection Gas 110
  units.
  DC: \$8,397 CC: \$70,610
- 11-9-92 TD: 4,196' (715') Day 7
  Formation: Green River
  MW 8.5 VIS 26 Ph 9.7
  Present Operation: Drilling
  Drill, survey, clean on rig, & paint. Background Gas 40 units.
  DC: \$10,305 CC: \$80,915



# DAILY OPERATING REPORT

BALCRON MONUMENT #33-6
Location: NW SE Section 6, T9S, R17E
Duchesne County, Utah

--TIGHT HOLE--

TD: 3,481' (569') Day 6
Formation: Green River
MW 8.5 VIS 26 pH 10.2
Present Operation: Run survey.
Finish trip & start to drill w/25000# weight & 65~70 RPM,
survey, clean & paint on rig. Increase weight to 35000#.
Background Gas - 30-50 units. Connection Gas - 110
units.
DC: \$8,397 CC: \$70,610

11-9-92 TD: 4,196' (715') Day 7
Formation: Green River
MW 8.5 VIS 26 Ph 9.7
Present Operation: Drilling
Drill, survey, clean on rig, & paint. Background Gas 40 units.
DC: \$10,305 CC: \$80,915

11-10-92 TD: 4,666' (470') Day 8
Formation: Green River
MW 8.5 VIS 26 pH 9.9
Present Operation: Cut drill line.
Drill,s urvey, circ btms up, TOH to PU reamers. TIH part way & cut drill line.
DC: \$7,775 CC: \$88,690

3

#### DAILY OPERATING REPORT

BALCRON MONUMENT #33-6 Location: NW SE Section 6, T98, R17E Duchesne County, Utah

--TIGHT HOLE--

- TD: 3,481' (569') Day 6
  Formation: Green River
  MW 8.5 VIS 26 pH 10.2
  Present Operation: Run survey.
  Finish trip & start to drill w/25000# weight & 65-70 RPM,
  survey, clean & paint on rig. Increase weight to 35000#.
  Background Gas 30-50 units. Connection Gas 110
  units.
  DC: \$8,397 CC: \$70,610
- TD: 4,196' (715') Day 7
  Formation: Green River
  MW 8.5 VIS 26 Ph 9.7
  Present Operation: Drilling
  Drill, survey, clean on rig, & paint. Background Gas 40 units.
  DC: \$10,305 CC: \$80,915
- TD: 4,666' (470') Day 8
  Formation: Green River
  MW 8.5 VIS 26 pH 9.9
  Present Operation: Cut drill line.
  Drill,s urvey, circ btms up, ToH to PU reamers. TIH part
  way & cut drill line.
  DC: \$7,775
  CC: \$88,690
- 11-11-92 TD: 4,695' (29') Day 9
  Formation: Green River
  MW 8.5 VIS 26 pH 9.7
  Present Operation: TIH w/bit.
  Cut drill line & start reaming. Ream dog leg & wash to btm to clean hole. TOH & PU core barrel. Tripping & start coring @ 4666', cut 29' & make connection & core barrel jammed. TOH & LD 29' of core. Stand back core barrel. Start in hole.
- 11-12-92 TD: 4,862' (167') Day 10
  Formation: Green River
  MW 8.5 VIS 26 pH 9.7
  Present Operation: Work on drawworks.
  TIH to drill. Drill to 4800' & TOH for core #2. TIH
  w/core barrel. Core 42' & jammed. TOH & LD core.
  Recover 42', 10'-12' good sand. Stand core barrel back
  & TIH to drill. WTB & drill. Work on rig.
  DC: \$6,496 CC: \$100,001

BALCRON MONUMENT #33-6

1.00

Location: NW SE Section 6, T98, R17E

Duchesne County, Utah

--TIGHT HOLE--

11-13-92 TD: 5,104' (242') Day 11

Formation: Green River

MW 8.5 VIS 26 pH 9.7

Present Operation: TOH for core bbl.
Replace bearing on main shaft in drawworks. Drill to 5104', cdrop survey & start out of hole. Smith bit

#KV0103, 207-1/2 hrs, 6871 feet in 4 holes.

DC: \$5,369 CC: \$105,370

Post-It™ brand fax transmittal memo 7671 # of pages

4



#### DAILY OPERATING REPORT

BALCRON MONUMENT #33-6 Location: NW SE Section 6, T98, R17E Duchesne County, Utah

--TIGHT HOLE--

- TD: 5,104' (242') Day 11
  Formation: Green River
  MW 8.5 VIS 26 pH 9.7
  Present Operation: TOH for core bbl.
  Replace bearing on main shaft in drawworks. Drill to 5104', cdrop survey & start out of hole. Smith bit #KV0103, 207-1/2 hrs, 6871 feet in 4 holes.
  DC: \$5,369

  CC: \$105,370
- 11-14-92 TD: 5,370' (266') Day 12
  Formation: Green River
  MW 8.5 VIS 26 pH 9.5
  Present Operation: Drilling
  TOH & PU core bbl. TIH & start coring @ 5104', cut 160'
  to 5164'. TOH & LD core, recover 58-1/2". LD core bbl
  & TIH w/bit. Go to drilling.
  DC: \$18,215 CC: \$123,585
- 11-15-92 TD: 5,740' (370') Day 13
  Formation: Green River
  MW 8.5 VIS 26 pH 9.5
  Present Operation: Logging
  Drill, circ for logs, drop survey. TOH WO Schlumberger
  logging. HCL on location @ 6 a.m.
  DC: \$8,305 CC: \$131,890
- TD: 5,740' (0') Day 14
  Formation: Green River
  Present Operation: Nipple down BOP.
  Log w/Schlumberger, let HLS run high resolution induction log. TIH & LD drill pipe & collars. Run 5-1/2" csg & cmt. Clean tanks, nipple down. 20 centralizers, 5-1/2" she joint & shoe; float collar; 125 jts 5-1/2", 15.5, K-55 csg; csg set @ 5713.92'. Cmt w/226 sxs hilift & 400 sxs Class "G". Plug down @ 4 a.m.
  DC: \$67,128 CC: \$199,018

Paid Mars Minion	From MOLLI CONVAC
Co. State of Usah	Co Balanch Que
Dept.	Phane - 259 - 7860
Fax \$401-359-3940	Fax#010-245- V3101

4

#### DAILY OPERATING REPORT

# BALCRON MONUMENT #33-6 Location: NW SE Section 6, T98, R17E Duchesne County, Utah

--TIGHT HOLE--

- 11-13-92 TD: 5,104' (242') Day 11
  Formation: Green River
  MW 8.5 VIS 26 pH 9.7
  Present Operation: TOH for core bbl.
  Replace bearing on main shaft in drawworks. Drill to 5104', cdrop survey & start out of hole. Smith bit #KV0103, 207-1/2 hrs, 6871 feet in 4 holes.
  DC: \$5,369 CC: \$105,370
- 11-14-92 TD: 5,370' (266') Day 12
  Formation: Green River
  MW 8.5 VIS 26 pH 9.5
  Present Operation: Drilling
  TOH & PU core bbl. TIH & start coring @ 5104', cut 160'
  to 5164'. TOH & LD core, recover 58-1/2". LD core bbl
  & TIH w/bit. Go to drilling.
  DC: \$18,215 CC: \$123,585
- 11-15-92 TD: 5,740' (370') Day 13
  Formation: Green River
  MW 8.5 VIS 26 pH 9.5
  Present Operation: Logging
  Drill, circ for logs, drop survey. TOH WO Schlumberger logging. HCL on location @ 6 a.m.
  DC: \$8,305 CC: \$131,890
- 11-16-92 TD: 5,740' (0') Day 14
  Formation: Green River
  Present Operation: Nipple down BOP.
  Log w/Schlumberger, let HLS run high resolution induction log. TIH & LD drill pipe & collars. Run 5-1/2" csg & cmt. Clean tanks, nipple down. 20 centralizers, 5-1/2" she joint & shoe; float collar; 125 jts 5-1/2", 15.5, K-55 csg; csg set @ 5713.92'. Cmt w/226 sxs hilift & 400 sxs Class "G". Plug down @ 4 a.m.
  DC: \$67,128 CC: \$199,018
- 11-17-92 Present Operation: Move off.

  ND BOP. Set slips, cut off csg. Move rig off.

  DC: \$16,540 CC: \$215,558

#### ATTACHMENT 1

#### BALCRON OIL MONUMENT BUTTE WATERFLOOD APPLICATION

#### INJECTION WELL PERFORATIONS

WELL NAME	ZONE NAME:	YELLOW	RED1	RED 2	RED 6	GREEN 1	GREENS	GREEN 4	GREEN 6	GREEN 6	BLUE
MONUMENT B	UTTE FED 11-6		4781-4790		(4930)		5208-5215		5288-5336		
ALLEN FED 13-	-6		**4744-4768		+4910-4920	**5054-5066					
ALLEN FED 22-	-6		+4765-4771		4910-4924		5190-5200		5270-5276		
MONUMENT B	UTTE FED 24-6		+4678-4681								**5556-5569
	UTTE FED 33-6		4658-4676		4814-4824						
MONUMENT B	UTTE FED 42-6		4757-4760		**4907-4927	**5065-5068					
ALLEN FED 1-6	(SE/SE)	**4169-4180	4698-4702	**4753-4757			**5141-5145				

#### PRODUCING WELL PERFORATIONS

WELL NAME	ZONE NAME:	YELLOW	RED 1	RED 2	RED 5	GREEN 1	GREEN 3	GREEN 4	GREEN 5	GREEN 6	BLUE
ALLEN FED 12-6		4302-4326	+4780-4788	4832-4851	T				5280-5301		5665-5676
ALLEN FED 21-6							5173-5194	5220-5228	5277-5381	5414-5419	·
ALLEN FED 23-6	. <u></u>	4249-4267	+4735-4750	4792-4808	4890-4908				5244-5260		
ALLEN FED 31-6						5050-5056		5235-5256			
ALLEN FED 32-6	<del></del>	4246-4289			4912-4934			5232-5354			
ALLEN FED 34-6			4690-4715		4856-4892		5162-5177	5189-5230			
ALLEN FED 41-6	<del></del>	4281-4318	4750-4764		4912-4938	5062-5068		5236-5260			
ALLEN FED 43-6			4666-4680	4712-4742	4817-4848			5138-5178	5179-5205		

+ TO BE ADDED

** NOT TO BE USED FOR INJECTION

RED 1 RED 6

GREENS

GREEN 6

ZONES FOR INJECTION

OPERATOR _

#### APPLICATION FOR INJECTION WELL - UIC FORM 1

BALCRON OIL

Billings, MT 59104
Well name and number: Balcron Monument Federal #33-6
Field or Unit name: <u>Monument Butte Field</u> Lease no. <u>U-020252A</u>
Well location: QQ <u>NW SE</u> section <u>6</u> township <u>9S</u> range <u>17E</u> county <u>Duchesne</u>
Is this application for expansion of an existing project? Yes [] No 內
Will the proposed well be used for: Enhanced Recovery? Yes [x] No [] Disposal? Yes [] No [x] Storage? Yes [] No [x]
Is this application for a new well to be drilled? Yes [] No № *
If this application is for an existing well, has a casing test been performed on the well? Yes [] No & Date of test: This well will be drilled and API number: 43-013-31361 completed prior to December 2 hearing.
Proposed injection interval: from 4,650' to 5,170'
Proposed maximum injection: rate600 BPD pressure2500psig
Proposed injection zone contains [X] oil, [] gas, and/or [] fresh water within $\mbox{\tt X}$ . mile of the well.
IMPORTANT: Additional information as required by R615-5-2 should accompany this form.

Phone No. ( ) and Regulatory Affairs PHONE: (406) 259-7860

List of Attachments: Logs are or will be on file prior to the Hearing.

I certify that this report is true and complete to the best of my knowledge.

(State use only)

Application approved by _____

Bobbie Schuman

Title Coordinator of Envrionmental


Approval Date _____

_____ Title ____

Signature Abbblu &


Date <u>October 16, 1992</u>

Comments:





P.O. Box 21017 1601 Lewis Avenue Building Billings, Montana 59104 (406) 259-7860



THE POST ! WHERE !

November 17, 1992

State of Utah Division of Oil, Gas, & Mining 355 West North Temple Salt Lake City, UT 84180

Gentlemen:

RE: Balcron Monument Federal #33-6

43-013-31361

NW SE Section 6, T9S, R17E

Duchesne County, Utah

Enclosed for your files are the update daily operating reports for the above referenced well.

Please feel free to contact me if you need any additional information.

Sincerely,

Molly M. Conrad

Operations Secretary

/mc

Enclosure

Mark Carlotte

OF CHANGE OF THE ST

#### DAILY OPERATING REPORT

BALCRON MONUMENT #33-6

Location: NW SE Section 6, T9S, R17E

Duchesne County, Utah

--TIGHT HOLE--

1829' FEL 1832' FSL

PTD: 6,200' Formation: Top of Wasatch

Green River Prospect
Elevations: 5267.7' GL
Contractor: Molen Rig #1
Operator: Balcron Oil

Spud: 10-24-92 @ 1 p.m. Casing: 8-5/8" @ 256' GL 5-1/2" @ 5713.92'

- 10-14-92 Move pipe line over to West side of location.
- 10-16-92 Start location.
- 10-20-92 Finish location.
- 10-23-92 MI Parker Air Drilling rig.
- 10-24-92 Spud @ 1 p.m. 10-24-92 & start drilling. Made 130' in 8" hole.
- 10-25-92 Drill to 260' w/8" bit. POOH & get ready to ream 12-1/4".
  DC: \$10,495 CC: \$10,495
- 10-26-92 Got 12-1/4" hole reamed to 140'.
- 10-27-92 Reamed 12-1/4" hole to 260'.
- 10-28-92 Pull drill stem & lay it down. Run 6 jts 8-5/8" csg & cmt w/Dowell. 3 centralizers & wood plug. Csg set @ 256' GL. Cmt w/161 sxs 75-25% w/2% CCL & 1/4#/sx Celoflake. 10 bbls cmt back & did not fall down hole. Plug down @ 2 p.m. 10-28-92. DC: \$7,880 CC: \$18,375
- 10-30-92 Drill rat hole & mouse hole. RD Parker air drilling & move off.
- Present Operation: Prepare to move rotary on.
  Put pit liner in pit & start hauling wtr.
  DC: \$3,700 CC: \$22,075

BALCRON MONUMENT #33-6

Location: NW SE Section 6, T9S, R17E

Duchesne County, Utah

--TIGHT HOLE--

11-3-92 TD: 306' (35') Day 1 Formation: Duchesne

MW fresh wtr

Present Operation: Drilling

MIRU, weld on csg head & NU BOP. Test BOP & manifold to 2000#. Test csq to 1500# - OK. PU drill collars & drill cmt. Drill new hole.

CC: \$22,702 DC: \$4,327

TD: 1,337' (1,031') Day 2 11-4-92 Formation: Duchesne MW 8.4 VIS 26 pH 9.7 Present Operation: Drilling Drill, survey, & clean on rig.

CC: \$37,458 DC: \$14,756

11-5-92 TD: 2,420' (1,083') Day 3 Formation: Horseshoe Bench MW 8.4 VIS 26 pH 10 Present Operation: Drilling

Drill, survey, work on mud pump, replace pony rod, & both

swabs.

DC: \$14,776 CC: \$52,234

TD; 2,715' (275') Day 4 11-6-92 Formation: Green River MW 8.5 VIS 26 pH 9.7 Present Operation: Drilling Drill, survey, hole getting crooked, out to 5-1/4° @

2596'. TOH, bit OK. WO IBS, TIH w/pendulum assembly. Drill & survey. Weight 10-1500# on bit, 85 RPM. Did not get over the drilling nipple gas.

DC: \$5,686 CC: \$57,920

11-7-92 TD: 2,912' (197') Day 5 Formation: Green River MW 8.5 VIS 26 pH 10.2 Present Operation: Trip

Drill w/15000# on bit & 85-90 RPM. Drill & survey. Trip

to remove TBS @ 2912', making dog leg.

CC: \$62,213 DC: \$4,293

#### BALCRON MONUMENT #33-6

Location: NW SE Section 6, T9S, R17E

Duchesne County, Utah

--TIGHT HOLE--

11-8-92 TD: 3,481' (569') Day 6 Formation: Green River MW 8.5 VIS 26 pH 10.2

Present Operation: Run survey.

Finish trip & start to drill w/25000# weight & 65-70 RPM, survey, clean & paint on rig. Increase weight to 35000#. Background Gas - 30-50 units. Connection Gas - 110 units.

DC: \$8,397 CC: \$70,610

11-9-92 TD: 4,196' (715') Day 7
Formation: Green River
MW 8.5 VIS 26 Ph 9.7
Procent Operation: Drill

Present Operation: Drilling

Drill, survey, clean on rig, & paint. Background Gas - 40 units.

DC: \$10,305 CC: \$80,915

11-10-92 TD: 4,666' (470') Day 8 Formation: Green River MW 8.5 VIS 26 pH 9.9

Present Operation: Cut drill line.

Drill, s urvey, circ btms up, TOH to PU reamers. TIH part

way & cut drill line.

DC: \$7,775 CC: \$88,690

11-11-92 TD: 4,695' (29') Day 9 Formation: Green River MW 8.5 VIS 26 pH 9.7

Present Operation: TIH w/bit.

Cut drill line & start reaming. Ream dog leg & wash to btm to clean hole. TOH & PU core barrel. Tripping & start coring @ 4666', cut 29' & make connection & core barrel jammed. TOH & LD 29' of core. Stand back core barrel. Start in hole.

11-12-92 TD: 4,862' (167') Day 10 Formation: Green River MW 8.5 VIS 26 pH 9.7

Present Operation: Work on drawworks.

TIH to drill. Drill to 4800' & TOH for core #2. TIH w/core barrel. Core 42' & jammed. TOH & LD core. Recover 42', 10'-12' good sand. Stand core barrel back & TIH to drill. WTB & drill. Work on rig.

DC: \$6,496 CC: \$100,001

BALCRON MONUMENT #33-6

Location: NW SE Section 6, T98, R17E

Duchesne County, Utah

--TIGHT HOLE--

- 11-13-92 TD: 5,104' (242') Day 11
  Formation: Green River
  MW 8.5 VIS 26 pH 9.7
  Present Operation: TOH for core bbl.
  Replace bearing on main shaft in drawworks. Drill to 5104', cdrop survey & start out of hole. Smith bit #KV0103, 207-1/2 hrs, 6871 feet in 4 holes.
  DC: \$5,369 CC: \$105,370
- 11-14-92 TD: 5,370' (266') Day 12
  Formation: Green River
  MW 8.5 VIS 26 pH 9.5
  Present Operation: Drilling
  TOH & PU core bbl. TIH & start coring @ 5104', cut 160'
  to 5164'. TOH & LD core, recover 58-1/2". LD core bbl
  & TIH w/bit. Go to drilling.
  DC: \$18,215 CC: \$123,585
- 11-15-92 TD: 5,740' (370') Day 13
  Formation: Green River
  MW 8.5 VIS 26 pH 9.5
  Present Operation: Logging
  Drill, circ for logs, drop survey. TOH WO Schlumberger logging. HCL on location @ 6 a.m.
  DC: \$8,305 CC: \$131,890
- 11-16-92 TD: 5,740' (0') Day 14
  Formation: Green River
  Present Operation: Nipple down BOP.
  Log w/Schlumberger, let HLS run high resolution induction log. TIH & LD drill pipe & collars. Run 5-1/2" csg & cmt. Clean tanks, nipple down. 20 centralizers, 5-1/2" she joint & shoe; float collar; 125 jts 5-1/2", 15.5, K-55 csg; csg set @ 5713.92'. Cmt w/226 sxs hilift & 400 sxs Class "G". Plug down @ 4 a.m.
  DC: \$67,128 CC: \$199,018
- 11-17-92 Present Operation: Move off.

  ND BOP. Set slips, cut off csg. Move rig off.

  DC: \$16,540 CC: \$215,558

## INJECTION WELL APPLICATION'

#### REVIEW SUMMARY

Applicant: BALCRON OIL Well: 33-6
Location: section 6 township 9 SOUTH range 17 EAST
API #: 43-013-31361 Well Type: disp enhanced recovX_
If enhanced recovery has project been approved by the Board ? NO
Lease Type: FEDERAL Surface Ownership: BLM
Field: MONUMENT BUTTE Unit: Indian Country: YES
UIC Form 1: YES Plat: YES Wells in AOR: 4P,6I
Logs Available: YES Bond Log:
Casing Program: ADEQUATE
Integrity Test: AT TIME OF CONVERSION
Injection Fluid: FRESH WATER
Geologic Information: DOUGLAS CREEK MEMBER OF GREEN RIVER FORMATION,
Analyses of Injection Fluid: NO Formation Fluid: YES Compat. NO
Fracture Gradient Information: .861PSIG/FT Parting Pressure 2500 PSI
Affidavit of Notice to Owners: YES
Fresh Water Aquifers in Area: THERE ARE NO USDW'S IN AREA
Depth Base of Moderately Saline Water: 4800-5000 MEAN SEA LEVEL
Confining Interval: GREEN RIVER AND WASATCH SHALES
Reviewer: D. JARVIS Date: 11-24 -92
Comments & Recommendation WELL IS BEING DRILLED NEED TO RUN MIT AT TIME OF CONVERSION, NEED ANALYSIS OF INJECTION FLUID.

Monument Federal #33-6 (Proposed Location) NW SE Sec. 6,T9S,R17E Lease No. U-020252A MONUMENT BUTTE FIELD DUCHESNE CO., UTAH

Proposed Injection Well Completion Diagram

BALCRON OIL 7-20-92



8 5/8",K-55,24#
Landed @ 260' KB
Cemented W/250 sx,Class-G,3% CaCl.
Cemented to surface.
Hole Size @ 12 1/4"

#### PRODUCTION CASING

5 1/2",J-55,15.5# Landed @ 5580' KB Cement Data: 250 sx Hifill w/10#/sx Gilsonite tailed w/180 sx 50-50 poz w/0.3% CFR-3,1/4#/sx Flocele,0.5% Halad-24 & 10% Salt. Cemented to surface. Hole Size @ 7 7/8"

#### **TUBING & PACKERS**

2 3/8",J-55,4.7# Landed @ 5130' KB

Retrievable Csg Tension Packer Landed @ 5134' KB

Tandem Tension Packer Landed @ 4810' KB Tandem Tension Packer Landed @ 4630' KB

Wireline retrievable downhole flow regulators set to control the flowrate into each injection zone.

- Uintah Formation Surface to 1400 ft.

- Green River Formation 1400 to 4100 ft.

#### PROPOSED PERFORATIONS

4650'- 4660' (10') 2 SPF 4830'- 4850' (20') 2 SPF 5150'- 5170' (20') 2 SPF 100 Holes

Douglas Creek Member 4100 to 5350 ft.Wasatch Fm. Transition 5350 to 6000 ft.

REGILME

WELL REPORT

NOV 3 0 1992

DIVISION OF OIL GAS & MININI

CONTRACTAL

Monument Butte Field
Balcron Oil Co. 33-6 Monument Butte-Federal
1832' FSL, 1829' FEL, Sec. 6, T9S-R17E
Duchesne County, Utah
43-0/3-3/36/

NWSE

BY

DENNIS REHRIG & ASSOC, INC.

OIL & GAS CONSULTING

4924 Rimrock Road Billings, Montana 59106

(406) 656 - 4785

#### WELLSITE GEOLOGISTS REPORT

Monument Butte Field
Balcron Oil Co. 33-5 Monument Butte-Federal
1832' FSL, 1829' FEL, Sec. 6, T9S-R17E
Duchesne County, Utah

DENNIS REHRIG & ASSOC.,INC.

OIL & GAS CONSULTING

4924 Rimrock Road Billings, Montena 59106

(406) 656 - 4785

### DENNIS C. REHRIG & ASSOCIATES, INC.

Oil & Gas Exploration

4924 RIMROCK ROAD • BILLINGS, MONTANA 59106 • (406) 656-4785

Monument Butte Field Balcron Oil Co. 33-6 Monument Butte-Federal 1832' FSL, 1829' FEL, Sec. 6, T9S-R17E Duchesne County, Utah

#### TABLE OF CONTENTS

Page	<u>Item</u>
1	General Well Review
2-4	Well Data
5	Daily Orilling History
6	Surveys
7	Bit Record
8	Mud Record
9	Time/Depth Penetration Curve
10	Drilled Well Formation Tops
11	Reference Well Formation Tops
12	Significant Gas and Sample Shows
13- 18	Core Reports and General Descriptions
19-46	Sample Descriptions
Insert	Geological Well Log

By: Dennis C. Rehrig Consulting Geologist

For:

Dennis C. Rehrig & Associates, Inc.

#### GENERAL REVIEW

The Balcron Oil Co. 33-6 Monument Butte-Federal (NW4SE4 S-6, T9S-R17E, Duchesne County, Utah) was drilled as an infill development well in the Monument Butte Field.

This well was supported by extensive subsurface offset well control and drilled for future water flood control and identification of anticipated additional Douglas Creek and Wasatch Tongue oil sands.

The surface hole was air drilled and surface casing was set prior to moving Molen Drilling Co. Rig No. 1 on location and spudding on November 3, 1992. A two-man mud logging unit and wellsite geologist were on-site from 1000' to total depth. The Green River and Douglas Creek formations were penetrated at 1410' and 4628' making them respectively 31' and 43' structurally high to the offset Diamond Shamrock Corp. 32-6 Allen-Federal (SW%NE% S-6, T9S-R17E) control well.

Three 4" whole cores were taken from Douglas Creek member Sandstone intervals. In addition, other numerous Sandstones were penetrated with gas and sample shows, which are noted elsewhere in this report.

This well was drilled to 5740' (Oriller) and 5743' (Logger).

Subsequent to log review the operator elected to run  $5\frac{1}{2}$ " production casing to total depth.

The rotary was released 11/17/92.

Respectfully submitted,

Dennis C. Rehrig

#### WELL DATA

OPERATOR:

Balcron Oil Company

LEASE & WELL NO .:

Monument Butte-Federal 33-6

LOCATION:

1832' FSL, 1829' FEL, Sec. 6, T9S-R17E

PROSPECT/FIELD:

Monument Butte Field

COUNTY:

Duchesne

STATE:

Utah

BASIN:

Uintah

WELL TYPE:

Development

BASIS FOR PROSPECT:

Subsurface well control

ELEVATIONS:

5267' G.L. 5278' K.B.

SPUD DATE:

6:00 AM (MST) 11/3/92 (Rotary)

OUT FROM UNDER

SURFACE CASING:

6:00 AM (MST) 11/3/92 (Surface casing

previously set)

DRILLING COMPLETED:

10:15 PM (MST) 11/14/92

LOGGING COMPLETED:

2:30 PM (MST) 11/15/92

RIG RELEASE:

Time unknown 11/17/92

TOTAL DAYS SPUD

THROUGH LOGGING:

13 days

TOTAL DEPTH:

5740' (Driller) 5743' (Logger)

TOTAL DRILLING DAYS:

12 days (surface casing previously set)

HOLE SIZE & CASING:

Hole Size

Casing Size

12¼" Surface to 271'

8 5/8" surface to

7 7/8" 271' to T.D.

271' K.B.

5½" Production csg to

5714' K.B.

WELL STATUS:

Cased for completion attempt in Douglas

Creek

PENETRATION:

265' into Wasatch Tongue

COMPANY DRILLING

CONSULTANT:

Al Plunkett

DRILLING CONTRACTOR:

Molen Drilling Co.

RIG NO.:

1

TOOLPUSHER:

Chuck Doornek

RIG SPECIFICATIONS:

Draw works - EMSCO GB-250T, Powered by 2 - Detroit 6-71 300 HP Diesels, Derrick - Idela, 104' mast.

BLOW OUT PREVENTER:

Make: Shaffer LWS. Type: 10" X 3000 lbs. Drill Pipe: Size 4½" 0D, 2½" ID, Thread XH. BHA: Length 840.00', 16 jts-6" DC-474.29' & -12 jts heavy weight pipe 360.71'. Tool joints: 6½" 0D, Type - XH.

PUMPS:

No. 1: EMSCO D-375 14" stroke 6" liner.

MUD COMPANY AND

MUD PROGRAM:

Unibar Drilling Fluids, Inc. Gerald Ashcraft

ENGINEER:

FreshWater KCL/Water 0-3000' .D.T-'000E

ELECTRIC OPEN-HOLE LOGGING PROGRAM:

Schlumberger Well Services Engineer - John Phillips

Witnessed by - Dennis Rehrig & Al Plunkett - Array Induction/Rwa Image High Resolution (272'-5726')

- Array Induction with Gamma Ray (272'-5726')

- Compensated Neutron/Litho-Density (2500'- 5726')

- NGT (2500'-5726')

OR DRILLING PROBLEMS:

None observed

WELLSITE GEOLOGIST:

Dennis C. Rehrig

SAMPLING PROGRAM:

30' Samples from 1000-4110'

20' Samples from 4110'-Total Depth, except

caught 10' Samples through drilling breaks.

SAMPLE QUALITY:

Generally good unless noted otherwise.

SAMPLE DISPOSITION:

Utah Geological Survey, Salt Lake City, Utah.

MUD LOGGING EQUIP .:

Cate Logging - two man unit operated by

Paul Nielsen & Gerry Brooke

CORE PROGRAM:	No. Interval Formation Cut Rec.  1 4666-4696' (Drlr) 4661-4691' (Logger) Douglas Creek 30' 30' 2 4800-4842' (Drlr) 4796-4838' (Logger) Douglas Creek 42' 42' 3 5104-5164' (Drlr) 5100-5160' (Logger) Douglas Creek 60 58.5
DRILL STEM TEST:	None.
SURFACE CASING:	8 5/8" New, 24 wt, J-55 Gr-STC, 6 jts, Surface - 271' K.B. Cemented w/161 sxs 75% Class 'G' & 25% Pozmix w/2% CaCl ₂ & ¼ lb/sx Celloflake. Plug down @ 2:00 PM (MST) 10/28/92. Surface hole drilled & casing set by small air-impact rig.
PRODUCTION CASING:	Ran 125 jts 5½" 15.5 lb K-55 casing to 5713.92' K.B. Cemented w/226 sxs Hilift and 400 sxs Class 'G'. Plug down @ 4:00 AM 11/16/92.
PLUGGING RECORD:	None.

ព្

Balcron 33-6 Monument Butte-Federal 1832' FSL, 1829' FEL, Sec. 6, T9S-R17E Duchesne County, Utah

#### DAILY DRILLING HISTORY

Daily drilling reports taken primarily from Rig Tower Sheets and supplemented by Drilling Supervisor. Day commenced at 8:00 AM (MST) of prior day of report and ends at 8:00 AM (MST) day of report.

		Pe	netration	,	Hours						
Days			Ftg in								
Since			Last		Maint &		Bit				
Spud	Date	Depth	24 hrs.	Drlg.	Repairs	Other	No.	WOB(M)	RPM	<u>PP</u>	Activity
<del></del>	1992										Rig-up, weld on well head, nipple up BOP, test stack, test casing,
1	11/3	305	34	2	0	22	1RR	25	50	500	PU DC & tag cement @ 200', drlg cement to 271'. (Note surface csg set to 271' K.B.) Spud 7 7/8" hole @ 6:00 AM 11/3/92.
•	11/4	1257	1052	23	0	1	1	35/40	70 ·		Drlg, survey.
2	11/4		1032	21.50		1.50		30/40	65/70	750	Drlg, survey, repair pump, drlg & survey.
3			273	13.25		10.75		10/12	80/90	750	Drlg, survey, drop survey. TOH to change bit because of hole dev-
4	11/6	2/10	2/3	13.23	U	10.75		20/14			iation, WO stabilizer, PU stabilizer, TIH, drlg, survey.
_			100	19.00	0	5.00	2	19	80/90	750	Survey, drlg, survey, TOH to change BHA.
5	11/7		196 583	19.00		5.00		35/40	65/70	750	TIH - no fill, drlg, survey.
6	11/8					1.00		40	65/70	750	Drlq, survey.
7	11/9		711	23.00 15.75		8.25		30/40	65/70		the second secon
8	11/10	4666	460	15./5	U	0.23	•	30, 10			survey, PU reamers, TIH w/DC & HWP, cut drlg line, TIH to ream.
9	11/11	4696	30	0	0	24.00	Core	15/20	800	<b>6</b> 50	TIH to ream dog leg, reaming, trip to btm, ream 100' to btm, circ, TOH for core, PU core barrel, TIH w/core barrel, wash 20' to btm,
											no fill, coring, TOH w/core, hoist core, recover 30' core, dress core barrel & stand back, TIH.
10	11/12	4862	166	5.00	1.75	17.25	Core	35/40	65/70	800	TIH, wash & ream 30' to bottom, no fill, drlg, TOH, drop survey, finish TOH, PU core barrel, TIH w/core barrel, wash 30' to bottom,
											core, TOH w/core, hoist core, recover core, dress core barrel & stand back, TIH, wash to bottom, drlg, repair bearing on drive shaft.
11	11/13	3 5104	242	5.29	12.50	€.25	4RR	40	65	800	
12		4 5386	282	9.50	0 ~ 0	14.50	5RR	35/40	50/55	800	TOH, make up core barrel, TIH, wash & ream 30' to btm, core, TOH w/
											core barrel, hoist core, recover core, breakdown, lay down core barrel, TIH, drlg.
	11/1	5 5740	354	14.2	5 0	0.75	5RR	40	60	800	and the state of t
13	11/1	3 3/40	334	14.2	, ,	9.73	JAA	40	•		E-Logs, hoist for E-Logs, WO E-Logs, RU E-Logs.
14	11/1	6 5740						, <del></del>			Run E-Logs, TIH, LD drill collars & drill pipe, run 5½" csg & cement, clean tanks & nipple down.
15	11/1	7 5740									Released rig.

#### SURVEYS VERTICAL HOLE

Drilling Depth	<u>De</u>	grees
366' 907' 1429' 1917' 2503' 2594' 2658' 2658' 2719' 2780' 2842' 2902' 2959' 3022' 3082' 3175' 3266' 3358' 3481' 3605' 3912' 4310' 4666'	1 45666664331111112233	1/2° 3/4° 3/4° 1/4° 1/2° 1/4° 1/2° 1/4° 1/2° 1/4° 1/2° 1/4° 1/2° 1/2° 1/2°
4800' 5104' 5719'	2	1/20

#### BIT RECORD

Company: Balcron Oil Co.

Field: Monument Butte. Lease: Federal. Well No. 33-6. Sec. 6, T9S-R17E.

Tool Pusher: Chuck Doornek. Day Driller: John Larson

Evening Driller: Joe Wipf

Morning Driller: A. E. Cook

Contractor: Molen Drilling Co.

Drill Pipe: Hughes- 45"- Type E.

Tool Joints - 4½" XH.

Length - 840.00'

Rig. No. 1. County: Duchesne

State: Utah.

Drawworks: EMSCO GB-250T.

Power: 2-Detroit 6-71 - H.P. 300.

Drill Collar-O.D. 6" I.D. 2 3/4" BHA. Pump No. 1: EMSCO, Model D-375, Stroke 14"

T.D. Date: 11-14-92

Under Surf.: 11-3-92

Spud Date: Surf. previously set

	Bit	Bit	Bit	Bit	Jet Size	Serial No.	Depth		Hours	Weight	Rotary	Vert.	Pump		Pumps		!	Mud	<u>Du</u> 1	11 (	Code	
	No.	Mfgr.	Size	Type	1 2 3	Of Bit	Out	Ftge.	Run	1000 #	R.P.M	Dev.	Press	No.	Liner	SPM	Wt	. Vis.	T	В	G	Remarks
	1RR	STC	7 7/8	F4HRR	14 14 14	KV0103	2594	2328	50 1/4	35/40	60-70	5	700	1	6	54	8 ⁴	26	2	2	I	Sing
ı	2RR	STC	7 7/8	F45RR	14 14 14	KT9847	4666	2051	86 1/4	35/40	60-70	3 1/4	800						2	2	I	Sing.
	1\$	DBS	7 7/8	CMPZI	.50	5920019	4697	24	1	20	80											Std.
	1RR	STC	7 7/8	F4HRR	14 14 14	KV0103	4800	103	4 1/2	35	65	3	850									Std.
	2 <b>∳</b> RR	DBS	7 7/8	CNPZI	.50	5920019	4842	42	2	10/20	65	3	850									Std.
	2RR	STC	7 7/8	F45RR	14 14 14	KT9847	5101	243	10	35/40	65				*							Std.
	3 <b>¢</b> RR	DBS	7 7/8	CMPZI	.50	5920019	5164	64	3 1/4	14/16	80											Std.
	2R <b>R</b>	STC	7 7/8	F45RR	14 14 14	KT9847	5740	576	23 3/4	40	65-70	2	800						2	2	I	Std.

Unibar Drilling Fluids, Inc. Representative: Gerald Ashcraft


#### DAILY DRILLING MUD REPORT

T C 6	Sample From Time Sample Taken Depth (ft) MD Weight (ppg) Funnel Viscosity (sec/qt) A.P.1. Retort Solids (% by vol)	1992 11/3 Pit 2:00 PM 484' 8.4	11/4 Pit 2:15 PM 1640' 8.4+ 26	11/5 Pit 11:45 AM 2560' 8.5 26 1.5	11/6 P1t 9:45 AM 2730' 8.5 26	11/7 P1t 11:00 AM 2945' 8.5 26	11/8 Pit 10:00 AM 3584' 8.5 26	11/9 Pit 1:00 PM 4370' 8.5 26	11/10 Pit 12:00 PM 2900* Reaming 8.5 26 1.5	11/11 Fit 9:30 AM 4695' 8.5 26 1.5	11/12 P1t 12:00 PM 4862' 8-5 26 1.5	11/13 Pit 10:30 AM 5104' 8.5 26	11/14 Pit 9:30 AM 5448' 8.5 26 1.5	11/15 Pit 10:30 AM 5740* 8.5 26 1.5
Ö	Retort Liquid (% by vol, oil/ water) ph Meter	9.7	10.0	98.5 9.7	98.5 10.2	98.5 10.2	98.5 9.7	98.5 9.9	98.5 9.7	98.5 9.7	98.5 9.7	98.5 9.5	98.5 9.5	98.5 9.5
•	Alkalinity Filtrate (P _f / M _f ) Chloride (mg/L)	.4/.7 5000	.6/.8 6500	.5/.8 7500	.8/.9 6800	.8/.9 7500	.4/.8 10.000	.5/.6 11.000	.4/.5 11,000	.4/.5 9000	.4/.5 11,000	.3/.4 11,000	.3/.4 10,500	.4/.5 12,000
	Total Hardness as Calcium (mg/L) Remarks	40	40	20 Native Water	80	120 Start To Add KCL	20	80	60	60	120	80	20	120

@ 3000°

#### BALCRON OIL CO. 33-6 MONUMENT BUTTE-FEDERAL 1832' FSL 1829' FEL, SECTION 6, T 9 S-R 17 E DUCHESNE COUNTY, UTAH

TIME / DEPTH PENETRATION CURVE



#### FORMATION TOPS

ELEVATIONS: G.L. 5267', K.B. 5278'

Formation	E-Log Top	Subsea Datum	Structural Relationship To Reference Well *
Green River	1410'	(+3868')	31' Hi
Horseshoe Bend	2200'	(+3078')	41' Hi
Douglas Creek	46281	(+ 650')	43' Hi
2nd Douglas Creek Mkr.	4876'	(+ 402')	39' Hi
Green Marker	5024	(+ 254')	39¹ Hi
Wasatch Tongue	547 <b>8'</b>	(- 200¹)	NDE
TOTAL DEPTH:	5743' L	ogger	•

#### * Reference Well

Diamond Shamrock Corp. 32-6 Allen-Federal SW½NE½ Sec. 6, T9S-R17E Duchesne County, Utah

# BOREHOLE AND SUBSEA DATUMS

Diamond Shamrock Corp. 32-6 Allen-Federal SW%NE% Sec. 6, T9S-R17E Duchesne County, Utah

K.B. 5337'

#### Formation

Green River	1500'	(+3837')
Horseshoe Bend	2300'	(+3037')
Douglas Creek	4730'	(+ 607')
2nd Douglas Creek Marker	4974'	(+ 363')
Green Marker	5122'	(+ 215')
Wasatch Tongue	NP	

TOTAL DEPTH: 5401' (Logger)

Note: Correlations provided by operator.

#### SIGNIFICANT GAS KICKS & DRILLING BREAKS

Provided By Mud Logger


Formatio	<u>'n</u>	Sample Depth	Time (Before-During-After) Min/Ft	Gas (Before-During-After)
Horsesho	" " " " Creek " "	2630-2650' 2695-2705' 2760-2775' 2925-2950' 3612-3619' 4174-4192' 4208-4226' 4658-4670' 4818-4826' 5128-5134' 5147-5151'	6.0-1.8-4.0 3.8-2.0-3.2 3.0-2.4-4.0 3.0-2.2-4.0 1.4-0.8-1.8 1.5-0.5-1.5 1.5-0.5-2.0 2.0-1.5-2.0 2.5-1.0-3.0 4.0-2.5-4.0 2.0-1.0-2.0	20-130-30 24-90-44 20-60-22 25-54-20 16-28-15 28-304-72 28-400-64 40-360-80 45-350-45 220-1080-360 420-840-200 30-150-30
Wasatch	Tongue	5636-5654'	2.0-1.0-2.0	30-133 30

#### POTENTIAL SS ZONES

Provided by Wellsite Geologist

#### E-Log Depth

2628-2648'
2696-2712'
3608-3616'
3842-3846'
4164-4187'
4202-4222'
4660-4665' (Cored)
4672-4675' (Cored)
5123-5125' (Cored)
5128-5132' (Cored)
5136-5146' (Cored)
5634-5654'



#### General Description For Core No. 1: (see previous page)

Core No. 1: Cut 30' and recovered 30' of 4" diameter whole core in the Douglas Creek interval of the Green River formation.

The top 3.5' of core consisted of very fine grained Sandstone ranging to Siltstone, which was well consolidated and moderately well sorted. Intergranular porosity is likely limited due to calcareous cement and sorting. This zone was evenly oil stained and exhibited good oil odor, some vertical hairline fracturing and only a trace of bleeding oil or gas.

The next 4.8' was dark gray, hard Shale. It was slightly calcareous and had frequent very thin even to wavy carbonaceous laminae.


Next a 4.0' Siltstone ranging to very fine grained Sandstone was penetrated. Some subtle coarsing occurred near the base in very thin moderately sloping Sandstone beds and black carbonaceous laminae. A sharp contact marked the base going to Shale. Generally dark brown oil stain was less even than the top zone, but oil and gas did bleed from bedding planes and hairline fractures. Porosity appeared fair in part and permeability was enhanced by fracturing.

Beneath this Siltstone/Sandstone zone was 15.1' of dark gray Shale. It was moderately calcareous, hard and exhibited much uneven to wavy very thin black-dark gray carbonaceous laminae.

The basal 2.6' of this core was a Shale-dolomitic Shale, which was dark brown, hard, brittle with conchoidal fracture and exhibiting some very thin carbonaceous laminae.

The intent was to take a 40' core, but the barrel jammed after making a connection.

Note the fracturing was restricted to Sandstone/Siltstone intervals. By in large this sedimentary section exhibits a low energy regime, with slow but methodic seasonal deposition, even the Sandstones are very fine grained and generally exhibit even laminae bedding, with very thin bed sets. Note the second Sandstone/Siltstone encountered did have subtle coarsing near the base in some depositional sloping very thin beds, but without cross bedding.



#### General Description or Core No. 2 (see previous page)

Core No. 2: Cut 42' and recovered 42' of 4" diameter whole core in the Douglas Creek interval of the Green River formation.

The top 2.2' of this core was medium-dark gray, with some poorly sorted Siltstone and very thin wispy laminae. Then 3.8' of dark gray, hard, brittle and generally highly calcareous and wispy laminated Shale was drilled.

Underneath this was 12.5' of Shale with some inter-mixed Silt-stone, light to medium gray, moderately calcareous with a high concentration of uneven to wispy laminae of Shale, silt and carbonaceous material.


Then 10.2' of very fine grained Sandstone ranging to Siltstone potential pay was penetrated. It was hard and well consolidated, but generally dark brown-amber oil stained, with open hairline fractures running the length of the Sandstone. Some intervals were poorly stained to unevenly stained, suggesting poor vertical matrix permeability. Fair-poor matrix intergranular porosity was noted. Near the base of this Sandstone there is subtle coarsing downward with sloping bedding planes and Shale drape.

Underneath this Sandstone was 5.7' of generally poorly sorted argillaceous Siltstone with some thin beds of Shale interspersed. No stain or show was observed.

The bottom 7.6' was predominately medium-dark gray Shale with some argillaceous Siltstone interspersed, much uneven-wispy very thin laminae are present. Also, a thin 2" soft bentonitic Shale was observed.

A 60' core was planned, but at 42' the core barrel jammed.

As in Core No. 1, the hairline vertical fracturing was limited to the Sandstone zone and the majority of cored interval represents a very low energy regime. Modest water flow is noted in the Sandstone, particularly where subtle coarsing downward in 10° plus sloping very thin beds and laminae, accompanied by Shale drape, were observed near the base of the unit.



### General description For Core No. 3 (see previous page)

Core No. 3: Cut 60' and recovered 58.5' of 4" diameter whole core in the Douglas Creek member of the Green River formation. It was assumed the bottom 1.5' was lost.

The top 22.1' was an alternating layering of Shale and Siltstone generally deposited in very thin beds and laminae, with some burrowing noted in the upper sections. No apparent shows were observed where the whole core was visually inspected.

Next a 3.5' very fine grained Sandstone was observed which was the best reservoir in this core. Although staining was generally spotty and uneven, some dark brown oil and gas did bleed mostly from some bedding planes.

Generally the next 21.4' was Siltstone ranging to very fine grained Sandstone with some Shale beds. The zone was tight in general with some spotty dark brown oil stain and a slight amount of bleeding gas and oil. Very thin bedding and laminae were common and porosity generally appeared to be poor.

The bottom 11.5' was predominately Shale with some tight Silt-stone.

Contrary to Cores 1 and 2, no hairline vertical fracturing was observed in the Sandstone intervals, although some closed fractures were present in predominately Shale near the top of the core. Again, a very low energy regime prevailed throughout almost all of this depositional sequence.

# SAMPLE DESCRIPTIONS By: Dennis C. Rehrig

Samples caught and lagged from shale shaker by Mud Loggers. Samples were examined wet, under reflected light and 2X magnification from 1000' to total depth, for porosity identification samples were dried. Sample descriptions generally tie well to drill time log. Sample quality was good unless stated otherwise in descriptions. All sample descriptions are interpretative.

1000-1030	Siltstone, generally light gray, frequently medium gray, occasionally cream, moderately-highly calcareous, moderately soft-moderately firm, medium-dark gray carbonaceous material in part, trace pyrite, some Shale, light gray-cream, soft, moderately-highly calcareous, trace pyrite. Trace Limestone, cream-white, microcrystalline, moderately firm, argillaceous in
	part.

1030-1060	Generally	as	above	with	more	Siltstone,	frequent
	glauconite	, 1	trace :	nica.			

1060-1090	Siltstone and Shale, as 1000-1030 above.
	Frequent Limestone, slightly orange-dark tan-
•	occasionally cream, microcrystalline-crypto-
	crystalline, firm-moderately firm, dense,
	possibly some silt grains interspersed.

1090-1120	Shale, medium-dark gray-brownish gray, occasion- ally light gray, moderately calcareous, sub-
	blocky to sub-platy in part, moderately firm-
	occasionally soft. Siltstone, clear-cream, firm-
	moderately firm, well consolidated, some
	glauconite and argillaceous fragments, slight
	calcareous cement. Occasional Sandstone, very
	fine grained, firm, well consolidated, no
	apparent porosity, some calcareous cement,
	moderately well sorted, sub-rounded, trace
	glauconite and argillaceous material, no show,
	fluorescence or cut.

1120-1150	Shale, Siltstone and Sandstone, as above, also frequent Limestone, slightly orange-slightly buff, microcrystalline-cryptocrystalline,
	moderately firm-moderately soft, dense, some silt grains.

1150-1180 Calcareous Shale, cream-light gray, frequently earthy-grainy, specks-streaks carbonaceous

material, moderately	firm-moderately soft.	Some
Siltstone, as above.	Frequent Limestone,	
slightly orange, as a	sbove.	

1180-1210

Siltstone, cream-white, calcareous cement, moderately well consolidated, frequently speckled with glauconite and carbonaceous material, no show, fluorescence or cut, frequent mica and pyrite. Shale, buff-tan, frequently cream-light gray, generally mottled, calcareous, moderately firm-occasionally soft, sub-splintery, some pyrite. Trace Limestone, as above.

1210-1240

As above, but more Shale with trace black Bitumen.

1240-1270

Limestone, white-cream, occasionally light gray, very slightly argillaceous in part, carbonaceous in part, microcrystalline, moderately firm, dense, some slight orange Limestone, as above. Shale, light-medium gray-tan-medium brown, subblocky, firm, moderately-highly calcareous, frequently carbonaceous, trace mica and pyrite.

1270-1300

Shale, light-medium gray, occasionally grayish brown, moderately-slightly calcareous, firm-moderately firm, sub-blocky to sub-splintery. Siltstone, cream-light gray, occasionally cream, moderately firm, generally specks of glauconite and carbonaceous material, calcareous cement, no show, fluorescence or cut.

1300-1330

Sandstone, very fine grained grading to Siltstone, clear-white, moderately unconsolidated, calcareous cement, sub-angular to sub-rounded, moderately well sorted, no show, fluorescence or cut, trace mica and pyrite, some carbonaceous material. Some dolomitic Limestone, orangish tan-tan, cryptocrystalline, firm-moderately firm, slightly argillaceous in part, dense.

1330-1390

Siltstone, clear-white, moderately calcareous cement, frequent specks glauconite and carbonaceous material, moderately firm-moderately soft, moderately consolidated-slightly consolidated, no show, fluorescence or cut. May grade occasionally to very fine grained Sandstone. Occasional Shale, light-medium gray, as above.

1390-1420

Siltstone, clear-white, moderately calcareous cement, moderately firm-friable in part, specks

glauconite and carbonaceous material, no show, fluorescence or cut, frequently grades to Sandstone, very fine grained, generally as above, moderately unconsolidated, sub-angular to sub-rounded, moderately well sorted. Shale, light-medium gray, occasionally cream, some streaks carbonaceous material, calcareous, moderately firm-moderately soft, sub-blocky.

1420-1450

Siltstone and Shale, as above. Argillaceous Limestone, 10-15%, tan-buff, occasionally medium brown, cryptocrystalline, occasionally microcrystalline, moderately firm, dense, specks carbonaceous-argillaceous material.

1450-1510

Argillaceous Limestone-limy Dolomite, tanmedium brown-grayish brown, occasionally bufforangish tan, microcrystalline-cryptocrystalline, moderately firm, some specks dark brown
carbonaceous material, no show, fluorescence or
cut, but dull yellow mineral fluorescence, dense.
Shale, white-cream-light gray, frequently
mottled-streaked with dark gray-medium dark brown
carbonaceous material, soft-moderately soft.
Siltstone, clear-light gray, looks dirty, calcareous cement, much argillaceous and/or carbonaceous material, moderately firm and moderately
well consolidated, no show, fluorescence or cut.

1510-1540

As above, but increase of limy Dolomite-argillaceous Limestone, buff-tan-medium brown-grayish brown, carbonaceous - trace Bitumen, no show, fluorescence or cut, some dull yellow mineral fluorescence, cryptocrystalline-microcrystalline, firm-moderately firm. Some Siltstone and Shale. appears to have black carbonaceous material petroliferous material, no show, fluorescence or cut.

1540-1600

Limy Dolomite, tan-medium brown, cryptocrystalline, hard-firm, sub-platy to sub-blocky in part, some carbonaceous material. Ranges to Dolomiteargillaceous Dolomite, dense, no show, fluorescence or cut. Argillaceous Limestone-argillaceous dolomitic Limestone, generally buffoccasionally cream, cryptocrystalline, moderately firm-soft, frequent carbonaceous material, dense, sub-platy in part.

1600-1660

As above, some pyrite. Some Shale, tan-medium brown-grayish brown, calcareous, soft, some carbonaceous material.

Limy Dolomite and argillaceous Limestone-argil-1660-1750 laceous dolomitic Limestone as 1540-1600 above, frequent pyrite. Limy Dolomite-Dolomite, brown-grayish brown, 1750-1840 cryptocrystalline, firm-moderately firm, argillaceous in part, dense. Argillaceous Limestone, cream-buff-light tan, cryptocrystalline, soft, marly-earthy, no show, fluorescence or cut. Limy Dolomite-Dolomite, medium gray, brownish 1840-1870 gray-occasionally medium brown, cryptocrystalline, firm-moderately firm, argillaceous in part, dense, some pyrite. Argillaceous Limestone, cream-light gray-buff, cryptocrystalline, softmarly in part-earthy in part, dense, trace pyrite, slightly bentonitic in part. Some Dolomite, clear-light As 1840-1870 above. 1870-1930 gray-light tan, amber, translucent, cryptocrystalline-amorphous, hard-firm, sharp edges, looks like chert, dense. Limy Dolomite-Dolomite, tan-medium gray-grayish 1930-1960 brown, cryptocrystalline, hard-moderately firm, argillaceous in part, dense. Argillaceous Limestone, cream-light gray, occasionally buff, marly-earthy in part, bentonitic in part, frequently streaked-mottled with medium gray carbonaceous material, cryptocrystalline in part, trace very weak dull yellow streaming cut. Limy Dolomite-Dolomite, light-medium gray-tan-1960-2050 medium brown, cryptocrystalline, moderately firmoccasionally hard, argillaceous in part, dense. Argillaceous Limestone, white-cream-buff, cryptocrystalline, soft-marly, possibly bentonitic in part, some microcrystalline disseminated pyrite. Dolomite-limy Dolomite, tan-medium brown, oc-2050-2110 casionally grayish brown, microcrystalline, hardmoderately firm, slightly argillaceous in part, no show, fluorescence or cut. Frequent argillaceous Limestone, cream-buff, light gray, cryptocrystalline, soft-marly, earthy in part, dense, some streaks carbonaceous material, some pyrite. Dolomite-limy Dolomite, generally as above, but 2110-2140 frequently medium gray-occasionally brownish gray. Dolomite-limy Dolomite, tan-medium brown, occ-2140-2170 asionally brown, occasionally amber-clear, hardmoderately firm, argillaceous in part, crypto-crystalline, dense, trace pin point vugs with spotty dark brown oil stain, dull gold fluores-cence and weak dull yellow streaming cut. Trace Siltstone, clear, some calcareous cement, glauconitic, some carbonaceous material, firm, trace show, as above.

2170-2200

Calcareous Shale, light-medium gray, firm, pyrite, sub-platy in part. Dolomite-limy Dolomite, as above. Siltstone, as above but more present, frequent spotty dark brown-black dead oil stain.

2200-2230

Dolomitic Limestone, light gray-cream-white, microcrystalline, moderately firm, dense, specks carbonaceous material. Siltstone, clear-white, calcareous cement, specks glauconite and carbonaceous material, firm, well consolidated, no show, fluorescence or cut.

2230-2260

Limy Dolomite-Dolomite, medium-dark gray-brownish gray, firm-moderately firm, slightly argillaceous in part, dense, trace pyrite, trace very weak dull yellow milky cut. Argillaceous Limestone, cream-light gray-buff, soft-marly, possibly bentonitic, cryptocrystalline, some light-medium gray carbonaceous material, trace pyrite.

2260-2350

Limy Dolomite-Dolomite, generally as above but primarily medium-dark brown-tan with similar cut. Argillaceous Limestone - generally as above but generally buff-light tan.

2350-2410

Limy Dolomite-Dolomite, dark brown-grayish dark brown, more argillaceous, moderately firm, dense, some carbonaceous material, very weak dull gold fluorescence in part, very weak dull yellow milky cut in part. Argillaceous Limestone, bufflight tan, cryptocrystaline, soft-marly, some carbonaceous material, very weak dull gold fluorescence in part, very weak dull yellow milky cut in part.

2410-2530

Limy Dolomite-Dolomite, medium dark browngrayish brown, cryptocrystalline, hard-moderately firm, argillaceous in part - carbonaceous in part, slightly dark gray - petroliferous in part, dull yellow-dull gold fluorescence in part, very weak-weak dull yellow streaming-milky cut in part. Argillaceous Limestone, tan-buff, occasionally cream, cryptocrystalline, moderately soft-soft, occasionally marly, frequently earthy, some carbonaceous material, show similar as Limy

#### Dolomite-Dolomite above.

2530-2560

Limy Dolomite, grayish tan-grayish brown, micro-crystalline-cryptocrystalline, firm-moderately firm, dense, argillaceous in part. Some Limestone, clear-white, microcrystalline, occasionally cryptocrystalline, moderately firm-soft, dense.

2560-2590

Limy Dolomite-argillaceous Dolomite, tan-medium brown, frequently dark brown-slightly black, firm-moderately firm, microcrystalline-crypto-crystalline, dense, highly carbonaceous-slightly petroliferous in part, some Bitumen, dull yellow fluorescence in part with very weak pale yellow streaming to milky cut.

Trip for bit @ 2594', did not circulate up samples.

2594-2620

Siltstone grading to very fine grained Sandstone, clear-white, calcareous cement, moderately firm, moderately well consolidated, no apparent porosity, some glauconite and black carbonaceous material. Possibly some black dead oil, trace dark brown oil stain with dull gold fluorescence and very weak dull yellow milky cut. Some pyrite. Shale, light gray-white, very calcareous, moderately firm-soft, frequently speckled with carbonaceous material, some pyrite.

2620-2650

Sandstone, very fine-occasionally medium grained, generally clear, generally loose grains to moderately unconsolidated, probably very good intergranular porosity, sub-rounded to sub-angular, moderately well sorted, frequent dark brown oil blobs, dull gold fluorescence and very good immediate bright yellow flash cut.

2650-2680

Shale, dark tan-dark brown to occasionally black, platy-sub-fissile, firm-moderately soft, very calcareous, algal laminae in part, highly carbonaceous-petroliferous, possibly some Bitumen, dull gold fluorescence in part, no cut.

2680-2710

Sandstone as 2620-2650 above with similar oil show.

2710-2740

Shale, light-medium gray, calcareous, soft-occasionally moderately firm. Siltstone grading to very fine grained Sandstone, clear-white, calcareous cement, moderately firm-friable in part, no apparent porosity, moderately well consolidated, some glauconite and carbonaceous material, no stain, very weak dull yellow fluorescence in part, very weak slow dull yellow streaming-milky cut. Limy Dolomite to argillaceous Limestone as 2410-2530 above, probably cavings.

2740-2770

Shale, light-medium gray, calcareous, soft-moderately firm, pyritic in part. Siltstone, clear-white, moderately firm-moderately friable, some glauconite and carbonaceous material. Some Sandstone, very fine-fine grained, clear-white in part, calcareous cement, some loose grains-clusters, sub-rounded to sub-angular, moderately well sorted, some good intergranular porosity, some uneven specks of dark brown oil and some dark brown globules, some dull gold fluorescence, poor dull yellow streaming cut.

2770-2800

Shale, generally as above, some grayish tan Siltstone, generally as above, frequently light gray and argillaceous.

2800-2830

Shale, light-medium gray, frequently streaked with medium dark gray carbonaceous material, calcareous, microcrystalline, disseminated pyrite, soft-moderately firm. Argillaceous Limestone, generally buff-tan, occasionally cream, cryptocrystalline, generally soft, frequently earthy, some carbonaceous material.

2830-2890

Shale, tan-medium-dark brown-occasionally black, calcareous, moderately firm-soft, some algal laminae, highly carbonaceous-occasionally petroliferous, frequently platy-sub-fissile, dull gold fluorescence in part, with very weak dull yellow milky cut. Argillaceous Limestone, buff-light tan, occasionally cream, generally soft, earthymarly in part, some carbonaceous material.

TOH @ 2912' to change BHA due to hole deviation, did not circulate out samples.

2890-2920

Shale, light-medium gray, occasionally dark gray, calcareous, moderately firm-soft. Siltstone, clear-white in part, some calcareous cement, moderately firm-friable in part, argillaceous in part. Some Sandstone, very fine-fine grained, occasional medium sized loose grains, clear-white in part, some calcareous cement in part, friable in part, moderately unconsolidated, trace dark brown oil stain, some dull gold fluorescence with weak dull yellow streaming-milky cut.

2920-2950	Shale and Siltstone, as above. Sandstone, clear-white, very fine-fine grained, moderately firm-occasionally friable, fair-poor intergranular porosity, sub-angular to sub-rounded, moderately well sorted. Frequent dark brown oil stain-droplets, dull gold fluorescence, weak-fair bright yellow streaming cut.
2950-2980	Shale, medium gray-brownish gray, moderately firm, calcareous, sub-blocky, highly pyritic. Siltstone, medium gray-brownish gray, frequently argillaceous, calcareous, moderately firm, highly pyritic.
2980-3010	Dolomite-argillaceous Dolomite, tan-grayish tan, occasionally white, firm-moderately hard, crypto-crystalline-microcrystalline, dense. Limestone-argillaceous Limestone, white-cream, occasionally buff, microcrystalline-cryptocrystalline, moderately firm-moderately soft, dense.
3010-3040	Shale, tan, medium-dark brown-occasionally black, moderately calcareous-non-calcareous, moderately firm-moderately soft, platy to sub-fissile, some algal laminae, highly carbonaceous-petroliferous, some Bitumen, dull gold-dull yellow mineral fluorescence, trace very weak dull yellow streaming cut.
3040 <b>-</b> 3070	Argillaceous Limestone, light gray-cream, frequently streaked and mottled with carbonaceous and microcrystalline disseminated pyrite, soft, generally marly. Limy Dolomite, buff-tan-grayish tan, microcrystalline-cryptocrystalline, moderately firm-moderately soft, much microcrystalline pyrite, argillaceous in part.
3070-3100	Limy Dolomite-Dolomite, cream-white-buff, very fine crystalline-microcrystalline, generally moderately firm, dense, argillaceous in part.
3100-3130	Argillaceous Limestone, white-cream-occasionally light gray, cryptocrystalline, frequently streaked with light-medium gray carbonaceous material, frequent microcrystalline disseminated pyrite, soft-moderately soft. Siltstone, clear-white, moderately firm, well consolidated, frequently speckled with glauconite and/or argillaceous material, calcareous cement.
3130-3160	Siltstone, as above grading to very fine grained Sandstone, clear-white, moderately firm, no apparent porosity, generally well consolidated,

	sub-angular to sub-rounded, moderately well sorted, trace dark brown oil stain with slight dull gold fluorescence, very weak dull yellow milky-halo cut.
3160-3190	Shale, light-medium gray, moderately soft, frequently streaked with carbonaceous material, some pyrite. Argillaceous Limestone, white-creamoccasionally buff, cryptocrystalline, generally moderately soft-soft, marly in part, carbonaceous in part, some microcrystalline pyrite, dense.
3190-3220	Dolomite-argillaceous Dolomite, medium tan-medium brown, cryptocrystalline, moderately firm-firm, sub-platy, dense. Dolomitic Limestone-argillaceous Limestone, cream-buff-occasionally light tan, generally soft, frequently earthy, cryptocrystalline, dense, frequent microcrystalline pyrite.
3220-3260	Dolomite-argillaceous Dolomite, as above. Dolo-mitic Limestone-argillaceous Limestone, increase of cream-white argillaceous Limestone, as above, marly in part.
3260-3290	Dolomite-argillaceous Dolomite, light-medium gray-tan, cryptocrystalline, moderately firm, occasionally mottled, dense, trace pyrite. Some argillaceous Limestone-dolomitic Limestone, white-cream-occasionally buff, generally soft, marly in part, cryptocrystalline, dense, some carbonaceous material and pyrite.
3290-3320	Argillaceous Limestone, generally white-cream, occasionally buff, frequently streaked or speckled with light gray carbonaceous material, crypto-crystalline, soft, marly in part, dense.
3320-3410	Argillaceous Limestone-dolomitic Limestone, white-cream-buff-tan, cryptocrystalline, some carbonaceous material, moderately soft-soft, earthy-marly in part, dense. Dolomite-argillaceous Dolomite, light-medium gray-tan, light brown, cryptocrystalline, firm-moderately firm, dense.
3410-3440	Dolomitic Limestone, tan-light brown, crypto-crystalline, moderately firm, dense, argil-laceous in part, occasionally earthy. Dolomite-argillaceous Dolomite, generally light-medium gray, occasionally grayish brown, cryptocrystalline, moderately firm, dense.

3440-3470	Dolomitic Limestone, generally as above but buff-light tan, frequently earthy. Dolomite-argillaceous Dolomite, generally as above, but generally light gray, occasionally white-clear.
3470-3530	Shale, light-medium gray, calcareous, moderately firm-moderately soft, sub-platy to sub-splintery. Some Siltstone, clear-white, moderately firm and moderately well consolidated, some calcareous cement, no show, fluorescence or cut, argillaceous in part.
3530-3560	Shale, light-medium gray-greenish gray, moderately firm, calcareous, sub-platy to sub-splintery. Limestone-argillaceous Limestone, tan-buff, moderately soft, cryptocrystalline, dense.
3560-3590	Dolomite-argillaceous Dolomite, medium brown-dark grayish brown, moderately firm-firm, crypto-crystalline, dense. Limestone-argillaceous Limestone, light-medium brown, occasionally tan, occasionally gray, streaks and specks of dark gray carbonaceous material, slightly mottled in part, cryptocrystalline, moderately firm-moderately soft, dense.
3590-3620	Sandstone, very fine grained grading to Silt- stone, clear-white, some calcareous cement, some loose grains, moderately unconsolidated, fre- quently friable, probably fair intergranular porosity, sub-angular to sub-rounded, moderately well sorted, trace dark brown oil stain with some dull gold-dull yellow fluorescence and very weak dull yellow streaming cut.
3620-3650	Siltstone, grading to very fine grained Sandstone, as above, <u>not as good a show.</u>
3650-3680	Limestone-argillaceous Limestone, medium-dark brown, frequently tan-grayish brown, crypto-crystalline, moderately firm and moderately soft, trace carbonaceous material, dull yellow mineral fluorescence, trace very weak dull yellow cut.
3680-3710	Limestone-argillaceous Limestone, generally as above but more tan color, some light-medium gray, no show.
3710-3740	Limestone-argillaceous Limestone, tan, occasion- ally buff, cryptocrystalline, moderately soft, dense. Dolomite-argillaceous Dolomite, dark tan- medium-dark brown, cryptocrystalline, moderately hard-firm, dense. Some dark brown-dark grayish

brown, slightly black in part, hard, brittle, carbonaceous in part, siliceous in part. Shale, medium-dark gray, calcareous-slightly cal-3740-3770 careous, moderately firm-moderately soft, subplaty in part. Some Limestone-argillaceous Limestone, as above. As 3710-3740 above. 3770-3800 Shale, as 3740-3770 above. Siltstone, clear-3800-383C white, calcareous cement, moderately firm, well consolidated, no show, fluorescence or cut, some specks of glauconite and argillaceous material. Limestone-argillaceous Limestone, generally 3830-3860 cream, frequently buff, cryptocrystalline, moderately soft, some carbonaceous material, dense. Some Sandstone, very fine grained, clear, occasionally white, some calcareous cement, moderately firm-frequently friable, some fair intergranular porosity, sub-angular to subrounded, moderately well sorted, trace dark brown oil stain, dull yellow to gold fluorescence, very weak dull yellow streaming cut. Shale, light-medium gray, frequently greenish 3860-3890 gray, moderately firm, sub-blocky, slightlymoderately calcareous, trace pyrite. Some Limestone-argillaceous Limestone, as above. Siltstone, clear, some calcareous cement, moderately firm, moderately well consolidated, dense, no show, fluorescence or cut. As above. Some Siltstone, clear-white, cal-3890-3920 careous cement, moderately firm, consolidated, no show, fluorescence or cut. Siltstone, clear-white, calcareous cement, 3920-3950 moderately firm-slightly friable in part, specks carbonaceous material, possible trace dead oil, trace dull yellow fluorescence, trace very weak dull yellow cut. Some Limestone, white-cream, moderately soft, cryptocrystalline, argillaceous in part, dense. Shale-dolomitic Shale, emerald green, moderately 3950-3980 soft-moderately firm, sub-blocky in part. Limestone-dolomitic Limestone, tan-buff, occasionally cream, cryptocrystalline, moderately firm-moderately soft, earthy in part, trace argillaceous material, dense.

Shale-calcareous Shale, light-medium gray, frequently cream, very fine specks and streaks argillaceous and/or carbonaceous material, moderately firm-moderately soft, sub-platy. Limestone-dolomitic Limestone, as above.

Shale, light gray-medium gray, occasionally cream, slightly-moderately calcareous, moderately firm, sub-platy to sub-splintery in part.

Shale, as above. Limestone-argillaceous Limestone, white-cream, occasionally light gray, moderately soft-soft, marly in part, cryptocrystalline, dense. Dolomite-argillaceous Dolomite, dark tan-dark brown, cryptocrystalline, moderately hard-moderately firm, dense. Trace Siltstone, clear-white, some calcareous cement, moderately firm, well consolidated, no show, fluorescence or cut.

4070-4120 Shale, as 4010-4040 above.

Mostly Shale, as above. Some Dolomite-argillaceous Dolomite, dark tan-dark brown, cryptocrystalline, moderately firm, dense. Some Siltstone, clear-light gray, firm-moderately firm, calcareous cement, frequently argillaceous, trace dark brown oil stain, faint dull gold fluorescence, trace very weak milky-very slow dull yellow cut.

Shale, as above. Some pyrite. Some Siltstone, as above. Some Limestone-argillaceous Limestone, white-clear, occasionally buff, cryptocrystalline, moderately soft, some dark grayblack carbonaceous material, dense.

Sandstone, grading to Siltstone, very fine grained, clear-light brown, moderately firm, generally friable, moderately unconsolidated, sub-rounded, moderately well sorted-poorly sorted, fair-good intergranular porosity, generally good even light-medium brown oil stain with good even dull yellow fluorescence and weak dull yellow milky-slow streaming cut, possibly some glauconite and argillaceous material.

Shale, light-medium gray, calcareous, moderately firm-moderately soft, sub-platy in part, frequently mottled or streaked with carbonaceous material, some pyrite. Limestone, in part, white-light gray, carbonaceous in part, some pyrite, cryptocrystalline, moderately soft.

4140-4160

4120-4140

4010-4040

4040-4070

4160-4190

4190-4200

4200-4210	Shale, as above. Siltstone grading to very fine grained Sandstone, clear-light brown, occasionally light gray, argillaceous in part, calcareous cement in part, firm-moderately firm, occasionally friable, generally well consolidated. Sandstone is sub-angular to sub-rounded, moderately-well sorted to poorly sorted, some fair-good intergranular porosity, some light brown oil stain with dull yellow fluorescence and very weak dull yellow steaming cut in part.
4210-4230	Sandstone, very fine-fine grained grading to some Siltstone, clear-medium brown, some calcareous cement in part, generally moderately firm-friable, moderately unconsolidated, argillaceous in part, sub-angular to sub-rounded, moderately well sorted-poorly sorted, generally fair-medium dark brown oil stain with dull yellow and fair-weak immediate dull yellow steaming cut.
4230-4240	Limestone-argillaceous Limestone, generally medium-dark brown-occasionally light-medium graytan, moderately firm-occasionally soft, cryptocrystalline, dense. Some limy Dolomite-argillaceous Dolomite, medium-dark brown, cryptocrystalline, moderately hard, dense. Trace Sandstone and Siltstone, as above.
4240-4260	Limestone-argillaceous Limestone, as above. Limy Dolomite-argillaceous Dolomite, as above.
4260 <b>-</b> 4280	Shale-calcareous Shale, cream-light-medium gray, soft-moderately soft, marly, frequently mottled with carbonaceous material.
4280-4300	Shale, as above. Dolomite-argillaceous Dolomite, medium-dark brown-grayish brown, cryptocrystal-line, moderately hard-firm, dense. Limestone-argillaceous Limestone, buff-light tan, cryptocrystalline, moderately firm-soft, marly in part, dense, trace dull yellow fluorescence with very weak dull yellow slow streaming cut.
4300-4320	Dolomite-argillaceous Dolomite, generlly as above, but tends to be darker. Some Limestone-argillaceous Limestone, as above.
4320-4340	As 4300-4320 above. Shale, dark brown-frequently grayish black, firm-moderately firm, slightly calcareous-moderately calcareous, platy to sub-fissile, highly carbonaceous-petroliferous in part, no show, fluorescence or cut.

4340-4380	Shale, light-medium gray-greenish gray, moderately firm, calcareous. Limy Dolomite, clear-white, cryptocrystalline, firm-moderately firm, frequently argillaceous, dense. Some Siltstone, clear-white, firm, well consolidated, calcareous cement, argillaceous in part.
4380-4420	Siltstone, clear, occasionally white, calcareous cement in part, trace glauconite, trace dark gray argillaceous material, firm-moderately firm, well consolidated, no show, fluorescence or cut. Trace Limestone, white, cryptocrystalline, moderately soft, dense, trace argillaceous material.
4420-4460	Shale, light-medium gray, occasionally cream, frequently speckled with carbonaceous material, moderately-highly calcareous, moderately firm-moderately soft, trace pyrite. Trace Limestone, cream-light gray, cryptocrystalline, moderately soft-soft and marly, dense, argillaceous in part.
4460-4480	Siltstone ranging to very fine grained Sandstone, moderately firm, moderately well consolidated, clear-occasionally white, moderate calcareous cement, sub-angular to sub-rounded, moderately well sorted, no apparent porosity, some glauconite and carbonaceous material, no show, fluorescence or cut. Limestone-argillaceous Limestone, tan-buff, cryptocrystalline, moderately firm-soft, earthy in part, dense. Trace Dolomite-argillaceous Dolomite, medium-dark brown-dark tan, cryptocrystalline, moderately hard-firm, dense, siliceous in part.
4480-4500	Shale, light-medium gray, slightly-moderately calcareous, moderately firm-moderately soft, sub-splintery. Some Limestone-argillaceous Limestone, cream-white, speckled with carbonaceous material, cryptocrystalline-moderately firm-soft. Trace Siltstone, as above.
4500-4520	As above with increase in Limestone-argillaceous Limestone which is carbonaceous and mottled in part.
4520-4540	Shale and some Limestone-argillaceous Limestone as 4480-4500.
4540-4560	As 4480-4500. Some Siltstone as 4460-4480 above.
4560-4580	Siltstone grading to very fine grained Sandstone, clear-occasionally white, some calcareous cement,

moderately firm, moderately well consolidated.
Sandstone is sub-angular to sub-rounded, mod-
erately well sorted, no show, fluorescence or
cut, some specks of carbonaceous material. Some
Shale as 4480-4500 above.

Shale, light-medium gray, slightly-moderately calcareous, moderately firm-soft, earthy in part.

Some Limestone, white-cream, occasionally speckled with carbonaceous material, crypto-

crystalline, moderately soft, marly in part, argillaceous in part. Trace Siltstone, as above.

Shale, medium gray-grayish brown, slightlymoderately calcareous, firm-moderately firm,
trace pyrite. Limestone-argillaceous Limestone,
white-cream, cryptocrystalline, soft-generally
marly.

Shale, dark brown-occasionally black, bronze cast in part, highly carbonaceous-slightly petroliferous, moderately firm-moderately soft, subplaty in part, earthy in part, dull yellow fluorescence, very weak dull yellow streaming cut.

Shale, light gray-greenish gray, cream in part, moderately firm-soft, frequently pyritic, sub-blocky to sub-platy in part.

Siltstone, clear-white-light gray, moderately firm, moderately well consolidated, some argillaceous material, no show, fluorescence or cut. Shale, as above.

Siltstone, light gray-buff, frequently clear-white, moderately firm, moderately well consolidated, some argillaceous material, no show, fluorescence or cut, possibly some very fine grained Sandstone. Trace Limestone, white-cream, streaks-specks carbonaceous material, cryptocrystalline, moderately firm, dense.

Sandstone, very fine grained grading to Siltstone, light tan-clear, moderately firm, slightly friable in part, some fair intergranular porosity, sub-angular to sub-rounded, moderately well sorted, generally even light brown oil stain, bright yellow fluorescence, weak dull yellow slow streaming-milky cut. Some Limestone-argillaceous Limestone, cream-light gray, argillaceous in part, cryptocrystalline, moderately firm-moderately soft.

4640-4650

4650-4655

4655-4660

4660-4666

Trip out of hole to take core.

# WHOLE CORE DESCRIPTION Core No. 1: (4666'-4696' Driller) Cut 30', Recovered 30'

- 4666.0-4669.5' (3.5') Sandstone, very fine grained ranging to Siltstone, dark brown, hard, vertical hairline fractures with oil stain, generally moderately calcareous, very little bleeding gas or oil, but generally good even dark brown oil stain and good oil odor, probable fair intergranular porosity.
- 46669.5-4674.3' (4.8') Shale, generally dark gray, hard, dense, moderately calcareous, very thin uneven-wavy dark gray-black carbonaceous laminae.
- (4.0') Siltstone-very fine grained Sandstone, 4674.3-4678.3' grades to slightly coarser sand at base where there is heavy concentration of mica, black thin carbonaceous laminae-very thin beds which are sloping approximately 10° between thin bedded sloping Sandstone. At base sharp contact, flat and smooth to Shale. No identifiable crossbedding. Moderate gas and oil bleeding from some bedding planes and hairline fractures, both oblique and vertical hairline fractures with oil stain. General tan-dark brown to dark brown oil stain is generally not even, moderately calcareous, some uneven fair intergranular porosity, but permeability may be marginal without fracturing.
- 4678.3-4693.4 (15.1') Shale, dark gray, moderately calcareous, hard, dense, much uneven-wavy very thin black carbonaceous laminae.
- 4693.4-4696.0 (2.6') Shale-dolomitic Shale, dark brown, very hard, brittle, dense, zone highly mechanically shattered and broken, frequent conchodial breaks, some very thin carbonaceous laminae.

MICROSCOPIC CORE CHIP DESCRIPTION
Core No. 1: (4666'-4696' Driller)
Cut 30', Recovered 30'

4666.0-4669.5' (3.5') Sandstone, very fine grained-ranging to Siltstone in part, generally medium-dark brown, firm-moderately firm in part, sub-rounded to sub-angular, moderately well sorted, well consolidated, slight-moderate calcareous cement,

generally <u>even da</u>	rk brown oil	<u>stain, br</u>	ight yellow
fluorescence with	weak immedi	ate <u>dull</u> y	ellow
oozing cut. Fair	-poor interg	ranular po	rosity in
part.			

- 4669.5-4674.3' (4.8') Shale, dark gray, hard-moderately hard, very slightly calcareous, some very fine carbonaceous laminae in part, generally massive homogeneous and dense.
- 4674.3-4678.3'

  (4.0') Siltstone-grading to very fine grained Sandstone, clear-generally uneven medium brown, hard-moderately hard, sub-rounded to sub-angular, moderately well sorted, generally moderate calcareous cement, well consolidated-well lithified, subtle gradation to larger size fraction near base with approximately 10° sloping bedding planes, generally bedding planes are parallel with some dark gray-black carbonaceous beds, uneven dark brown oil stain, bright yellow fluorescence and fair-weak dull yellow-bluish yellow streaming cut. Generally poor intergranular porosity.
- 4678.3-4693.4' (15.1') Generally Shale, dark gray-brownish gray, hard, dense, very slightly calcareous-highly calcareous, generally gradational with much Siltstone in top of interval interspersed in very calcareous Shale, much very fine mica in upper interval, grades to generally homogeneous Shale very low in carbonate at base, some very fine carbonaceous laminae.
- 4693.4-4696.0' (2.6') Shale, dark gray, moderate-high calcareous, much loose silt faction, some loose very fine quartz grains in part, appears well rounded. Upper interval poorly sorted, very hard and brittle, breaks with conchoidal fracture in part, some wavy-very wispy black-dark gray carbonaceous laminae.
- Shale, light gray-light brownish gray, moderately calcareous, moderately firm-moderately soft, some streaks carbonaceous material. Some Siltstone, clear-white, moderately firm, moderately well consolidated, slightly calcareous, no show, fluorescence or cut.
- 4720-4740 Shale, as above. Siltstone, as above, but more present.
- 4740-4780 Shale, light-medium gray, firm-moderately firm,

slightly calcareous, sub-blocky to sub-platy in part. Some Siltstone, as above.

Trip out of hole for core @ 4800', didn't circulate samples.

# WHOLE CORE DESCRIPTION Core No. 2: (4800'-4842' Driller) Cut 42', Recovered 42'

- 4800.0-4802.2' (2.2') Shale, medium-dark gray, moderately calcareous, hard, possibly some Siltstone, some very thin even-wispy laminae.
- 4802.2-4806.0' (3.8') Shale, dark gray, very hard and brittle, section highly broken, moderately-highly calcareous, some very thin wispy carbonaceous-argillaceous laminae.
- 4806.0-4818.5' (12.5') Shale, light-medium gray, hard, probably silty in part, moderately calcareous, no show, fluorescence or cut, very high concentration of uneven-wispy very thin laminae of argillaceous and or carbonaceous material.
- (10.2') Sandstone, very fine grained ranging to 4818.5-4828.7' Siltstone, slightly calcareous, hard, well consolidated, generally even dark brown-amber oil stain, but some sections have little to no staining, suggesting vertical matrix permeability may be low. Much bleeding gas and oil from stained sections. Good open oil stained hairline vertical fractures running throughout Sandstone interval. No real obvious grading, except near the base a thin 2-3' interval may be coarsing downward where there is a heavy concentration of mica, bed dips in excess of 10° on some very thin bed sets and laminae with sharp contact to a Shale bed drapped and generally conforming to the sand beds and argillaceous laminae.
- 4828.7-4834.4' (5.7') Generally Siltstone, light-medium gray, hard, moderately calcareous, no show, fluor-escence or cut, generally appears to be dirty with Shale intermixed and some thin homogeneous Shale beds, some very thin bedding and laminae.
- 4834.4-4842.0 (7.6') Shale, medium-dark gray, hard, slightlymoderately calcareous, some Siltstone interspersed, much uneven-wispy very thin bedding and
  laminae. At 4840.2-4840.4' Shale, brownish gray,
  soft, bentonitic, no reaction to Hcl.

### MICROSCOPIC CORE CHIP DESCRIPTION Core No. 2: (4800-4842' Driller) Cut 42', Recovered 42'

- 4800.0-4802.2' (2.2') Shale ranging to poorly sorted Siltstone, medium-dark gray, hard, dense, slightly calcareous, trace microcrystalline disseminated pyrite, some very thin carbonaceous and silty laminae.
- 4802.2-4806.0' (3.8') Shale, dark gray-occasionally black, generally very hard, brittle, generally highly calcareous and may have some replacement microcrystalline calcite crystals, some wispy very thin laminae, in which there is highly carbonaceous material and possibly some is petroliferous, some loose quartz and silt grains in part, generally sub-angular.
- 4806.0-4818.5' (12.5') Shale, light-medium gray-bluish gray, hard, dense, mica flakes in part, platy in part, slightly-moderately calcareous, some wispy bedding planes containing darker carbonaceous material and argillaceous material.
- 4818.5-4828.7'

  (10.2') Sandstone, very fine grained ranging to Siltstone in part, generally tan-light brown, slightly calcareous-moderately calcareous, hard, well consolidated, fair-poor intergranular porosity, pore openings are extremely small, some glauconite and/or heavy minerals, sub-angular to sub-rounded, moderately well sorted, generally medium brown oil stain, with some bleeding oil and gas, bright yellow fluorescence with fair dull yellow milky-halo cut.
- 4828.7-4834.4' (5.7') Generally Siltstone, light gray-occasionally gray, highly calcareous, hard, dense,
  well consolidated, no obvious bedding or thin
  laminae, some specks of glauconite and/or carbonaceous material, no show, fluorescence or cut,
  some thin beds between depositional Siltstone
  sequences of medium-dark gray Shale, hard,
  generally homogeneous, very slightly calcareous.
- 4834.4-4842.0' (7.6') Shale, medium-dark gray, hard, moderately calcareous and Siltstone, light gray-brownish gray, moderately hard, well consolidated, moderately-highly calcareous, no show, fluorescence or cut, moderately-poorly sorted, moderate amount argillaceous and some carbonaceous material. At 4840.2-4840.4' appears to be bentonitic Shale, no

	reaction to HCl medium gray, moderately firm-moderately soft when wet.
4842-4860	Shale, light-medium gray-brownish gray, moderately firm slightly-moderately calcareous. Some Siltstone, clear-light gray, moderately firm, well consolidated, slightly calcareous, argillaceous in part, no show, fluorescence or cut.
4860-4880	Shale, tan-grayish brown, moderately firm-soft, earthy in part, slightly-moderately calcareous, moderately calcareous-slightly petroliferous, trace very slight slow dull yellow milky cut, trace pyrite.
4880-4900	Shale, generally light gray, occasionally cream, moderately calcareous, generally moderately soft, sub-platy in part, some microcrystalline disseminated pyrite, show as above. Dolomitic Limestone-argillaceous Limestone, tan-buff, microcrystalline-cryptocrystalline, moderately firmfirm, dense.
4900-4920	Shale, light-medium gray, frequently cream, very slightly calcareous, moderately firm-frequently soft, marly in part. Trace Siltstone, clear-occasionally white, some calcareous cement in part, moderately firm, well consolidated, argillaceous in part, no show, fluorescence or cut.
4920-4940	As above. Some dolomitic Limestone, tan-buff, medium brown, firm-moderately soft, crypto-crystalline, slightly argillaceous in part.
4940-4960	Shale and Siltstone as 4900-4920 with increase in cream colored Shale which is generally soft and marly. Dolomitic Limestone, as above.
4960-4980	As above with increase in dolomitic Limestone.
4980-5000	Shale, generally medium gray, frequently creamlight gray, generally moderately firm, occasionally soft and marly, moderately calcareous, subplaty to sub-splintery in part, trace very weak milky cut. Dolomitic Limestone, as above.
5000-5020	Shale, dark tan-dark brown, frequent bronze cast, occasionally black, firm-moderately firm, moderately-highly calcareous, sub-platy, highly carbonaceous-petroliferous in part, weak dull yellow streaming-milky cut.

5020-5040	Shale, as above, with some medium tan-medium
	brown, soft-earthy, moderately calcareous, trace very weak slow_dull yellow streaming-milky_cut.

5040-5060

Shale, as above, with show and cream-light gray frequently medium gray-brownish gray, moderately firm-moderately soft, sub-platy in part, trace pyrite. Some Siltstone, clear-white, very hard-firm, siliceous in part, well consolidated, no show, fluorescence or cut. Some argillaceous Limestone, cream-light gray, soft-marly in part, cryptocrystalline.

Shale, tan-medium brown-grayish brown in part, moderately firm, moderately calcareous, subblocky, Siltstone, tan-medium brown, occasionally clear-white, moderately firm, moderately calcareous, well consolidated, trace dead oil no fluorescence, very weak slow streaming-milky dull yellow cut.

Trip out of hole for core @ 5104', did no circulate out samples.

### WHOLE CORE DESCRIPTION Core No. 3: (5104-5164' Driller) Cut 60', Recovered 58.5'

- 5104.0-5109.9' (5.9') Shale, medium-dark gray, moderately calcareous, hard, Siltstone in part, some very thin laminae, some apparent burrows.
- 5109.9-5119.9' (10.0') Shale and Siltstone, light-medium gray, hard, dense, heavy concentration of very thin beds, laminae, and burrows. Some relatively homogeneous Shale zones, light gray, moderately-slightly calcareous, dense, no apparent show in interval.
- 5119.9-5122.0' (2.1') Shale, mostly dark gray, hard, slightly calcareous, some Siltstone laminae at base.
- 5122.0-5126.1' (4.1') Siltstone and Shale, grayish tan-tan, slightly-moderately calcareous, hard, bottom 6" is homogeneous Shale with very thin carbonaceous laminae. Entire interval highly concentrated with very thin beds and laminae.
- 5126.1-5129.6' (3.5') Sandstone, very fine grained, tan-grayish tan, hard-moderately hard, moderately calcareous, some tight zones and some fair-good intergranular porosity. Spotty-uneven dark brown oil stain and bleeding oil and gas mostly along bedding planes.

High density	of	very	thin	beds	and	laminae.	No
fracturing.							

- 5129.6-5137.3' (7.7') Siltstone ranging to very fine grained Sandstone, grayish brown-light tan, looks tight and generally unstained, moderately calcareous, trace spotty dark brown oil stain. Much very thin bedding near base, some slight crossbedding, beds somewhat contorted from soft sediment deformation.
- 5137.3-5139.1' (1.8') Shale and some Siltstone, light-medium gray, very hard and dense, moderately calcareous, no show, fluorescence or cut.
- 5139.1-5151.0' (11.9') Siltstone ranging to very fine grained Sandstone, medium brown-grayish brown, slightly-moderately calcareous, looks tight, much very thin bedding and laminae, very slight dark brown spotty oil stain with trace bleeding oil.
- 5151.0-5158.9' (7.9') Shale and some Siltstone, light-medium gray to dark brown, slightly-moderately calcareous, hard, much very thin bedding and laminae. At base appears to be ripup clasts and some soft sediment deformation.
- 5158.9-5162.5' (3.6') Shale with possibly some Siltstone, dark gray, moderately calcareous, hard, frequent very thin laminae.

## MICROSCOPIC CORE CHIP DESCRIPTION Core No. 3: (5104-5164' Driller) Cut 60', Recovered 58.5'

- 5104.0-5109.9' (5.9') Shale, medium brown-grayish brown, moderately hard, dense, some lenses and laminae of Siltstone interspersed with laminae of Shale and carbonaceous material, very slightly-moderately calcareous, frequent burrows and some bioturbations, trace dark brown oil stain, dull yellow fluorescence and very weak dull yellow streaming cut.
- 5109.9-5119.9' (10.0') Shale and Siltstone, grayish brown,
  Shale, generally dense, hard, very slightly
  calcareous, frequently burrowed, with trace dark
  brown oil stain, no fluorescence, very weak dull
  yellow milky cut. Siltstone, generally hard, no
  apparent porosity, frequently burrowed, some dark
  brown-black dead oil stain, no fluorescence, very
  weak dull milky cut.

- 5119.9-5122.0' (2.1') Shale, medium gray, slightly calcareous, moderately hard, some very fine carbonaceous and argillaceous laminae.
- 5122.0-5126.1' (4.1') Siltstone and Shale, medium gray-brownish gray, hard, dense, very slightly calcareous, burrowed with some dark brown-black dead oil stain in part, no fluorescence, trace very weak dull yellow milky cut.
- 5126.1-5129.6' (3.5') Sandstone, very fine grained, moderately firm, sub-angular to sub-rounded, moderately well sorted, some burrows, even-uneven dark brown-black oil stain, frequent bleeding black oil, dull yellow fluorescence in part, very good immediate bright yellow flash cut, good-fair intergranular porosity.
- 5129.6-5137.3' (7.7') Siltstone ranging to very fine grained Sandstone, grayish tan, moderately firm, moderately calcareous, generally argillaceous, light tan oil stain in part, dull yellow fluorescence, with fair-weak dull yellow streaming cut, some mica. Some evidence of very fine bedding and laminae.
- 5137.3-5139.1' (1.8') Shale, medium gray-brownish gray, very hard, dense, frequent mica, some Siltstone, very slightly calcareous.
- 5139.1-5151.0' (11.9') Siltstone ranging to very fine grained Sandstone, grayish brown-medium tan, firm, frequent mica, very slightly calcareous, very poor-fair intergranular porosity, sub-angular to sub-rounded, moderately well-poorly sorted, burrowed in part, very slight tan oil stain dark brown oil stain, spotty-patchy stain in part, dull yellow fluorescence, very weak-good dull bright yellow streaming-flash cut.
- 5151.0-5158.9' (7.9') Shale, medium gray, moderately firm, some very fine laminae, Siltstone in part, moderately calcareous.
- 5158.9-5162.5' (3.6') Shale, medium gray-brownish gray in part, very slightly calcareous, moderately firm-moderately soft, some very fine carbonaceous-argillaceous laminae.
- 5163-5180 Sandstone, very fine grained ranging to Siltstone, tan-medium brown, grayish brown in part, moderately firm-slightly friable in part, sub-

	angular to sub-rounded, moderately-poorly sorted, fair-poor intergranular porosity, slightly-moderately calcareous, generally argillaceous, looks clay filled, light brown-medium brown oil stain, trace dull yellow fluorescence, weak dull yellow streaming cut.
5180-5220	Shale, medium-light gray, moderately firm-mod- erately soft, slightly calcareous, sub-blocky to sub-platy in part. Some argillaceous Limestone, cream-white, cryptocrystalline, soft, marly in part.
5220-5240	Shale, dark tan-dark brown, generally soft- earthy, moderately-highly calcareous. Shale, grayish black-very dark brown, hard, sub- platy, slightly calcareous, highly carbonaceous- slightly petroliferous, no show, fluorescence or cut.
5240-5260	Shale, light-medium gray, moderately firm-mod- erately soft, generally slightly calcareous, Limestone in part, some argillaceous Limestone, white-cream-light gray in part, mottled in part, cryptocrystalline, generally moderately firm- soft.
5260-5280	Shale, dark gray-dark brown-occasionally brownish black, firm-moderately soft, non-calcareous-slightly calcareous, sub-platy in part, highly carbonaceous.
5280-5320	Shale, black-bronze cast in part, moderately firm-moderately soft, non-calcareous, frequent microcrystalline disseminated pyrite, sub-platy to sub fissile in part, some argillaceous-carbonaceous laminae, highly carbonaceous-petroliferous, no fluorescence, very weak slow dull yellow streaming cut.
5320-5360	Shale, as above and Shale, dark brown-grayish brown, moderately soft, very slightly calcareous, some pyrite.
5360-5380	Shale, grayish black-dark brown-black, sub-platy to sub-fissile in part, slightly calcareous, hard-brittle-moderately soft, highly carbon-aceous-petroliferous, no fluorescence, very weak dull yellow streaming cut.
5380-5420	Shale, as above, also Shale, light-medium gray, moderately firm, moderately calcareous, some

	pyrite, 5400-5420' some argillaceous Limestone, tan, cryptocrystalline, moderately firm-mod-erately soft, dense.
5420-5480	Shale, black-grayish black, bronze cast in part, firm-moderately firm, very slightly calcareous, highly carbonaceous-petroliferous, pyritic in part, sub-platy to sub-fissile in part, no fluorescence, very weak slow dull yellow streaming cut, pyritic.
5480-5500	Shale, as above. Limy Dolomite, dark tan-dark brown, cryptocrystalline, moderately firm-firm, dense, argillaceous in part.
5500-5520	Shale, light gray, moderately-highly calcareous, moderately soft, Limestone in part, mottled-streaked in part, trace Siltstone. Limestone-argillaceous Limestone, white-cream-light gray, cryptocrystalline, moderately firm-moderately soft, dense.
5520-5560	Shale, light gray-cream, moderately soft-soft, moderately calcareous, trace carbonaceous laminae, trace Siltstone, clear-white, moder-ately firm-friable in part, slightly calcareous, no show, fluorescence or cut. Some argillaceous Limestone, cream, cryptocrystalline, soft, marly.
5560-5580	Shale, light-medium gray, moderately firm-mod- erately soft, slightly-moderately calcareous, sub-blocky in part. Some Siltstone, clear-white, light gray in part, slightly calcareous, argil- laceous in part, no show, fluorescence or cut.
5580-5600	Sandstone, very fine grained ranging to Siltstone, clear-white in part, slightly-moderately calcareous, slightly-moderately argillaceous, speckled with carbonaceous and/or argillaceous material in part, generally poor intergranular porosity, sub-angular, moderately-poorly sorted, some specks dark brown-black dead oil, no fluor-escence, very weak slow dull yellow streaming cut. Some Limestone, cream-white, cryptocrystalline, moderately firm-moderately soft, frequent argillaceous material, streaked-mottled in part.
5600-5620	Shale, dark brown, grayish black-black, bronze cast in part, moderately firm-moderately soft, moderately-highly calcareous, some microcrystl-line disseminated pyrite, highly carbonaceous-

petroliferous, no show, fluorescence or cut. Limestone, cream-buff-light tan, cryptocrystalline, moderately firm-moderately soft, argillaceous in part.

5620-5640

Sandstone, very fine-fine grained, clear, subangular to sub-rounded, moderately well-well
sorted, moderately firm-friable, slightly calcareous, trace very light tan oil stain, some
globules of black oil, bright yellow fluorescence, very weak dull yellow-bluish yellow
milky cut. Some Limestone, white-cream, occasionally light gray, cryptocrystlline, moderately firm-moderately soft, argillaceous in
part, good-fair intergranular porosity.

5640-5660

Sandstone, very fine grained ranging to Siltstone, generally as above, but more calcareous, tighter, Shale, light-medium gray, moderately calcareous, moderately firm-moderately soft.

Some Limestone, as above. Limy Dolomite, buff-light tan, cryptocrystalline, moderately firm-moderately soft, dense, argillaceous in part.

5660-5680

Sandstone, very fine-fine grained, slight calcareous cement, clear, sub-rounded to sub-angular, moderately-well sorted, moderately firm-friable, good-fair intergranular porosity, trace very slight light tan oil stain, bright yellow fluorescence, very weak dull yellow-bluish yellow milky cut. Some Limestone, white-cream, cryptocrystalline, moderately firm-moderately soft, slightly argillaceous in part.

5680-5700

Sandstone, very fine-fine grained, clear, slightly calcareous, moderately firm-friable, sub-rounded to sub-angular, moderately well-well sorted, trace argillaceous-glauconitic fragments, no stain, bright yellow fluorescence, minor trace dull yellow streaming-milky cut.

Possibly some black dead oil. Generally poor intergranular porosity. Some Limestone, as above.

5700-5720

Shale, dark brown-grayish black-black, moderately firm-moderately soft, highly calcareous, subplaty in part, highly carbonaceous-petroliferous, no fluorescence, weak yellow streaming cut. Limestone, cream-light gray-grayish brown, moderately-highly argillaceous, cryptocrystalline, moderately firm-moderately soft, dense.

5720-5740

Shale, light-medium gray, moderately firm, moderately-highly calcareous, Siltstone, clear-white, moderate calcareous cement, moderately firm-occasionally hard, frequently argillaceous, well consolidated, no show, fluorescence or cut.

TOTAL DEPTH: 5740' (Oriller)

#### DENNIS REHRIG & ASSOCIATES, INC.

OIL & GAS CONSULTING







**GEOLOGIC WELL LOG** 

DIVISION OF OIL GAS & MINING

NOV 3 0 1992

(406) 656-4785

4924 RIMROCK ROAD

BILLINGS, MONTANA 59106

MONUMENT BUTTE FIELD BALCRON OIL CO. 33-6 MONUMENT BUTTE-FEDERAL 1832' FSL 1829' FEL, SECTION 6, T 9 S-R 17 E DUCHESNE COUNTY, UTAH

FI EVATIONS: 5267' GL 5278' KB

SPUD: 6:00 AM (MST) 11/3/92 (ROTARY)

OUT FROM UNDER SURF. CSG.: 6:00 AM (MST) II/3/92 Surface Csg previously set)

DATE DRLG. COMP :: 10:15 PM (MST) 11/14/92

DATE WELL COMPLETED: TIME UNKNOWN II/17/92

STATUS: CASED FOR OIL COMPLETION ATTEMPT

SURF. CSG .: 271' OF 8 5/8"

PRODUCTION CSG: 5 I/2" TO 5714' KB

CORES: #I 4666'-4696' (DRLR) 466I'-469I' (LOGGER)

#2 4800'-4842' (DRLR) 4796'-4838' (LOGGER) #3 5104'-5164' (DRLR) 5100'-5160' (LOGGER)

DRILL STEM TESTS: NONE

CONTRACTOR: MOLEN DRILLING CO.

RIG: I

DERRICK: IDELA, 104' MAST (DOUBLE)

DRAWWORKS: EMSCO GB-250T, POWERED BY 2-DETROIT

6-71 300 HP DIESELS

PUMPS: EMSCO D-375 14" STROKE

DRILL PIPE: 4 1/2" OD, 2 1/4" ID, XH-THREAD

COLLARS: BHA 840.00-474.29 6" DC 8 360.71" HWP


MUD SYSTEM: FRESHWATER & KCL/WATER @ T.D.


TOTAL BITS: 2 ROTARY, AIR DRILLED FOR SURFACE CASING


TOTAL DAYS TO LOG POINT: 12 TO COMPL: 15


T.D. DRILLER 5740' LOGGER 5743'


DEALE TO ATION ... GOES WITH WAS ATOUT TONGUE



































Form 3160-5

# UNITED STATES FORM APPROVED Budget Bureau No. 1004-0135 Budget Bureau No. 1004-0135

June 1990)	DEPARTMEN	T OF THE INTERIOR	Expires: March 31, 1993
	BUREAU OF I	AND MANAGEMENT	5. Lease Designation and Serial No.
		AND DEPORTS ON WELLS	U-020252-A
		AND REPORTS ON WELLS	6. If Indian, Allottee or Tribe Name
Do not use th	is form for proposals to dri	Il or to decpen or reentry to a different reservoir. R PERMIT—" for such proposals	
	USE APPLICATION FOR	T FERMIT — For Such proposals	n/a 7. If Unit or CA, Agreement Designation
	SUBMIT	IN TRIPLICATE	7. If that of CA, Agreement Sengament
			n/a
1. Type of Well Oil Well	Gas —		8. Well Name and No.
2. Name of Operator	Well Uther		Balcron Monument Federal #33-6
EQUITABLE	RESOURCES ENERGY CO	MPANY (Balcron Oil Division)	9. API Well No.
3. Address and Telep		1	43-013-31361
	21017; Billings, MT	59104 (406) 259-7860	10. Field and Pool, or Exploratory Area
4. Location of Well (	Footage, Sec., T., R., M., or Survey De	escription)	Monument Butte/Green River
	ction 6, T9S, R17E	•	11. County or Parish, State
	-		Duchesne County, UTAH
	L, 1829' FEL		
12. CHE	CK APPROPRIATE BOX(	s) TO INDICATE NATURE OF NOTICE, REPO	ORT, OR OTHER DATA
TYPE	OF SUBMISSION	TYPE OF ACTION	<u> </u>
[X] N	otice of Intent	Abandonment	Change of Plans
	•	Recompletion	New Construction
□ s	ubsequent Report	Plugging Back	Non-Routine Fracturing
	•	Casing Repair	Water Shut-Off
F	inal Abandonment Notice	Altering Casing	Conversion to Injection
		Other <u>waterflood completic</u>	(Note: Report results of multiple completion on Well
	<u> </u>		Completion or Recompletion Report and Log form.)
13. Describe Proposed	or Completed Operations (Clearly state a	If pertinent details, and give pertinent dates, including estimated date of start call depths for all markers and zones pertinent to this work.)*	ing any proposed work. If well is directionally diffied,
Bive snoznii	ice locations and measured and true veri		
Operator	intends to complete	this well as part of our Monument Bu	tte pilot waterflood
project.	Work will be done a	is showin on the attached Waterflood I	Recompletion Procedure
and Well	Report. Work will b	pegin immediately.	Karind handler mile mile mile
		\D)\S(C	
		US ner	i C 1000
•		obica by miss 21916	1 8 1992
	0	T Utah Divicios os	•
	0	il Gae and the tare	ISION OF
			AS & MINING
	D	ate: 12/30/92	
	R	y:	
		· town	
	ν.	O	

A		
4. 1 hereby certify that the foregoing is true and correct Signed Solution Chuman	Coordinator of Environmental Tide and Regulatory Affairs	Date December 16, 1992
(This space for Federal or State office use)  Federal Approval of this  Approved by Conditions of approval, if any:  Action is Necessary	Title	Date

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

# Balcron Oil Monument Butte Federal # 33-6 NW SE Sec.6 Twn.9S Rge.17E Duchesne County, Utah

# Waterflood Recompletion Procedure

- 1.) Move in and rig up completion rig.
- 2.) Trip out of hole laying down rods and pump.
- 3.) Nipple up BOP. Circulate hole with hot 2% KCl water. Trip out with 2 7/8" tubing.
- 4.) Pick up packer assembly. Trip in hole. Set packers. Nipple up injection head. Load casing with packer chemical. Preform MIT on casing.
- 5.) Rig down and move off completion rig.

Casing:

5725', 5 1/2", 15.50 #/ft, J-55

PBTD = 5693' KB

Tubing:

148 Joints (4575'), 2 7/8", 6.4 #/ft, J-55

Rods:

120 - 3/4" X 25' Scrapered rods

60 - 3/4" X 25' plain rods

## BALCRON OIL

### WELL REPORT

WELL NAME: Balcron Monument Federal #33-6

FIELD: Monument Butte

FEDERAL LEASE NO.: U-020252A

LOCATION: NW SE Sec. 6.T9S.R17E

COUNTY/STATE: Duchesne, UT

WORKING INTEREST: 1.00

PRODUCING FORMATION: Green River

COMPLETION DATE:

INITIAL PRODUCTION: OIL/GAS PURCHASER:

PRESENT PROD STATUS:

**ELEVATIONS - GROUND: 5267** 

TOTAL DEPTH:

API NO .:

**NET REVENUE INT.:** 

SPUD DATE: 11/3/92

OIL GRAVITY:

BHT:

DATE: 7/30/92

KB: 5278' (11'KB)

0.825

PLUG BACK TD: 5693'KB

### SURFACE CASING

## PRODUCTION CASING

STRING: CSG SIZE: 8 5/8" GRADE: K-55 WEIGHT: 24 lbs. LENGTH: 258' DEPTH LANDED: 267'KB HOLE SIZE: 12 1/4"

CEMENT DATA: 161 sx 75% Class - G

& 25% Litpoz

STRING: 1 CSG SIZE: 5 1/2" GRADE: J-55 WEIGHT: 15.5# LENGTH: 5714' DEPTH LANDED: 5725'KB

HOLE SIZE: 77/8" CEMENT DATA: 226 sx Lilift &

400 sx Class - G

CEMENT TOP AT:

### **TUBING RECORD**

SIZE/GRADE/WT.: LENGTH:

NO. OF JOINTS:

TUBING LANDED AT:

TUBING ANCHOR:

SEATING NIPPLE:

PERF. SUB:

MUD ANCHOR:

PACKER:

**PERFORATIONS** 

Schlumberger

4658'-4666' 4 holes

4672'-4676' 2 holes

4814'-4824' 6 holes

# SUCKER ROD RECORD

ACID JOB

4814'-4824' Spot 250 gal 15% HCl Acid, BD @ 2300, Avg. 5.5 STBPM @ 1690psig, ISIP @ 740psig.

4658'-4676' Spot 250 gal 15% HCl Acid w/10 ball sealers, BD @ 4550, 5.5 BPM @ 1800psig,

Good ball action, ISIP @ 950psig.

PUMP SIZE:

STROKE LENGTH:

PUMP SPEED, SPM: PUMPING UNIT SIZE:

PRIME MOVER:

FRAC JOB

Frac w/Western @ 32 BPM @ 2900psig, ISIP @ 1850psig,

5 min @ 1550psig, 10 min @ 1340psig, 15 min

@ 1020psig.



P.O. Box 21017 1601 Lewis Avenue Building Billings, Montana 59104 (406) 259-7860

December 30, 1992

Bureau of Land Management 170 South 500 East Vernal, UT 84078

Gentlemen:

RE: Balcron Monument Federal #33-6

NW SE Section 6, T9S, R17E Duchesne County, Utah

Enclosed is a sundry notice reporting a spill on the referenced well.

Sincerely,

Bobbie Schuman

Coordinator of Operations,

Environmental and Regulatory Affairs

/rs

Enclosure

cc: State of Utah; Division of Oil, Gas, & Mining

JAN 0 4 1993

DIVISION OF OIL GAS & MINING Form 3160-5 (June 1990)

# UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

# SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.

Use "APPLICATION FOR PERMIT—" for such proposals

FORM APPROVED							
Budget Bureau No. 1004-0135							
Expires: March 31, 1993							

5. Lease Designation and Serial No. U-020252-A

				_		
6.	Iſ	Indian,	Allone	or	Tribe	Name

n/	a		

		7. If Unit or CA, Agreement Designation
SUBMIT	IN TRIPLICATE	n/a
. Type of Well  X Oil Gas Well Well Other		8. Well Name and No. Balcron Monument Fed. #33-6
. Name of Operator  EQUITABLE RESOURCES ENERGY CON	MPANY	9. API Well No. 43-013- 31361
P.O. Box 21017; Billings, MT Location of Well (Footage, Sec., T., R., M., or Survey De NW SE Section 6, T9S, R1	escription)	10. Field and Pool, or Exploratory Area  Monument Butte/Green River  11. County or Parish, State
1832' FSL, 1829' FEL		Duchesne County, UTAH
2. CHECK APPROPRIATE BOX(	s) TO INDICATE NATURE OF NOTICE	E, REPORT, OR OTHER DATA
· TYPE OF SUBMISSION	<del></del>	FACTION
Notice of Intent    Notice of Intent	Abandonment Recompletion Plugging Back Casing Repair Altering Casing Other OTI Spill	Change of Plans  New Construction  Non-Routine Fracturing  Water Shut-Off  Conversion to Injection  Dispose Water (Note: Report results of multiple completion on Well Completion on Recompletion Report and Log form.)
Clardy state a	Il pertinent details, and give pertinent dates, including estimated	date of starting any proposed work. If well is directionally drilled,

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. It was a give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

At oil spill occurred at 6:30 a.m. on 12/30/92 at this well. Cause was due to the well blowing back out. Approximately 30 BO was spilled. All remained at the wellhead. The oil will be shoveled into a tank and hot oiled. We anticipate total recovery of the oil.

The following were notified by telephone 12/30/92:

Benna Muth, Vernal Bureau of Land Management Frank Matthews. Utah Division of Oil, Gas, & Mining



DIVISION OF

Signed Schuman	Coordinator of Environmental Tile and Regulatory Affairs	Date December 30, 1992
(This space for Federal or State office use)		
Approved by	Title	Date

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

FORM 8			STATE	OF UTAH	ı			M P			الاستخداد	F			
	DIVI	SION	OF OIL	., GAS	AND N	1IN U	AU -	Í	1 1 J	-	FL	.S# U-	-0202!		
	MPLETION	4 OR	RECO	MPLET	ION	REPC	ORT	A٨	ID LO	G	6. LF		4. ALLO	TTEE OR TRI	BE NAME
In. TYPE OF WE	W	X	GAS WELL		AT 🗌	Other					7. 01	IT AGR	EEWEN	EMAK T	
L TYPE OF COM		[	PLUG	DIF	्वि	3	13	77	VIR	n	S. FA	AM OR	LÍASE	NAME	
2. NAME OF OPERA					1	5		<del>4,</del> 6	3 5		L			ument Fede	eral
EQUITABLE RE	ESOURCES ENER	RGY COM	PANY		110	CC	. 0	2 4	007	2	┙"	ell no. 33–6	•		
P.O. Box 210	017, Billing	js, MT	59104	····		137	3 2	4 1	773 		10. 7	IELD A		L, OR WILDCA	_
At surface	1832' FSL,			accordance	e with ar	DIV								tte/Green	
At top prod. In	iterval reported b		I LL		O				INING			R AREA			
At total depth											N.	ISE S	ectio	on 6, T9S	. R1 <i>7</i> E
			•	14. AP		24.064	,		ISSUED		12. c	TTKOO		13. STAT	z
15. DATE SPUDDED	16. DATE T.D.	REACHED	IT. DAT	E COMPL.	3-013-0 (Ready )		18		-25-92 Vations (c	r. 151		ouches		Uta ELEV. CASING	
10-24-92	11-15-9		1	2-1-92	600000			52	67.7' GL	<u>.</u>					
20. TOTAL DEPTE. MD	1	6931	T.D., MD A	770 22	HOW H		OMPL.	•	23. INT	LED BY	Sfc.	. TD	LS	none	OLE
24. PRODUCING INTE	EVAL(S), OF THE	COMPLE	T10 H T01	P. BOTTOM.	NAME (	MO AND	TVD)		<u> </u>	<del>-&gt;</del>	1010.	- 1:5	2:	SURVET M	
Green River	46581-48241			,	zS	07							r	no	
26. TYPE ELECTRIC	AND OTHER LOGS	EGN		CB(	16R	CLL	27	AS VEL	L CORED Y	ESIX) NO	C (Submit			e back	<del></del>
Array Induct	tion Log, FDC	CNL-G		my		06	DI	IILL ST	TEM TEST Y	ES   100	[]  See	ree sidel		- Duck	
CASING SIZE	WEIGHT, LE	/57.	CAS DEPTH 31	ING RECO		LE SIZE		aet i		ENTING	RECORD			AMOUNT P	GLLED
8-5/8"	24#		256'		12-1	<i>  [</i> [!!		15	1 sxs "(	a" wit	h addi	tives		none	
5-1/2"	15.5#		5714'		7-7	7/8"		95	5 sxs Hi	lift	and 40	n sys			
	10.0//		<u> </u>			70					ditive			none	<del></del>
29.	TOP (MD)	<del>,                                    </del>	RECORD	SACES CE	WENT	SCAF	(M)		30.		TUBING				
n/a		-		31643		JCAL	(2)		2-7/8		4575		<u>")</u>	n/a	(MD)
31. PERFORATION RE	CORD Unterval	156 074 7	lum heel												
4658'4666' -	- 4 holes					32.	THI E		ID. SHOT.					EEZE. ETC.	
4672'-4676' 4814'-4824'						4558				500	gallons 15% HCL				
	- o notes 'casing guns									6210	0# 16/	30 sa	nd		
						-						<del></del>	·····	· · · · · · · · · · · · · · · · · · ·	
DATE FIRST PRODUCT	ION PROD	UCTION M	ETROD ()	lowing, ga		OUCTIO		ind to	une of our					(Producing	
n/a		.bbed	,						, pc 0, pan	.,,		*Atu	t-in)	SI	ar .
DATE OF TEST	BOURS TESTED		EE SIZE	PROO'N		011			GA5		. 1	r-89L	•	GAS-OIL RATE	5
12-1-92 PLOW. TUBING PRESS.	CASING PRESSU	RE CAL	n/a	011-8		5	GAS1	4CP.	not mea	SUPEC		<u>5</u>	OIL GI	LAVITY-API (C	ORE.)
			HOUR BAT		)						30				·
140]] SI _ Wi	11 probably	-			rtion "	ا [مر					1	withes Plunk			
35. LIST OF ATTACE		DE COIN	vei læu	w mile	CIUII V	ACIT.		<u></u>	<del></del>		I VI	TUNK	CUL		
36. I hereby certify	that the forerol	ag and a	ttached in	formation	le comp	ete and	COFFE	CT EA	determine	d from	ail ave	iable -	ecord.		
36. I hereby certur	Allio -	This	mas	4					nvironi Affair			(1	~	117/02	
SIGNED 40	bie Schuman	Ju	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	TIT	LE	anu K	-yu i c	iwi )	, Aliail	<u>.                                    </u>	<del></del> -	DATE	/لم	1/1/1/	

## INSTRUCTIONS

This form should be completed in compliance with the Utah Oil and Gas Conservation General Rules. If not filed prior to this time, all logs, tests, and directional surveys as required by Utah Rules should be attached and submitted with this report.

ITEM 18: Indicate which elevation is used as reference for depth measurements given in other spaces on this form and on any attachments.

ITEMS 22 and 24: If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

ITEM 29: "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

ITEM 33: Submit a separate completion report on this form for each interval to be separately produced (see instruction for items 22 and 24 above).

and all dril	ortant zones 1-stem tests	of porosity , including d and shut-in p	38. GEOLOGIC MARKERS				
<u>Formation</u>	Тор	Bottom	Description, contents, etc.	Name	Top  Meas. Depth   True Vert.Depth		
			No DSTs run.		c Report to be separately.		
			Cores #1: 4666'-4695' Recovered 29'. Cores #2: 4800'-4842' Recovered 42'. Cores #3: 5104'-5164' Recovered 59-1/2'				

BALCRON MONUMENT #33-6 43-013-3136/

Location: NW SE Section 6, T9S, R17E

Duchesne County, Utah 1829' FEL 1832' FSL

PTD: 6,200' Formation: Top of Wasatch

Green River Prospect
Elevations: 5267.7' GL
Contractor: Molen Rig #1
Operator: Balcron Oil

Spud: 10-24-92 @ 1 p.m. Casing: 8-5/8" @ 256' GL

5-1/2" @ 5713.92' Tubing: 2-7/8" @ 4574.97' KB

•

--TIGHT HOLE--



FEB 2 2 1993

DIVISION OF OIL, GAS & MINING

10-14-92 Move pipe line over to West side of location.

10-16-92 Start location.

10-20-92 Finish location.

10-23-92 MI Parker Air Drilling rig.

10-24-92 Spud @ 1 p.m. 10-24-92 & start drilling. Made 130' in 8" hole.

10-25-92 Drill to 260' w/8" bit. POOH & get ready to ream 12-1/4".
DC: \$10,495 CC: \$10,495

10-26-92 Got 12-1/4" hole reamed to 140'.

10-27-92 Reamed 12-1/4" hole to 260'.

10-28-92 Pull drill stem & lay it down. Run 6 jts 8-5/8" csg & cmt w/Dowell. 3 centralizers & wood plug. Csg set @ 256' GL. Cmt w/161 sxs 75-25% w/2% CCL & 1/4#/sx Celoflake. 10 bbls cmt back & did not fall down hole. Plug down @ 2 p.m. 10-28-92. DC: \$7,880 CC: \$18,375

10-30-92 Drill rat hole & mouse hole. RD Parker air drilling & move off.

11-1-92 Present Operation: Prepare to move rotary on.
Put pit liner in pit & start hauling wtr.
DC: \$3,700 CC: \$22,075



DIVISION OF OIL, GAS & MINING

BALCRON MONUMENT #33-6 Location: NW SE Section 6, T9S, R17E Duchesne County, Utah

--TIGHT HOLE--

11-3-92 TD: 306' (35') Day 1 Formation: Duchesne MW fresh wtr

Present Operation: Drilling

MIRU, weld on csq head & NU BOP. Test BOP & manifold to 2000#. Test csg to 1500# - OK. PU drill collars & drill cmt. Drill new hole.

DC: \$4,327 CC: \$22,702

11-4-92 TD: 1,337' (1,031') Day 2 Formation: Duchesne MW 8.4 VIS 26 pH 9.7

Present Operation: Drilling Drill, survey, & clean on rig.

DC: \$14,756 CC: \$37,458

11-5-92 TD: 2,420' (1,083') Day 3 Formation: Horseshoe Bench

MW 8.4 VIS 26 pH 10 Present Operation: Drilling

Drill, survey, work on mud pump, replace pony rod, & both

swabs.

DC: \$14,776 CC: \$52,234

11-6-92 TD; 2,715' (275') Day 4 Formation: Green River MW 8.5 VIS 26 pH 9.7 Present Operation: Drilling

Drill, survey, hole getting crooked, out to 5-1/4° @ 2596'. TOH, bit OK. WO IBS, TIH w/pendulum assembly. Drill & survey. Weight 10-1500# on bit, 85 RPM. Did not get over the drilling nipple gas.

DC: \$5,686 CC: \$57,920

11-7-92 TD: 2,912' (197') Day 5 Formation: Green River MW 8.5 VIS 26 pH 10.2 Present Operation: Trip

Drill w/15000# on bit & 85-90 RPM. Drill & survey. Trip

to remove TBS @ 2912', making dog leg.

DC: \$4,293 CC: \$62,213



DIVISION OF OIL, GAS & MINING

BALCRON MONUMENT #33-6
Location: NW SE Section 6, T9S, R17E
Duchesne County, Utah

--TIGHT HOLE--

TD: 306' (35') Day 1
Formation: Duchesne
MW fresh wtr
Present Operation: Drilling
MIRU, weld on csg head & NU BOP. Test BOP & manifold to
2000#. Test csg to 1500# - OK. PU drill collars & drill
cmt. Drill new hole.
DC: \$4,327 CC: \$22,702

11-4-92 TD: 1,337' (1,031') Day 2
Formation: Duchesne
MW 8.4 VIS 26 pH 9.7
Present Operation: Drilling
Drill, survey, & clean on rig.
DC: \$14,756 CC: \$37,458

11-5-92 TD: 2,420' (1,083') Day 3
Formation: Horseshoe Bench
MW 8.4 VIS 26 pH 10
Present Operation: Drilling
Drill, survey, work on mud pump, replace pony rod, & both swabs.
DC: \$14,776 CC: \$52,234

TD; 2,715' (275') Day 4
Formation: Green River
MW 8.5 VIS 26 pH 9.7
Present Operation: Drilling
Drill, survey, hole getting crooked, out to 5-1/4° @
2596'. TOH, bit OK. WO IBS, TIH w/pendulum assembly.
Drill & survey. Weight 10-1500# on bit, 85 RPM. Did not get over the drilling nipple gas.
DC: \$5,686 CC: \$57,920

11-7-92 TD: 2,912' (197') Day 5
Formation: Green River
MW 8.5 VIS 26 pH 10.2
Present Operation: Trip
Drill w/15000# on bit & 85-90 RPM. Drill & survey. Trip
to remove TBS @ 2912', making dog leg.
DC: \$4,293 CC: \$62,213



FEB 2 2 1993

DIVISION OF OIL. GAS & MINING

## DAILY OPERATING REPORT

BALCRON MONUMENT #33-6
Location: NW SE Section 6, T9S, R17E
Duchesne County, Utah

--TIGHT HOLE--

11-8-92 TD: 3,481' (569') Day 6
Formation: Green River
MW 8.5 VIS 26 pH 10.2
Present Operation: Run survey.
Finish trip & start to drill w/25000# weight & 65-70 RPM,
survey, clean & paint on rig. Increase weight to 35000#.
Background Gas - 30-50 units. Connection Gas - 110
units.
DC: \$8,397 CC: \$70,610

11-9-92 TD: 4,196' (715') Day 7
Formation: Green River
MW 8.5 VIS 26 Ph 9.7
Present Operation: Drilling
Drill, survey, clean on rig, & paint. Background Gas 40 units.
DC: \$10,305 CC: \$80,915

11-10-92 TD: 4,666' (470') Day 8
Formation: Green River
MW 8.5 VIS 26 pH 9.9
Present Operation: Cut drill line.
Drill,s urvey, circ btms up, TOH to PU reamers. TIH part
way & cut drill line.
DC: \$7,775 CC: \$88,690

11-11-92 TD: 4,695' (29') Day 9
Formation: Green River
MW 8.5 VIS 26 pH 9.7
Present Operation: TIH w/bit.
Cut drill line & start reaming. Ream dog leg & wash to btm to clean hole. TOH & PU core barrel. Tripping & start coring @ 4666', cut 29' & make connection & core barrel jammed. TOH & LD 29' of core. Stand back core barrel. Start in hole.

11-12-92 TD: 4,862' (167') Day 10
Formation: Green River
MW 8.5 VIS 26 pH 9.7
Present Operation: Work on drawworks.
TIH to drill. Drill to 4800' & TOH for core #2. TIH
w/core barrel. Core 42' & jammed. TOH & LD core.
Recover 42', 10'-12' good sand. Stand core barrel back
& TIH to drill. WTB & drill. Work on rig.
DC: \$6,496 CC: \$100,001



FEB 2 2 1993

4

## DAILY OPERATING REPORT

DIVISION OF OIL, GAS & MINING

BALCRON MONUMENT #33-6

Location: NW SE Section 6, T9S, R17E

Duchesne County, Utah

--TIGHT HOLE--

11-13-92 TD: 5,104' (242') Day 11
Formation: Green River
MW 8.5 VIS 26 pH 9.7
Present Operation: TOH for core bbl.
Replace bearing on main shaft in drawworks. Drill to 5104', cdrop survey & start out of hole. Smith bit #KV0103, 207-1/2 hrs, 6871 feet in 4 holes.
DC: \$5,369 CC: \$105,370

11-14-92 TD: 5,370' (266') Day 12
Formation: Green River
MW 8.5 VIS 26 pH 9.5
Present Operation: Drilling
TOH & PU core bbl. TIH & start coring @ 5104', cut 160'
to 5164'. TOH & LD core, recover 58-1/2". LD core bbl
& TIH w/bit. Go to drilling.
DC: \$18,215 CC: \$123,585

11-15-92 TD: 5,740' (370') Day 13
Formation: Green River
MW 8.5 VIS 26 pH 9.5
Present Operation: Logging
Drill, circ for logs, drop survey. TOH WO Schlumberger logging. HCL on location @ 6 a.m.
DC: \$8,305 CC: \$131,890

11-16-92 TD: 5,740' (0') Day 14
Formation: Green River
Present Operation: Nipple down BOP.
Log w/Schlumberger, let HLS run high resolution induction
log. TIH & LD drill pipe & collars. Run 5-1/2" csg &
cmt. Clean tanks, nipple down. 20 centralizers, 5-1/2"
she joint & shoe; float collar; 125 jts 5-1/2", 15.5, K55 csg; csg set @ 5713.92'. Cmt w/226 sxs hilift & 400
sxs Class "G". Plug down @ 4 a.m.
DC: \$67,128 CC: \$199,018

11-17-92 Present Operation: Move off.

ND BOP. Set slips, cut off csg. Move rig off.

DC: \$16,540 CC: \$215,558



DIVISION OF OIL, GAS & MINING

BALCRON MONUMENT #33-6

Location: NW SE Section 6, T9S, R17E

Duchesne County, Utah

--TIGHT HOLE--

- 11-18-92 Completion
  Weld on bell nipple & install tbg head. Set anchors.
  Start leveling location w/road drag.
- 11-19-92 Completion
  Finish cleaning & get location ready for pulling unit.
  DC: \$2,808 CC: \$218,366
- 11-24-92 Completion
  MI pulling unit & RU. Nipple up BOP. Move circulating unit & frac tanks to location. Fill tank on circ unit w/2% KCL wtr. PU bit & craper & run 2-1/2" tbg. Find PBTD @ 5691'. Circ hole w/2% KCL wtr. POOH & get ready to perf in a.m. SWI & SDFN.
  DC: \$12,757 CC: \$231,123
- 11-25-92 Completion RU Schlumberger & run collar & bond log. Perf w/4" csg 4658'-4666', 4 holes, 4672'-4676', 2 holes, 4814'-4824' 6 holes. Run bridge plug & packer. Break down perfs 4814'-4824' w/250 gal HCL. Spot acid & break down @ 2300#. Pump in @ 5-1/2 bbls/min @ 1690#. Move plug & packer up to perfs @ 4658'-4676'. Spot 250 gal HCL & drop 10 RCN balls. Break down @ 4550# down to 1900#. Get good ball action up to 2800#. Shut down & surge ball off. Get 5-1/2 bbls/min @ 1800#. RD Dowell dowj & move plug below perfs & set packer above perfs @ 4600'. & SDFN. Instant shut down pressure on btm perfs 740#, instant shut down pressure on top perfs 950#. CC: \$237,528 DC: \$6,405
- 11-26-92 Well shut-in.
- 11-27-92 Completion
  TP 175#, FL 2300'. Swab well down approximately 50% oil. Make 1 swab pull per hr for 5 hrs. Get 150' per hr. Leave a plug in hole, fill tbg w/wtr & release packer & POOH. get ready for frac in a.m. SWI & SDFN. Recover 14 bbls oil & wtr.
  DC: \$3,152 CC:\$240,680



FEB 2 2 1993

6

### DAILY OPERATING REPORT

DIVISION OF OIL, GAS & MINING

BALCRON MONUMENT #33-6

Location: NW SE Section 6, T9S, R17E

Duchesne County, Utah

--TIGHT HOLE--

11-28-92 Completion

RU Western Company & frac well. All went very good. Average treating pressure 2900#, average rate 32 bbls/min. ISDP - 1850#, 5 min, 1550, 10 min 1340, 15 min 1020.. Total fluid pumped 610 bbls. SWI & SDFN. Got 3" of snow.

DC: \$23,583

CC: \$264,263

11-29-92 Completion

Well on slight vaccumn. TIH w/plug catcher, 1 jt tbg & packer. Tag sand @ 4530'. Circulate sand out & circ hole clean to bridge plug @ 4855'. Pull 10 jts & set packer @ 4510', end of tbg @ 4550'. RU swab & start swabbing. Swab 4 hrs & recover 105 bbls oil & wtr 50% oil. Has enough gas to blow fluid off swab when stop @ top. Last 2 pulls - 20 min apart, had 500' fluid each pull. SWI & SDFN. Swab 105 bbls oil & wtr.

DC: \$4,375

CC: \$268,638

11-30-92 Completion

TP - 65#, FL - 1300'. Swab 30 bbls. 80% oil making a big mess. Release packer & retrieve bridge plug. TOOH, TIH w/roduction tbg. SWI, get flat tank emptied & cleaned. SDFN.

DC: \$2,030

CC: \$270,668

12-1-92 Completion

RD BOP, flange up wellhead. Run pump & rods. Space out pump, pressure test to 800# - OK. RD pulling unit & move off. Tbg detail: 1 jts 2-7/8", J-55 tbg - 31.15'; perf sub - 3'; seating nipple - 1'; 147 jts 2-7/8", J-55 tbg - 4527.97'; KB - 12'; tbg landed @ 4574.97' KB. Rod detail: Polish rod 1-1/4 x 20; 3/4 subs 6', 6', 4', 4', 2'; 3/4 slick rods - 60; 3/4 metal scraper rods - 120; 2-1/2" x 1-1/4" x 20 top holddown pump.

DC: \$4,310

CC: \$274,978



# United States Department of the Interior AMERICA

# TAKE PRIDE IN AMERICA

IN REPLY REFER TO:

# BUREAU OF LAND MANAGEMENT

Vernal District Office 170 South 500 East Vernal, Utah 84078

FAX (801) 789-3634

Phone (801) 789-1362

# MECHANICAL INTEGRITY PRESSURE TEST CASING/TUBING ANNULUS

Company 1	Name: Ba	loron Oil	<i>!</i>		e: <u>/-7</u> -		
Well Name	e: <u>A/len P</u>	Federal	#33-6	Pormit No	· <u> </u>	020252 A	
Field Na	ne: Mon	ument B		Coun	ty: <u><i>Du</i></u>	chesne	
	ation: _//		Sec (	т <u> </u>	95	_ R	<u> </u>
Well Type		ER ~	2H	Othe:	r:		
		e Notes	Relow	Tota	l Depth:		
Dagkor S	at at (den	th):		FT			
Facker D	Casing Siz	e: 85/2", K	-55- 24#	From: 258	G.L. FT	to Surface	e FT
Surface (	ize. 5%"	J55 , 15.	r# Fr	om: <u>57/4</u> G	FT	to Surface	e_FT
Casing 5	:20: <u>37/2-</u>	755 , 6.5#	Tubing P	ressure du	ring Tes	st: <u>0</u>	psig
			am/pm)				
Time of				4464		L 70 KH 201	1 401 ml
FILLIA IN	Annulass <u>C</u>	hampion Chem Test #1	veal, Cortro	7 7 2 3 8 3 M/X Test #2	vea sogat	Not	es:
1345-	0 Min:	400	_ psig			Fackers?	
	5	600	_ psig		psi	g Set @ 470	Sef -!
	10	600	_ psig				
	15	1000	_ psig			g @ ARROW	3nap 3 e 4633'K.
	20	600	_ psig		psi	9	7633 111
	25	600	psig		psi		
	30	600	_ psig		psi	g	
	35	600	_ psig		psi	g	
lote:	40	<u></u>	_ psig	k in the second	psi	g	•
mbrent temp	45	599	psig		psi	g This we	11
rocced 30°	5.0	<u> 598</u>	psig		psi	g mis we	n was
uring this	55	598	psig		psi	g capped	and to
uring this	60	598	psig		psi	g diesel f	freeze
/9 95 -	C. 33	% loss in 1	hr.		1		55%
		: Allniter		211100 -	Pat lu	Usener	

Test Conducted by: Allniter Hot Oil Service - Pat Wisener
Inspected by: John Jelliti - Balcron Jerry Barnes - B.L.M.
Others Present:

# REPORT OF WATER ENCOUNTERED DURING DRILLING - FORM 7

1. Well name and number: Balcron Monument Federal # 33-6 API number: 43-013-31361							
2. Well location: QQ NW SE section 6 township 9S range 17E county Duchesne							
3. Well operator: BALCRON OIL Address: P.O. Box 21017 phone: (406) 259-7860 Billings, MT 59104							
4. Drilling contractor: Molen Drilling Address: P.O. Box 2222 phone: (406) 252-2591 Billings, MT 59103							
5. Water encountered (continue on reverse side if necessary)							
Depth Volume Quality from to (flow rate or head) (fresh or salty) No measurable water encountered during drilling opprations.							
RECEIVE)							
FEB 2 2 1993							
OIL, GAS & MINING							
6. Formation tops:  See Geologic Report sent separately.							
If an analysis has been made of the water encountered, please attach a copy of the report to this form.							
I certify that this report is true and complete to the best of my knowledge.							
Name Bobbie Schuman Signature Sobbie Schuman  Title Coordinator of Environmental Date 2/17/93  and Regulatory, Affairs							

Comments:

· WELL PROFILE	Casing Liner				Tuk	oing				
		ERATOR DIVERON OIL CO	<u> </u>	J9		וני				
	1	LL # MONUMENT FED 33-6	SIZE	5/2		2/8				
	i .	LD MONUMENT BUILS	WEIGHT	15.5		6.4				
	ŀ	INTY DUCIESUS	CDADE	J-55		) }\$\$				
	STA	STATE DIMIT								
	DA	TE 12-31-92	THREAD			Bend				
		☐ NEW COMPLETION ☐ WORKOVER	DEPTH	TD						
	ITEM	EQUIPMENT AND SER	110CC			<del>                                     </del>				
	NO.				(B 10)					
		150 5TS J-55 TUBING 27/8		46	21.85	1	0'			
	2	27/8 STANDARD PUMP SEATING N	ipple.	<del></del> .		1	1.85			
	3 4	ARROWSNAP 2 PACKER 27/8 EUE X 23/8 EUE X-OVER	· · · · · · · · · · · · · · · · · · ·		3.35					
	5	2 575 JSS 23/8 TURING			40 2.77					
		I KOMM SIDE POCKET MANDREL			1.35					
	7_	2 STS 238 J-SS TOBING		(	2.30	1				
	8	51/2 x 23/8 ARROWSST 1					S1.8			
	9	2 275 23/8 2-55 TUBILIZE	·		2.64					
	10	KIBMM Sids Pocker MANDERL				1	54.96			
	11	1 JUT 23/8 J-55 TUBING			31160					
2	12	23/8 X-H BOLL Plug			1 50	ı	1			
1632						48	15,41			
4658 + 5										
1:40%   17:11   2.11										
			·							
7										
4768 B				· · · · · · · · · · · · · · · · · · ·		<u> </u>				
4814 9		2, 1				ļ				
	<u> </u>	INJECTION VALVE WITH 3/8" OR	FACE			-				
			. '		·	-				
				·						
	COM	MENTS:				<u> </u>				
	COM	MENTS								
<u>k-1-i-1-</u> 12:-		SN @ 2.25" ID			**-					
			~~~							
		Packers set in compr	ession							
	<u></u>									
	ļ	.								
	ALL	DEPTHS ARE TO TOP of T	2005							
	PREP	ARED BY . OFFICE	· · · · · · · · · · · · · · · · · · ·	PH	ONE					
	L	Mady Lenline Office North	۲	8	01-7	89.	121			
		U								

n 1,50 00

e contra

MOURITAIN
STATES
OIL 10015



Form 3160-5 (June 1990)

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

IAP 0 1 1993

DIVISION OF

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

		137. p.1. C			
5.	Lease	Designation	and	Serial	No.

					_		-	
NDRY NOTICES	AND	REPORTS	ON	WELDA-	GAS	&	MINII	١

U-020252A
6. If Indian, Allottee or Tribe Name

	6. If I
Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.	n/a
LICE HARRISCATION FOR REPMIT—" for such proposals	,

n/a

SUBMIT IN TRIPLICATE				
njection COMPANY Balcron Oil Division	8. Well Name and No. Balcron Monument Fed. 33-6 9. API Well No. 43-013-31361			
3. Address and Telephone No. P.O. Box 21017; Billings, MT 59104 (406) 259-7860 4. Location of Well (Footage, Sec., T., R., M., or Survey Description) NW SE Section 6, T9S, R17E 1832' FSL, 1829' FEL				
s) TO INDICATE NATURE OF NOTICE, REP	ORT, OR OTHER DATA			
TYPE OF ACTION	NC			
Abandonment Recompletion Plugging Back Casing Repair Altering Casing Other	Change of Plans New Construction Non-Routine Fracturing Water Shut-Off Conversion to Injection Dispose Water (Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)			
	OMPANY Balcron Oil Division 59104 (406) 259-7860 secription Type of Action Abandonment Recompletion Plugging Back Casing Repair Altering Casing			

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

This well was converted to a water injection well on 12/31/92. An injection packer assembly was run on 2-7/8" tubing to isolate two injection zones each having individual injection mandrels and orifices to control the water flow to the various zones. The packers and injection mandrels are set as follows:

Top zone Perfs @ 4658'-4676' KB, Packer @ 4632' KB; Mandrel @ 4699' KB Lower zone Perfs @ 4814'-4824' KB; Packer @ 4768' KB; Mandrel @ 4837' KB

The casing annulus was displaced w/60 STB fresh water and 55 gallons of Champion chemical corrosion inhibitor (Cortron-2383) prior to setting the packers. The backside was then pressured to 500 psig and the pressure was held for a one-hour test. Water injection was started on 1/22/93 and is presently injecting at a rate of 110 STBWPD and a tubing pressure of 800 psig. Refer to the attached wellbore diagram for packer and tubing details.

	•	
14. I hereby certify that the foregoing is true and correct Signed Dobbus Achuman	Coordinator of Environmental Title and Regulatory Affairs	Date February 25, 1993
(This space for Federal or State office use) Approved by Conditions of approval, if any:	Title	Date

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



EQUITABLE RESOURCES ENERGY COMPANY, BALCRON OIL DIVISION

1601 Lewis Avenue P.O. Box 21017 Billings, MT 59104 (406) 259-7860 FAX: (406) 245-136\$

March 4, 1993

State of Utah Uintah County 152 East 100 North Vernal, UT 84078

Gentlemen:

Effective March 1, 1993, the name of our company has changed from Balcron Oil Company to Equitable Resources Energy Company, Balcron Oil Division.

Please make the necessary changes in your records and let me know if there is anything else we need to do in order to effect the change for the 1993 Uintah County Business License.

Sincerely,

Bobbie Schuman

Coordinator of Operations,

Environmental and Regulatory Affairs

/rs

MAR 0 8 1993

DIVISION OF OIL GAS & MINING

Page ____ of ___6

MONTHLY OIL AND GAS PRODUCTION REPORT

Operator name and address	:	·		············	
DAWN SCHINDLER BALCRON OIL PO BOX 21017 BILLINGS MT 59104				Utah Account No. Report Period (Mo	onth/Year) 1 / 93
Well Name	Producing	Days	Production Volume	· · · · · · · · · · · · · · · · · · ·	
			Oil (BBL)	Gas (MSCF)	Water (BBL)
BALCRON COYOTE FEDERAL 22-7					
#304732256 3 11408 08S 25E 7	GRRV	<u> </u>			
BALCRON COYOTE FEDERAL 42-6X 4304732346 1409 088 25E 6	GRRV				
BALCRON COYOTE FEDERAL 13-7					
4304732255711412 08S 25E 7	GRRV	ĺ			
FEDERAL 13-13					
4304732196 11417 085 24E 13	GRRV				
BALCRON MONUMENT FEDERAL 11-6			(1)		
¥301331362311422 09S 17E 6	GRRV	-	-WIW		
BALCRON COYOTE FEDERAL 33-5					•
04732257 11424 08S 25E 5	GRRV	<u> </u>			
CRON MONUMENT FEDERAL 24-6			1.21.5		
4301331363 11426 09S 17E 6	GRRV		- WIW		
BALCRON COYOTE FEDERAL 13-5			,		
430473226 1 11427 08S 25E 5	GRRV				
PARIETTE BENCH U #4			1.00		
∠4304715681, 99990 9S 19E 7	GRRV		- WDW		
EAST RED WASH 2-5					
43-047-20252 1112 8S 25E 5	GRRV				
BALCRON COYOTE FED 42-6					
43-047-32258 11386 8S 25E 6					
BALCRON COYOTE FED 33-7					
43-047-32259 99999 8S 25E 7					
ALLEN FEDERAL A-1					
43-013-15780 1115 9S 17E 5	GRRV	<u> </u>			
BALCRON MONUMENT FED 33-6	ODDII		- WIW		
43-013-31361 11438 9S 17E 6	GRRV T	OTAL			
Comments (attach separate sheet if nece	ssary)				
***************************************	·				
I have reviewed this report and certify the	information	to be	accurate and complete.	Date	
					•
Authorized signature				Telephone	, , , , , , , , , , , , , , , , , , ,
- Mario 1204 Orginaturo					

	of Oil, Gas and Mining OR CHANGE WORKSHEET				Routing:
	all documentation received by the division regularity and its second and its seco		able.		2-DFS//58-LEC ² 3-VLC 4-RJF
□ Chan □ Desi	ge of Operator (well sold) [gnation of Operator XX	□ Designation of X Operator Name	Agent Change Only		5-RWM 16-ADA
The op	erator of the well(s) listed below ha	as changed (EFFEC	CTIVE DATE:	3-1-93)
TO (ne	w operator) EQUITABLE RESOURCES ENERG (address) BALCRON OIL DIVISION PO BOX 21017 BILLINGS MT 59104 phone (406) 259-7860			PO BOX 210 BILLINGS M	17 r 59104
	account no. <u>N</u> 9890			account no	
Hell(s) (attach additional page if needed):				
Name: Name: Name:	**ALL WELLS** API: API: API: API: API:	Entity: Entity: Entity:	SecTwp SecTwp SecTwp	oRng l oRng l oRng l	_ease Type: _ease Type: _ease Type:
Name:	API:	Entity:	SecTw	oRng l	_ease Type:
μ/A 1.	OR CHANGE DOCUMENTATION (Rule R615-8-10) Sundry or other operator (Attach to this form). (Rule R615-8-10) Sundry or other lead (Attach to this form).				
<u>fec</u> 3.	The Department of Commerce has been operating any wells in Utah. Is convers, show company file number: 1346	ompanv registere	e new opera d with the	tor above i state? (ye	s not currently s/no) If
	(For Indian and Federal Wells ONLY (attach Telephone Documentation Focomments section of this form. Machanges should take place prior to o	orm to this rep nagement review completion of sta	ort). Mak of Federal ens 5 throug	e note of and India h 9 helow	BLM status in n well operator
	Changes have been entered in the Oi listed above. (3-19-93)				1) for each well
Jec 6.	Cardex file has been updated for each	ch well listed at	oove. <i>(3-19-9</i> 3	37	
Jec 7.	Cardex file has been updated for each Well file labels have been updated f	for each well lis	sted above.	(3-19-93)	
<u>Jee</u> 8.	Changes have been included on the m for distribution to State Lands and	nonthly "Operator	r, Address,	and Accoun	t Changes" memo
<u>Jec</u> 9.	A folder has been set up for the Opplaced there for reference during ro				

ERATOR CHANGE WORKSHEET (CONTINUED) Ini each item when completed. Write N/A item is not applicable.
NTITY REVIEW
1. (Rule R615-8-7) Entity assignments have been reviewed for all wells listed above. I entity changes made? (yes/no) (If entity assignments were changed, attach copies Form 6, Entity Action Form).
2. State Lands and the Tax Commission have been notified through normal procedures entity changes.
OND VERIFICATION (Fee wells only) * 930319 Red bond ride, eff. 3-4-93.
1. (Rule R615-3-1) The new operator of any fee lease well listed above has furnished proper bond. #5578314/80,000 Belown Oil, A Division of Equitable Resources Energy Company. 2. A copy of this form has been placed in the new and former operators' bond files.
3. The former operator has requested a release of liability from their bond (yes/no) _ Today's date 19 If yes, division response was made by led
CASE INTEREST OWNER NOTIFICATION RESPONSIBILITY
1. (Rule R615-2-10) The former operator/lessee of any fee lease well listed above has least notified by letter dated
2. Copies of documents have been sent to State Lands for changes involving State leases .
ILMING TWM All attachments to this form have been microfilmed. Date: March 30 199
iling
$\frac{f}{f}$ 1. Copies of all attachments to this form have been filed in each well file.
2. The <u>original</u> of this form and the <u>original</u> attachments have been filed in the Opera Change file.
MMENTS 130308 Bhm 15.7. No whenge newssary, they always recognized company name as "Equilable Resources Energy Company, Baleron Oil Division".

STATE-OF	UTA	Н			
DIVISION	0F (OIL.	GAS	AND	MINING

OPERATOR BALCRON OIL

APPLICATION FOR INJECTION WELL - UIC FORM 1

ADDRESS P.O. Box 21017 Billings, MT 59104
Well name and number: No Balcron Monument Federal #33-6
Field or Unit name: <u>Monument Butte Field</u> Lease no. <u>U-020252A</u>
Well location: QQ <u>NW SE</u> section <u>6</u> township <u>9S</u> range <u>17E</u> county <u>Duchesne</u>
Is this application for expansion of an existing project? Yes [] No 內
Will the proposed well be used for: Enhanced Recovery? Yes [x] No [] Disposal? Yes [] No [x] Storage? Yes [] No [x]
Is this application for a new well to be drilled? Yes [] No ❷*
If this application is for an existing well, has a casing test been performed on the well? Yes [] No & Date of test: API number: 43-013-31361 Completed prior to December 2 hearing.
Proposed injection interval: from 4.650' to 5.170' Proposed maximum injection: rate 600 BPD pressure 2500 psig Proposed injection zone contains [X] oil, [] gas, and/or [] fresh water within % mile of the well.
IMPORTANT: Additional information as required by R615-5-2 should accompany this form.
List of Attachments: Logs are or will be on file prior to the Hearing.
I certify that this report is true and complete to the best of my knowledge. Name Bobbie Schuman Signature Schuman Title Coordinator of Envrionmental Date October 16, 1992 Phone No. () and Regulatory Affairs PHONE: (406) 259-7860
(State use only) Application approved by Title Approval Date

Comments:



1601 Lewis Avenue P.O. Box 21017 Billings, MT 59104

OMFIDENTIAL

Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361

April 8, 1993

Mr. Chuck Williams
Underground Injection Control 8WM-DW-UIC
U.S. Environmental Protection Agency
Region 8
999 - 18th Street, Suite 500
Denver, CO 80202-2466

Dear Mr. Williams:

Enclosed are copies of the Mechanical Integrity Pressure Tests which were conducted on the following wells:

Allen Federal #1-6 SE SE Section 6, T9S, R17E Duchesne County, Utah 43-013-15779

Balcron Monument Federal #33-6 47-0/3-3/36/ NW SE Section 6, T9S, R17E Duchesne County, Utah

Sincerely,

Bobbie Schuman

Coordinator of Operations,

Environmental and Regulatory Affairs

/rs

Enclosures

cc: Utah Division of Oil, Gas and Mining Bureau of Land Management, Vernal BECERVED

APR 1 0 1993

DIVISION OF OIL GAS & MINING



United States Depart

BUREAU OF LANI Vernal Distr

Vernal Disu 170 South

Post-It™ brand fax transmittal	memo 7671 # of pages > 1
Tohn Zellitti	From Jerry Barnes
Balcren Oil	co. 3. L. M.
Dept.	Phone # 801-789 - 1362
Fox# 406-245-1361	Fax # 801-789-3634

Vernal, Utas

FAX (801) 789-3534

Phone (801) 789-1362

MECHANICAL INTEGRITY PRESSURE TEST CASING/TUBING ANNULUS

Lease No. <u>utu-ozoz</u>	A	Date:	2-2-93	
Company Name: Bal	eran Oil			_
Well Name: Monum	ent receval	Permit No County: _	Duchesne	•
Field Name: Monu	ment Buttes		R /1E	-
Well Location:N	W/SE Sec 6	T		-
Well Type: SWD	ER 2H	Other:		-
Type of Packer:	See Notes Below	Total Der	/CII+	-
Backer Set at (dep	th):	_ ET	FT to Jurface	FT
Surface Casing Siz	e: 85/8 K-55 , 34"	From: <u>258 G.C.</u>	FT to Surface	FT
Casing Size: 5/2",	J-55, 15.5 Fro	m: <u>57/4 G.C.</u>	mast: /50 DS	<u>i</u> a
Tubing Size: 27/8	J-55, 4.52 rubing ex	essure during	1820/20	
			• •••	
Fluid in Annulas: Chan	npion Chemical, Cortron	-2383 mixed 55	gal to 70 hbl 2% KC	<u>L</u> wat
	Test #1			
10:30 0 Min:	840 psig		psig Packers—	
5	840 psig		osig @ Arrow Set-	
10	840 psig	Name of Street, or other Designation of the Owner, where the Parks of the Owner, where the Owner, which is the Owner, whi	psig set @ 4768'	K. D.
15	840 psiq	The second line was a second line with the second l	psig Arrow Smap	Set
20	840 psig		psig(2) Armu Just set@ 4633'k psig	.B.
25	840 psig		· · · · · · · · · · · · · · · · · · ·	
	840psig		psig	
30	840 psig	and the standard to	psig	-
35	840 psig		3 1 110 500	പ്പട
40	840 psig		paig capped wir	1 + 140
45	840 psig		psig to prevent t	reez
50	840 berd		psig	•
55	846 paig		psig	
11:3° 60				
	Alluster Hot Oil S	Service - Pat	WISHER	-0.0
Test Conducted by	Au Fornemarth - Balc	· · · · · · · · · · · · · · · · · · ·	Barnes - B.L.	rı.
Land hare illow	AUTI LULALINAL TEL		` '	



1601 Lewis Avenue P.O. Box 21017 Billings, MT 59104 Office: (406) 259-7860 FAX: (406) 245-1365 LJ FAX: (406) 245-1361 KJ

April 15, 1993

Bureau of Land Management 170 South 500 East Vernal, UT 84078

Gentlemen:

RE: Balcron Monument Federal #33-6

NW SE Section 6, T9S, R17E

Duchesne County, Utah

and

Balcrom Monument Federal #42-6 SE NE Section 6, T9S, R17E

Duchesne County, Utah

Enclosed are the site security/site facility diagrams for the referenced wells.

Sincerely, Bobbie Schunan

Bobbie Schuman

Coordinator of Operations,

Environmental and Regulatory Affairs

/rs

Enclosures

cc: Utah Division of Oil, Gas and Mining

RECEIVED

APR 1 9 1993

DIVISION OF OIL GAS & MINING

Form 3160-5 (June 1990)

UNITED STATES DEPARTMENT OF THE INTERIOR

BUREAU OF LAND MANAGEMENT

10.00		,
Budget Bure	eau No.	1004-013
Expires:		

٥.	rease Designation and	SCLIM	110.
	U-020252-A		

6.	If	Indian,	Allottee	or	Tribe	Name

SUNDRY NOTICES . Do not use this form for proposals to dri Use "APPLICATION FOR	6. If Indian, Allottee or Tribe Name	
SUBMIT	IN TRIPLICATE PROCEDENTIAL	7. If Unit or CA, Agreement Designation
i. Type of Well X Oil Well Gas Well X Other injection		Balcron Monument Fed. #33-6
2. Name of Operator EQUITABLE RESOURCES ENERGY COI 3. Address and Telephone No.	MPANY	API Well No. 43-013- 31361
P.O. Box 21017; Billings, MT 4. Location of Well (Footage, Sec., T., R., M., or Survey De NW SE Section 6, T9S, R1 1832' FSL, 1829' FEL	59104 (400) 239 7000 escription) 7E	Monument Butte/Green Rive The County or Parish, State Duchesne County, UTAH
12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT TYPE OF ACTION	, OR OTHER DATA
Notice of Intent Subsequent Report Final Abandonment Notice	Abandonment Recompletion Plugging Back Casing Repair Altering Casing X Other site security diagram	Change of Plans New Construction Non-Routine Fracturing Water Shut-Off Conversion to Injection Dispose Water (Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)
Describe Proposed or Completed Operations (Clearly state al give subsurface locations and measured and true vertice)	ll pertinent details, and give pertinent dates, including estimated date of starting a cal depths for all markers and zones pertinent to this work.)*	ny proposed work. It wen is unectionally united,

Attached is the site security/site facility diagram for this injection well.



DIVISION OF OIL GAS & MINING


Signed Signed Chilman	Coordinator of Environmental	April 15, 1993
(This space for Federal or State office use) Approved by Conditions of approval, if any:	Title	Date

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Site Security Diagram Equitable Resources Energy Company Balcron Oil Division

Balcron Monument Butte Fed. #33-6 NW SE Sec.6 Twn.9S Rge.17E Duchesne County, Utah

Lease #: U-020252-A



Injection Well:

No sealed valves

P.O. Box 21017 Billings, Montana 59104 OF GASS PAINING

406-259-7860



1601 Lewis Avenue P.O. Box 21017 Billings, MT 59104

ALTS BILL SU

Office: (406) 259-7860 FAX: (406) 245-1365 [] FAX: (406) 245-1361 [X

AUG 2 0 1993

DIVISION OF OIL GAS & MINING

August 18, 1993

-- BY FAX and MAIL --

Bureau of Land Management 170 South 500 East Vernal, UT 84078

ATTENTION: Jamie Sparger or Jerry Kenczka

Gentlemen:

I am FAXing a sundry notice reporting discharges made on some of our Monument Butte Field injection wells by Environmental Protection Agency representatives during inspections they made. The original sundry notice will be put in the mail today.

If you have any questions, please feel free to give me a call.

Sincerely, Schuman

Bobbie Schuman

Coordinator of Operations,

Environmental and Regulatory Affairs

/rs

Enclosure

cc: Utah Division of Oil, Gas and Mining (Frank Matthews)

Form 3160-5 (June 1990)

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

(Note: Report results of multiple completion on Well

5.	Lease	Designation	and	Serial	No.

U-	0	2	0	2	5	2A
----	---	---	---	---	---	----

		O OLOLJEN
Do not use this form for proposals to dr	AND REPORTS ON WELLS III or to deepen or reentry to a different reservoir. R PERMIT—" for such proposals	
	IN TRIPLICATE AUG 2 0 1993	7. If Unit of CA, Agreement Designation Jonah Unit
1. Type of Well X Well	59104 (406) 259-7860	8. Well Name and No. See attached list 9. API Well No. See attached list 10. Field and Pool, or Exploratory Area Monument Butte/Grn.River 11. County or Parish, State Duchesne County, UTAH
12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPO	RT, OR OTHER DATA
TYPE OF SUBMISSION	· TYPE OF ACTION	,
Notice of Intent	Abandonment Recompletion	Change of Plans New Construction Non-Routine Fracturing
Subsequent Report Final Abandonment Notice	Plugging Back Casing Repair Altering Casing X over report of discharge	Water Shut-Off Conversion to Injection

Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

On August 17, 1993, operator discovered that Environmental Protection Agency (Region 8) representatives conducted inspections of the injection wells on the attached list and in their inspection blew the backside down causing a mixture of diesel and water (approximately 1/2-1 bbl total per location) to discharge onto location. The diesel is used as a blanket to prevent freezing. It is estimated that approximately 1/2 yard of dirt per location was impacted. The diesel stained the soil only slightly. On the Balcron Monument Federal #24-6 there was no diesel; however, water with a trace of oil blew from the tubing string causing minor staining.

The EPA Region 8 office was notified by telephone 8/17/93.

Cleanup of the locations will be done in conjunction with upcoming proposed reworks.

)		
14. I hereby certify that the foregoing is true and correct Signed Supplies Supplies	Coordinator of Environmental Title and Regulatory Affairs	Date <u>August 18, 1993</u>
(This space for Federal or State office use) Approved by Conditions of approval, if any:	Title	Date

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Attachment to Sundry Notice Federal Lease #U-020252A

Allen Federal #13-6 NW SW Section 6, T9S, R17E 2070' FSL, 578' FWL API #43-013-30918

Allen Federal #22-6 NW SE Section 6, T9S, R17E 2141' FNL, 1902' FWL API #43-013-30919

Balcron Monument Federal #11-6
NW NW Section 6, T9S, R17E
804' FNL, 696' FWL
API #43-013-31362

Balcron Monument Federal #24-6
SW SE Section 6, T9S, R17E
504' FSL, 1613' FWL
API #43-013-31363


Balcron Monument Federal #33-6 NW SE Section 6, T9S, R17E 1832' FSL, 1829' FEL API #43-013-31361

Balcron Monument Federal #42-6 SE NE Section 6, T9S, R17E 1806' FNL, 921' FEL API #43-013-31364

8/18/93 /rs



1601 Lewis Avenue Billings, MT 59102 Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361



March 16, 1995

Mr. Dan Jarvis State of Utah Division of Oil, Gas & Mining 355 West North Temple Salt Lake City, UT 84180

bie Schuman

Dear Mr. Jarvis:

Attached are copies of the injection profile reports for our enhanced recovery wells in the Jonah Unit.

If you have any questions, please call John Zellitti at (406) 259-7860.

Sincerely,

Bobbie Schuman

Regulatory and Environmental Specialist


/hs

Attachments

EQUITABLE RESOURCES ENERGY COMPANY-BALCRON OIL DIVISION <u>INJECTION PROFILE</u>

BALCRON MONUMENT FEDERAL 33-6

Date: 1/4/95 Surface Temp: 44 F BHT: 128 F PBTD: TD: 4874 Desired Rate: 150 B/D Metered Rate: 150 B/D Measured Rate: 152 B/D Tbg Pressure: 2000 PSI Csg Pressure: 0 PSI



Remarks: R/A Tracer survey indicates exits as shown. Packers check okay.

Service Company: Well Information Services, Inc.

Operator: Bart Williams

STATE OF UTAH
Division of Oil, Gas and Mining
355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203

INJECTION WELL - PRESSURE TEST

Test Date:		. 121
Disposal Well:		
API No.: 43- <u>013-3/36/</u>	Well Name/Number: Mokukel	+ Fed. 37-6
Section: 6	Township: 95	Range: <u>//E</u>
Initial Conditions:		
Tubing - Rate:	Pressure:	/50 psi
Casing/Tubing Annulus	- Pressure: O p	si
Conditions During Test:		
Time (Minutes)	Annulus Pressure	Tubing Pressure
0 5	10 90	1425
10	10 40	1490
	10 40	14 95
15	10 40	1500
20		1500
25	10 40	1500
30	10 40	
Results: Pass/Fail		
Conditions After Test:		
Tubing Pressure:/	500 psi	
Casing/Tubing Annulus	s Pressure: ps	i
REMARKS: Tiled to	bleed off tubing	before testing. Would
not bleed off		
Ju Jamos	not De	un le. She for
Operator Representative	DOGN	1 Witness '



United tates Department of the Interior

BUREAU OF LAND MANAGEMENT

Vernal District Office 170 South 500 East Vernal, Utah 84078



Phone (801) 789-1362

FAX (801) 789-3634

MECHANICAL INTEGRITY PRESSURE TEST CASING/TUBING ANNULUS

Lease No. 11-02	0252-A		,
Company Name:	intable Kesoure	J Energy (O, Date	: 1/- 19-96
THE THOMAS	ment + ed 33-(Permit No.	
Field Name: ///		Count	
Well Location:	NW SE Sec		9 S R 17 F
Well Type: SWD	ER 2H	Other	· _ / / =
Type of Packer:	Arraw set 1		
Packer Set at (de	epth): 4583.6	Y KB FT	Depth: 5693
Surface Casing Si	ze: 8.5/g	From: Sur	Court to OI
	1/2	From: Sur Ra	
Tubing Size: 27	Tubin	g Pressure duri	Let FT to 5790 FT lng Test: 1500 psig
Time of Day: //s	am/pm		ing lest: 7500 psig
Fluid in Annulas:	2acker Fluid		
,	Test #1	Test #2	
0 Min:		1000 12	mad
5			_ psig
10			_ psig
1 5	<u>/040</u> psig		_ psig
20	/0 40 psig		_ psig
25	1040. psig		_ psig
30	/040 psig		_ psig
35	/040 psig		_psig
40	10 40 psig		psig
45	/040 psig		psig
50	1040 psig		psig
55	<u>1040</u> psig		psig
60	1040 psig		psig
-			psig
est Conducted by:	0		
nspected by: Oa	and W. Sheedler	5/24 5/2-	1.1 /4
thers Present:	an Francisco	State of UT	136 (DOGM)



APR 4 1996

Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361

1601 Lewis Avenue Billings, MT 59102

April 1, 1996

Mr. Dan Jarvis
Utak Division of Oil, Gas and Mining
UIC Program
355 West North Temple
Salt Lake City, UT 84180

Dear Dan:

Effective April 1, 1996, our name will change from Equitable Resources Energy Company, Balcron Oil Division to Equitable Resources Energy Company. Attached is a listing of permits which we have with your Agency. This change will apply to those. If you note that I have missed some or if you have any questions, please do not hesitate to give me a call at (406) 259-7860, extension 240 to discuss this.

This change affects <u>only</u> our company name. The physical locations of our offices and the personnel remain the same.

If you have any questions, please do not hesitate to give me a call.

Sincerely,

Bobbie Schuman Regulatory and

Environmental Specialist

/hs

Enclosures

UTAH UIC PERMITS


Balcron Oil Monument Butte Jonah Unit Waterflood (new name)	
Formerly Monument Butte Area-A Waterflood Approved 12/22/92	
Area Permit No. UT2642-00000	
Alien Federal #22-6	UT2642-03729 (AREA PERMIT UT2642-00000)
Allen Federal #13-6	UT2642-03730 (AREA PERMIT UT2642-00000)
Allen Federal #31-6	UT2642-03731 (AREA PERMIT UT2642-00000) (State #UIC-142)
Alien Federal #1-6	UT2642-03732 (AREA PERMIT UT2642-00000)
Allen Federal #1A-5	UT2642-03733 (AREA PERMIT UT2642-00000)
	NOTE: Never converted to UIC - put back on production
Balcron Monument Fed. #11-6	UT2642-03734 (AREA PERMIT UT2642-00000)
Balcron Monument Fed. #24-6	UT2642-03735 (AREA PERMIT UT2642-00000)
Balcron Monument Fed. #33-6	UT2642-03736 (AREA PERMIT UT2642-00000)
Balcron Monument Fed. #42-6	UT2642-03737 (AREA PERMIT UT2642-00000)
Balcron Monument Fed. #13-5J	UT2642-04208 (AREA PERMIT UT2642-00000) (State #UIC-149)
Balcron Monument Fed. #22-5J	UT2642-04209 (AREA PERMIT UT2642-00000) (State #UIC-149)
Balcron Monument Fed. #24-5	UT2642-04210 (AREA PERMIT UT2642-00000) (State #UIC-149)
Balcron Monument Fed, #31-7J	UT2642-04211 (AREA PERMIT UT2642-00000) (State #UIC-149)
Monument Butte #1-33	State #UIC-151
Monument Butte #1-24	State #UIC-151
Monument Butte #1-13	State #UIC-151
Balcron Monument Fed. #42-1J	State #UIC-151
Getty #12-1	State #UIC-151
Balcron Monument Fed. #41-15	State #UIC-152
Balcron Monument Fed. #32-15	State #UIC-152
Balcron Monument Fed. #23-15	State #UIC-152
Balcron Monument Fed. #41-14J	State #UIC-152
Balcron Monument Fed. #21-14J	State #UIC-152
Balcron Monument Fed. #32-12J	State #UIC-152
C & O Gov't #4	State #UIC-152
Balcron Monument Fed. #14-12J	State #UIC-152
Balcron Monument Fed. #12-12J	State #UIC-152
Balcron Monument Fed. #43-11J	State #UIC-152
Balcron Monument Fed. #32-11	State #UIC-152



1601 Lewis Avenue Billings, MT 59102 Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361 \[\bar{\text{\tint{\text{\ti}\text{\texi}\text{\text{\text{\text{\text{\text{\text{\text{\texi\text{\text{\texi}\tex{\texi{\text{\texit{\text{\text{\texi}\text{\texi}\text{\texi}\tiin

March 22, 1996

Utah Division of Oil, Gas and Mining 355 West North Temple Salt Lake City, UT 84180



Gentlemen:

Effective April 1, 1996, our name will change from Equitable Resources Energy Company, Balcron Oil Division to Equitable Resources Energy Company. Attached is a sundry notice reflecting that change. To simplify paperwork, I have done one sundry notice with copies for each of the wells. To this letter I have attached a list of our wells for your ease in filing the sundry notices in the well files. This should be sufficient for your purposes.

I have the listings on a spreadsheet so if it would be easier for you to have them sorted differently (for example, the Montana Board of Oil and Gas prefers them sorted by API number), please give me a call at (406) 259-7860, extension 240 and I would be glad to provide a list to your specifications.

This change affects only our company name. The physical locations of our offices and the personnel remain the same. We will be changing our well signs and ask for your patience and cooperation as this will be done as soon as possible but may take some time since we do have so many properties at which to make the change.

If you have any questions, please do not hesitate to give me a call.

Sincerely,

Bobbie Schuman Regulatory and

Environmental Specialist

/hs

Enclosures

F OF UTAH DIVISION OF OIL, GAS AND MINING

		·	See attached listing
SUND	RY NOTICES AND REPORTS	ON WELLS	8. If Indian, Allottee or Tribe Name:
Do not use this form for p	proposals to drill new wells, deepen existing wells, or to reen	ter plugged and abandoned wells, such proposals.	7. Unit Agreement Name: See attached listing
1. Type of Well: OIL GA	s□ OTHER: See attached lis	sting	8. Well Name and Number: See attached listing
2. Name of Operator: Equitable Re	9. API Well Number: See attached listing		
3. Address and Telephone Number: 1601 Lewis A	10. Field and Pool, or Wildcat: See attached listing		
4. Location of Well	See attached listing		county: See attached list
QQ, Sec.,T.,R.,M.:			State: UTAH
11. CHECK APP	ROPRIATE BOXES TO INDICATE N	NATURE OF NOTICE, REPO	RT, OR OTHER DATA
	TICE OF INTENT Bubmit in Duplicate)		UENT REPORT riginal Form Only)
☐ Abandon	□ New Construction	☐ Abandon *	☐ New Construction
Repair Casing	Pull or Alter Casing	☐ Repair Casing	☐ Pull or Alter Casing
Change of Plans	☐ Recomplete	☐ Change of Plans	☐ Reperforate
☐ Convert to Injection	☐ Reperforate	☐ Convert to Injection	☐ Vent or Flare
☐ Fracture Treat or Acidize	☐ Vent or Flare	☐ Fracture Treat or Acidize	☐ Water Shut-Off
Multiple Completion	☐ Water Shut-Off	Other Operator name	change
 Other	_		
		Date of work completion	
Approximate date work will sta	\rf		
Approximate date work will sta	.rt	Report results of Multiple Completions an COMPLETION OR RECOMPLETION REPO	
		COMPLETION OR RECOMPLETION REPO Must be accompanied by a cement verification.	RT AND LOG form.
Effective Ap Energy Compa Physical loc (406) 259-78	TED OPERATIONS (Clearly state all pertinent details, and g	completion or recompletion reports of the pertinent dates. If well is directionally drilled, the pertinent dates. If well is directionally drilled, thange its name from Equitable Resources Errors as: 1601 Lewis Avenue is is to report the open	attant LOG form. give subsurface locations and measured and true quitable Resources nergy Company. 2: Billings. MT 59102
DESCRIBE PROPOSED OR COMPLE vertical depths for all markers and zon Effective Ap Energy Compa Physical loc (406) 259-78	TED OPERATIONS (Clearly state all pertinent details, and gines pertinent to this work.) oril. 1, 1996, operator will cony, Balcron Oil Division TO: ation of the operator remain 60, FAX: (406) 145-1361. Th	completion or recompletion reports of the pertinent dates. If well is directionally drilled, the pertinent dates. If well is directionally drilled, thange its name from Equitable Resources Errors as: 1601 Lewis Avenue is is to report the open	give subsurface locations and measured and true quitable Resources nergy Company.
Effective Ap Energy Compa Physical loc (406) 259-78	TED OPERATIONS (Clearly state all pertinent details, and gines pertinent to this work.) oril. 1, 1996, operator will cony, Balcron Oil Division TO: ation of the operator remain 60, FAX: (406) 145-1361. Th	completion or recompletion reports of the pertinent dates. If well is directionally drilled, the pertinent dates. If well is directionally drilled, thange its name from Equitable Resources Errors as: 1601 Lewis Avenue is is to report the open	give subsurface locations and measured and true quitable Resources nergy Company.
Effective Ap Energy Compa Physical loc (406) 259-78 only. It af	TED OPERATIONS (Clearly state all pertinent details, and gines pertinent to this work.) oril. 1, 1996, operator will cony, Balcron Oil Division TO: ation of the operator remain 60, FAX: (406) 145-1361. Th	completion or recompletion reports of the perfinent dates. If well is directionally drilled, thange its name from Equitable Resources Ends as: 1601 Lewis Avenue is is to report the openhed listing. Regulatory ar	give subsurface locations and measured and true quitable Resources nergy Company. e; Billings, MT 59102 erator name change

Balcron Monument Fed. #32-1J	Monument Butte	SW NE	1	98	16E	Duchesne	UT	Oil	Green River	U-33992	43-013-31414	2143' FNL, 1987' FEL	Vernal	Jonah
Balcron Monument Fed. #32-25	Undesignated	SW NE	25	85	17E	Uintah	υT	Oil	Green River	U-67845	43-047-32524	1980' FNL, 1980' FEL	Vernal	1
Balcron Monument Fed. #33-11J	Monument Butte	NW SE	11	98	16E	Duchesne	UT	Oil	Green River	U-096550	43-013-31451	1971' FSL, 2032' FEL	Vernal	Jonah
Balcron Monument Fed. #33-25	Undesignated	NW SE	25	88	17E	Uintah	UΤ	Oil	Green River	U-67845	43-047-32525	2097' FSL, 2067' FEL	Vernal	-
Balcron Monument Fed. #33-6	Monument Butte	NW SE	6	98	17E	Duchesne	UΤ	ww	Green River	U-020252-A	43-013-31361	1832' FSL, 1829' FEL	Vernal	Jonah
Baicron Monument Fed. #33-8	Monument Butte	NW SE	8	98	17E	Duchesne	UT	Oil	Green River	UTU-74108	43-013-31427	1980' FSL, 1980' FEL	Vernal	Beluga
Balcron Monument Fed. #34-10J	Monument Butte	SW SE	10	98	16E	Duchesne	UΤ	ww	Green River	U-017985	43-013-31416	592' FSL, 1979' FEL	Vernal	Jonah
Balcron Monument Fed. #34-25	Undesignated	SW SE	25	88	17E	Uintah	UT	PND	Green River	U-67845		800' FSL, 2100' FEL	Vernal	OOTIET!
Balcron Monument Fed. #34-7	Monument Butte	SW SE	7	98	17E	Duchesne	υT	PND	Green River	UTU-72106	43-013-31426	810' FSL, 1736' FEL	Vernal	
Balcron Monument Fed. #41-12J	Monument Butte	NE NE	12	98	16E	Duchesne	UT	Oil	Green River	U-44426	100,000,120	395' FNL, 476' FEL	Vernal	Jonah
Balcron Monument Fed. #41-14J	Monument Butte	NE NE	14	98	16E	Duchesne	UΤ	wiw	Green River	U-096550	43-013-31408	363' FNL, 600' FEL	Vernal	Jonah
Balcron Monument Fed. #41-15	Monument Butte	NE NE	15	98	16E	Duchesne	UΤ	wiw	Green River	U-017985	43-013-31367	460' FNL, 500' FEL	Vernal	Jonah
Balcron Monument Fed. #41-17	Monument Butte	NE NE	17	98	17E	Duchesne	UT	Oil	Green River	UTU-72106	43-013-31466	660' FNL, 660' FEL	Vernal	Beluga
Balcron Monument Fed. #41-26	Monument Butte	NE NE	26	85	17E	Uintah	UT	PND	Green River	U-67845	43-047-32456	660' FNL, 500' FEL	Vernal	ga
Balcron Monument Fed. #42-11J	Monument Butte	SE NE	11	98	16E	Duchesne	UT	Oil	Green River	U-096550	43-013-30066	1992' FNL, 496' FEL	Vernal	Jonah
Balcron Monument Fed. #42-12J	Monument Butte	SE NE	12	98	16E	Duchesne	υT	Oil	Green River	U-035521	43-013-31486	2550' FNL, 391' FEL	Vernal	Jonah
Balcron Monument Fed. #42-14J	Monument Butte	SE NE	14	98	16E	Duchesne	UT	PND	Green River	U-096550	43-013-21491	1882' FNL, 773' FEL	Vernal	Jonah
Balcron Monument Fed. #42-17	Monument Butte	SE NE	17	98	17E	Duchesne	UΤ	Oil	Green River	UTU-72106	43-013-31467	1800' FNL, 700' FEL	Vernal	Beluga
Baicron Monument Fed. #42-18	Monument Butte	SE NE	18	98	17E	Duchesne	UΤ	PND	Green River	UTU-72106	43-013-31433	1800' FNL, 800' FEL	Vernal	Deloga
Balcron Monument Fed. #42-1J	Monument Butte	SE NE	1	98	16E	Duchesne	UΤ	ww	Green River	U-40652	43-013-31404	2087 FNL, 692 FEL	Vernal	Jonah
Balcron Monument Fed. #42-26	Undesignated	SE NE	26	88	17E	Uintah	UT	PND	Green River	U-67845		2100' FNL, 660' FEL	Vernal	JOHAN .
Balcron Monument Fed. #42-6	Monument Butte	SE NE	6	98	17E	Duchesne	UΤ	wiw	Green River	U-020252-A	43-013-31364	1806' FNL, 921' FEL	Vernal	Jonah
Balcron Monument Fed. #43-11J	Monument Butte	NE SE	11	98	16E	Duchesne	υT	wiw	Green River	U-096550	43-013-31002	2127' FSL, 693' FEL		Jonah
Balcron Monument Fed. #43-26	Undesignated	NE SE	26	88	17E	Uintah	υT	PND	Green River	U-67845		1880' FSL, 379' FEL	Vernal	00.1011
Balcron Monument Fed. #43-7	Monument Butte	NE SE	7	98	17E	Duchesne	UT	Oil	Green River	UTU-72106	43-013-31432	1850' FSL, 850' FEL	-	Beluga
Balcron Monument Fed. #44-1J	Monument Butte	SE SE	1	98	16E	Duchesne	UT	wiw	Green River	U-44426		338' FSL, 859' FEL	-	Jonah
Balcron Monument State #12-2	Undesignated	SW NW	2	98	17E	Duchesne	UΤ	Oil	Green River	ML-45555	43-013-31481	1980' FNL, 660' FWL		
Balcron Monument State #13-2	Undesignated	NW SW	2	98	17E	Duchesne	UT	Oil	Green River	ML-45555		2210' FSL, 604' FWL		
Balcron Monument State #14-2	Undesignated	sw sw	2	98	17E	Duchesne	UT	Oil	Green River	ML-45555		513' FSL, 787' FWL		
Balcron Monument State #21-2-9-17	Undesignated	NE NW	2	98	17E	Uintah	υT	Oil	Green River			821' FNL, 2187' FWL		
Balcron Monument State #22-2	Undesignated	SE NW	2	98	17E	Uintah	+	Oil	Green River	ML-45555	43-047-32610	1980' FNL, 1980' FWL	-	
Balcron Monument State #23-2	Undesignated	NE SW	2	98	17E	Uintah	UT	wsw	Green River	ML-45555		1980' FSL, 1980' FWL		
Balcron Monument State #24-2	Undesignated	SE SW	2	98	17E	Uintah	υT	Oil	Green River	ML-45555		660' FSL, 1980' FWL		
Balcron Monument State #32-2	Undesignated	SW NE	2	98	17E	Uintah	UT	PND	Green River	ML-45555	43-047-32609	1980' FNL, 1980' FEL		
Balcron Monument State #34-2	Undesignated	SW SE	2	98		Uintah .	UT	PND	Green River	ML-45555		800' FSL. 1980' FEL		

	n of Oil, Gas a FOR CHANGE H								ile: EP-7-SJ
				-	ding this change item is not appl			2- D	LD GILLS
	nge of Opera ignation of		sold)		Designation Operator Nam		nly		TIM V
The op	perator of t	he well(s) listed be	low has	changed (EFF	ECTIVE DAT	E: <u>4-1-96</u>))
TO (ne	ew operator) (address)	1601 LEW BILLINGS phone (4		4126	COEROM (form	ner operato (addres	BALCRON 1601 LE BILLING phone (OIL DIV WIS AVE S MT 59 406) 259- noN 98	102-4126 -7860
Hell(s) (attach addi	itional page	e if needed):		•				
Name: Name: Name:			API: API: API:		Entity: Entity: Entity: Entity: Entity: Entity: Entity: Entity:	Sec Sec Sec	TwpRng TwpRng Twp Rna	_ Lease _ Lease Lease	Type: Type: Type:
Le 1.	operator (A	i-8-10) S Attach to -8-10) Sui	undry or o this form)	· Check 4.	gal documen 4-96 % 4-8-96 documentati	/			
<u>N/A</u> 3.	operating a	any wells	ommerce has in Utah. ile number:	is comp	ontacted if i bany register	the new ope red with t	erator abov he state?	e is not (yes/no)	currently If
	changes sho	lephone ection of	Documentation this form	on Form . Manag	The BLM has to this regement revie pletion of s	eport). M W of Feder tops 5 thro	lake note r al and In e	of BLM dian w ell	status in I operator
Le 5.	Changes hav	'e been ei 'e . <i>(4-10-91</i>	ntered in th	he Óil a	and Gas Infor	rmation Sys	tem (Wang/	IBM) for	-each-well
<u>Le</u> 6.	Cardex file	has beer	updated fo	or each	well listed	above. (4-11	-967		
Lec 7.	Well file 1	abels hav	e been upda	ted for	each well l	isted above	e. (4-11-967		
A -	101 0121110	ution to	State Fallos	anu tne	thly "Operat e Tax Commis	STOIL (4-/0.	-961		
<u>lic</u> 9.	A folder ha placed ther	is been so e for ref	et up for t erence duri	he Opera	ator Change ing and proce	file, and essing of t	a copy of the origina	this page 1 docume	has been nts.

1

OPERATOR	CHANGE WORKSHEET (CONTINUED) Initial each item when completed. Write N/A if item is not applicable.
ENTITY	REVIEH
Lie1.	(Rule R615-8-7) Entity assignments have been reviewed for all wells listed above. Were entity changes made? (yes/no) (If entity assignments were changed, attach copies of Form 6, Entity Action Form).
<u>N</u> A 2.	State Lands and the Tax Commission have been notified through normal procedures of entity changes.
BOND V	ERIFICATION (Fee wells only) # 5578314 (\$80,000) Sikes Ins. C. (Brad Rider In Progress)
Lic 1.	(Rule R615-3-1) The new operator of any fee lease well listed above has furnished a proper bond.
2.	A copy of this form has been placed in the new and former operators' bond files.
N/A 3.	The former operator has requested a release of liability from their bond (yes/no) Today's date 19 If yes, division response was made by letter dated 19
LEASE :	INTEREST OHNER NOTIFICATION RESPONSIBILITY
	(Rule R615-2-10) The former operator/lessee of any fee lease well listed above has been notified by letter dated
2.	Copies of documents have been sent to State Lands for changes involving State leases.
FILMIN	$m{\wedge}$
10/1.	All attachments to this form have been microfilmed. Date: $\frac{May}{20}$ 19 $\frac{46}{20}$.
FILING	
1.	Copies of all attachments to this form have been filed in each well file.
2.	The <u>original</u> of this form and the <u>original</u> attachments have been filed in the Operator Change file.
COMMEN	TS .
	Blm/BIA Formal approved not necessary".

WE71/34-35

STATE OF UTAH INVENTORY OF INJECTION WELLS

Page No. 03/07/96

OPERATOR API NO. WELL TNS RGE SE WELLTYPE INDIAN COU ************************************	
CROSS CREEK 43-037-20117 NAVAJO A #1 41S 26E 5 INJD Y CROSS CREEK 43-037-20164 NAVAJO A #3 41S 26E 5 INJI Y ENSERCH EXPL 43-013-31240 FEDERAL 43-3 08S 16E 33 INJW N ENSERCH EXPL 43-013-31269 FEDERAL 34-3 08S 16E 33 INJW N ENSERCH EXPL 43-013-31229 FEDERAL 14-3 08S 16E 33 INJW N ENSERCH EXPL 43-613-31225 FEDERAL 14-3 08S 16E 34 INJW N ENSERCH EXPL 43-013-31272 FEDERAL 21-4 09S 16E 4 INJW N	
CROSS CREEK 43-037-20164 NAVAJO A #3 41S 26E 5 INJI Y ENSERCH EXPL 43-013-31240 FEDERAL 43-3 08S 16E 33 INJW N ENSERCH EXPL 43-013-31269 FEDERAL 34-3 08S 16E 33 INJW N ENSERCH EXPL 43-013-31229 FEDERAL 14-3 08S 16E 33 INJW N ENSERCH EXPL 43-013-31225 FEDERAL 14-3 08S 16E 34 INJW N ENSERCH EXPL 43-013-31272 FEDERAL 21-4 09S 16E 4 INJW N	
ENSERCH EXPL 43-013-31240 FEDERAL 43-3 08S 16E 33 INJW N ENSERCH EXPL 43-013-31269 FEDERAL 34-3 08S 16E 33 INJW N ENSERCH EXPL 43-013-31229 FEDERAL 14-3 08S 16E 33 INJW N ENSERCH EXPL 43-613-31225 FEDERAL 14-3 08S 16E 34 INJW N ENSERCH EXPL 43-013-31272 FEDERAL 21-4 09S 16E 4 INJW N	
ENSERCH EXPL 43-013-31269 FEDERAL 34-3 08S 16E 33 INJW N ENSERCH EXPL 43-013-31229 FEDERAL 14-3 08S 16E 33 INJW N ENSERCH EXPL 43-013-31225 FEDERAL 14-3 08S 16E 34 INJW N ENSERCH EXPL 43-013-31272 FEDERAL 21-4 09S 16E 4 INJW N	
ENSERCH EXPL 43-013-31229 FEDERAL 14-3 08S 16E 33 INJW N ENSERCH EXPL 43-013-31225 FEDERAL 14-3 08S 16E 34 INJW N ENSERCH EXPL 43-013-31272 FEDERAL 21-4 09S 16E 4 INJW N	
ENSERCH EXPL 43-013-31225 FEDERAL 14-3 08S 16E 34 INJW N ENSERCH EXPL 43-013-31272 FEDERAL 21-4 09S 16E 4 INJW N	
ENSERCH EXPL 43-013-31272 FEDERAL 21-4 09S 16E 4 INJW N	
DIVIDENCE: BILLE TO THE THEORY OF THE PROPERTY	
- KNSKKIM KXPL 45-015-10070 FRUKAL 57-0 020 IOD O INOW N	
ENSERCH EXPL 43-013-31205 FEDERAL 41-5 09S 16E 5 INJW N	
ENSERCH EXPL 43-047-32248 1-26B 09S 19E 26 INJG N	
ENSERCH EXPL 43-013-30913 44-5H 09S 17E 5 INJW N	
ENSERCH EXPL 43-013-30678 42-8H 09S 17E 8 INJW N	
ENSERCH EXPL 43-013-31457 22-8H 09S 17E 8 INJW N	
ENSERCH EXPL 43-013-30679 31-8H 09S 17E 8 INJW N	
ENSERCH EXPL 43-013-31049 22-9H 09S 17E 9 INJW N	
ENSERCH EXPL 43-013-30682 24-9H 09S 17E 9 INJW N	
ENSERCH EXPL 43-013-30887 11-9H 09S 17E 9 INJW N	
ENSERCH EXPL 43-013-30087 11-5H 098 17E 9 INJW N	
ENSERCH EXPL 43-013-31100 33-9H 09S 17E 9 INJW N	
EOUITABLE RE 43-013-31362 FEDERAL 11-6 09S 17E 6 INJW Y	
EQUITABLE RE 43-013-31361 FEDERAL 33-6 09S 17E 6 INJW Y	
Dyottiman in the state of the s	
Decimal Revision of the second	
DOTTING REPORT OF THE PROPERTY	
Agorribada ka to oro ovaro respectivo de la companya de la company	
DOTTIME IN 15 OF 15 OUT THE PLANT SELECTION OF THE PROPERTY OF	
To the second se	
Decimal Resident States and State	
TO THE STATE OF TH	
POLITICAL DE 42 012 20701 1 24 000 16F 1 TNTW N	
100111111111 KH 15 010 00101 1 11	
DOTTINDED RE 15 015 51 120 51 200	
DQ0111DDH KB 15 015 51002 15 125	
avortiment in the state of the	
ngorithan it is ore order or and	
DXOTTIMDE NO 15 020 02011 21 210	
DOTTIME RELIGION OF THE PROPERTY OF THE PROPER	
DOTTIME RELIGION TO THE CONTRACT OF THE CONTRA	
TO THE TO THE TOTAL THE TAXABLE PROPERTY.	
To the state of th	
DOTTIME REPORT OF THE PROPERTY	
DOTTIMAL KA 15 015 010 0	
EQUITABLE RE 43-013-31375 24-5 09S 17E 5 INJW Y	
EQUITABLE RE 43-013-31370 FEDERAL 13-5 09S 17E 5 INJW Y	
EQUITABLE RE 43-013-31195 ALLEN FEDERA 09S 17E 6 INJW N	
EQUITABLE RE 43-013-31405 31-7J 09S 17E 7 INJW Y	
EQUITABLE 43-013-31492 11-79 95 17E 7 INGW N	

Form 3160-5 (Jun .990)

> 1. Type of Well Oil Well

2. Name of Operator

3. Address and Telephone No.

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

NW SE Section 6, T9S, R17E

1832' FSL, 1829' FEL

Equitable Resources Energy Company

1601 Lewis Avenue; Billings, MT 59102

DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

Vacuu	NOTICES	AND	REPORTS	ON	WELLS
HINDRY	NOTICES	ANU	REPURIS	\mathbf{v}_{i}	,,

Do not use this form for proposals to drill or to deepen or reentry to a different res Use "APPLICATION FOR PERMIT—" for such proposals

		1				
TINI.	STATES	FORM APPROVED Budget Bureau No. 1004-0135				
, UNI	OF THE INTEDIOD	Expires: March 31, 1993				
DEPARTMENT	DEPARTMENT OF THE INTERIOR					
BUREAU OF LA	BUREAU OF LAND MANAGEMENT					
	IND REPORTS ON WELLS	6. If Indian, Allottee or Tribe Name				
SUNDRY NOTICES A	IND REPORTS OF TREATTY to a different reservoir.	1				
se this form for proposals to drill	or to deepen or reentry to a different reservoir.	n/a				
Use "APPLICATION FOR	PERMIT—" for such proposals	7. If Unit or CA, Agreement Designation				
	W TOUR ICATE	7. If Out of C/1, /18-00-11-11				
SUBMIT	IN TRIPLICATE					
eli		Jonah Unit				
□ Gas □		10				
	Balcron Monment Fed. #33-6					
perator	9. API Well No.					
table Resources Energy Co	мірану	43-013-31361				
d Telephone No.	MT 59102 (406) 259-7860	10. Field and Pool, or Exploratory Area				
Lewis Avenue; Billings,		Mon. Butte/Green River				
of Well (Footage, Sec., T., R., M., or Survey De	scription)	11. County or Parish, State				
SE Section 6, T9S, R17E		Duchesne County, UTAH				
32' FSL, 1829' FEL						
	NATURE OF NOTICE REPO	RT. OR OTHER DATA				
CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPO					
TYPE OF SUBMISSION	TYPE OF ACTION					
	Abandonment	Change of Plans				
Notice of Intent	Recompletion	New Construction :				
	· ·	Non-Routine Fracturing				
X Subsequent Report	Plugging Back	Water Shut-Off				
	Casing Repair	Conversion to Injection				
Final Abandonment Notice	Altering Certing rework & MIT	Dispose Water				


Final Adamondment House	Other Well Teller II a view	Dispose water
	C Oulei	(Note: Report results of multiple completion on Well
	l .	Completion of Recompletion Report and Log form.)
	Il pertinent details, and give pertinent dates, including estimated date of starting as cal depths for all markers and zones pertinent to this work.)*	an proposed work. If well is directionally drilled,
	It pertinent details, and give pertinent dates, including estimated date of starting at	ny proposed work. It was a
13. Describe Proposed or Completed Operations (Clearly state a	cal depths for all markers and zones pertinent to this work.)	
give subsurface locations and measured and true verti	cal depuis for all markers and control	
0		

Attached is an EPA Well Rework Form showing work that was done on this well. Also attached is a copy of the Mechanical Integrity Test (MIT) that was run on the well.

ORIGINAL: Bureau of Land Management (Vernal, UT)

COPY: Environmental Protection Agency (Chuck Williams) - by FAX and mail

COPY: Utah Division of Oil, Gas and Mining (Dan Jarvis)



4. I hereby certify that the foregoing is true and correct Signed Dobbia Schuman	Regulatory and Tiule Environmental Specialist	Date November 20, 1996
(This space for Federal or State Office use)	Title	Date
Approved by		
knowingly	and willfully to make to any department or agency of the United States	any false, fictitious or fraudulent statements

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to r or representations as to any matter within its jurisdiction.

credit denied - 9/4 See Instruction on Reverse Side



United Ites Department of the Interior

BUREAU OF LAND MANAGEMENT

Vernal District Office 170 South 500 East Vernal, Utah 84078



Phone (801) 789-1362

FAX (801) 789-3634

MECHANICAL INTEGRITY PRESSURE TEST CASING/TUBING ANNULUS

Lease No. 11 Oo		THE WHATTA
	0252-A	
Company Name: 29	mitable Resources	
Well Name: Monu		Permit No. 43-013-31361
Field Name: Mon	whent Butte	County: Duches Ne
Well Location: _	NW SE Sec	
Well Type: SWD _	ERX 2H	Other:
Type of Packer:	Arrow set -1	Total Depth: 56 93' PBT
Packer Set at (d	epth): 4583.64	KB FT (Bottom of Tool) 5740' TD
Surface Casing S	ize: 8 5/8	From: SurfaceFT to 26/ FT
Casing Size:	1/2 "	From: Surface FT to 5740 FT
Tubing Size: 2	Vs "Tubing	Pressure during Test: 1500 psig
Time of Day: /:	55 am/pm)	7500 psig
Fluid in Annulas:	Packer Fluid	(Cortron - 2383)
	Test 1	Test #2
0 Min:		psig
5		psig
10		psig
1 5		psig
20	_/0 40 psig	psig
25	1040 psig	psig
· 3 0	/040 psig	psig
35	1040 psig	psig
40	10 40 psig	psig
45	/040 psig	psig
50	1040 psig	psig
55	<u>/047</u> psig	psig
60	<u>/04/0</u> psig	psig
•		
Test Conducted by	· · · · · · · · · · · · · · · · · · ·	
Inspected by: _	and W. Sheefford,	State of Utal (DOGM)
Others Present:	Jan Franciosto-	TRECTION (DOOM)

STATE OF UTAII Division of Oil, Gas and Mining 355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203

INJECTION WELL. - PRESSURE TEST

		المراجع فالمراجع		
Test Date: _///1/16	Well Owner/Operator:	quitable Keso	041615	
Diepond Well:	Enhanced Recovery Wel	1:	Other:	
API No.: 43-013-3/36/	Well Name/Number: Me	SELACHT Feel	37-6	
Section: 6	Township: 95	R	ange: <u>//E</u>	
Section:				
Initial Conditions:	•			
Tubing - Rate:	Pressure	=: <u>1450</u>	psi	
Casing/Tubing Annulu	as - Pressure:O	psi		
Conditions During Test:				
Time (Minutes) 0 5 10 15 20 25 30	Annulus Pressu 1050 1040 1040 1040 1040 1040 1040	re I	1495 1495 1490 1495 1500 1500	0
Results: Pass/Fail				
Conditions After Test:				
Tubing Pressure:	_	•		
Casing/Tubing Annu	ilus Pressure:	psi	,	.0
REMARKS: 111ed to	Weed off +	Lubing bet	fore testing.	World
not bleed off	1			
Operator Representative	suot -	DOGM Witness	w. Sheefer	

≎ EP/	4			ENVIRONMENTA VASHINGTON, D REWORK	C 20460		CY		
Eauitab	ins here	ces Enem	7 Compa	~y N	Basi P.O	n We	OF CONTRACTOR N Service 2876 , Utah		
LOCATE WI	ELL AND OUTLINE ON PLAT 640 AC	UNIT ON	STATE Utah	COUNTY Duch CATION DESCR	esne		~+7	PERMIT NUMBER 143-013-3136	
	N	LOCATE WELL Surface Location & and \(\frac{829}{2} \)	32 tt. from (N/) 1. from (E/W) L ACTIVITY	N/S) S Line of quarter section Line of quarter section Total Depth Before Rework			TYPE OF PERMIT		
w	+ + +	E	☐ Hydroca Lease N	ed Recovery arbon Storage	5740' KB Date Rework Commenced			Well Number Balcon Monument Federal # 33-6	
	Š		WELL CASIN	IG RECORD	— BEFOR	E REWO	RK		
Cas Size	Degin Degin	Cem Secks	Type	Fram	erforations To			Acid or Fracture Treatment Record	
		(See	Attac	hed D	iags	am)			
		WELL CASING	RECORD - A	FTER REWO	RK (Indica	te Additio	ns and Changes	: Only).	
Size Size Q 6/g "	0 on 1 267 KB	Sacks	Type Class - G	From None			Acid or Fracture Treatment Record Pickle Hog & Derfs W/		
51/2"	5725' KB	226 400	Hilift Class-G	4658	46				
-	ESCRIBE REWO	ORK OPERATION	S IN DETAIL				perfora		
TOOH WI	use addition	AL SHEETS IF NE	CESSARY Lcidize 1	tha #		Log Typ		Logged intervals	
HCI acid	d, swab t-1 pac	8'-4824' w back loa Ker 0 45 Cortron- annulus	76' KB	pump ker flu	tems	xed,	w/ 60 578 test cse		
st in	certify under to ubmitted in to nmediately re nd complete.	the penalty of his document esponsible for	f law that I ha t and all atta obtaining th at there are s	eve persona achments a ne informat significant p	ally exam and that, ion, I be penalties	nined ai based lieve tha s for sub	on my inquit at the informa	r with the information ry of those individuals ation is true, accurate, information, including	
			l sic	NATURE	· · · · · · · · · · · · · · · · · · ·			DATE SIGNED	

NAME AND OFFICIAL TITLE (Please type or print)

John Zellitti

Senior Production Engineer

SIGNATURE John Tellith

11-19-96

BALCRON OIL

WELL NAME: Monument Federal #33-6

FIELD: Monument Butte

FEDERAL LEASE NO.: U-020252A

LOCATION: NW SE Sec.6, T9S, R17E COUNTY/STATE: Duchesne County, Utah

WORKING INTEREST: 0.79942652 PRODUCING FORMATION: Green River

COMPLETION DATE: 12-1-92
INITIAL PRODUCTION: 30 STBOPD, 30 STBWPD

PRESENT PROD STATUS: Water Injection Well Started Water Inj. 1-22-93

ELEVATIONS - GROUND: 5267'

TOTAL DEPTH: 5740'KB

SURFACE CASING

STRING: ______ CSG SIZE: 8 5/8" GRADE: K-55 WEIGHT: 24 lbs

LENGTH: 6 jts @ 258' DEPTH LANDED: 267'KB

HOLE SIZE: 12 1/4"
CEMENT DATA: 161 sx 75% Class - G

& 25% Litpoz

INJECTION	LENGTH	SETTING DEPTH
EQUIPMENT & SIZE	FT.	(W/11'KB)FT.
1)150 jts J-55,2 7/8,J-5 2) 2 7/8" SN 3) Arrowsnap 2 packer 4) 2 7/8 x 2 3/8 x-over 5) 2 jts j-55 2 7/8 tbg 6) KBMM side pckt mndrl 7) 2 jts 2 3/8 J-55 tbg 8) Arrow Set-1 packer 9) 2 jts 2 3/8 J-55 tbg 10) KBMM side pckt mndrl 11) 1 jt 2 3/8 J-55 tbg 12) 2 3/8 J-55 tbg	4621.85 1.10' 3.35' .40' 62.77' 62.30' 62.30' 62.64' 6.35' 31.60' 1.50'	11' 4632.85' 4633.95' 4637.30' 4637.70' 4700.47' 4706.82' 4769.12' 4775.32' 4837.96' 4844.31'

INJECTION HORIZONS

Red 1 @ 4658'-4676'KB Red 5 @ 4814'-4824'KB WELL REPORT

DATE: 9-10-93 JZ

API NO.: 43-013-31361

NET REVENUE INT.: 0.72981781 Oil 0.65881769 Gas

SPUD DATE: 10-24-92

BHT: 139 Deg.F

KB: 5278' (11'KB)

PLUG BACK TD: 5693'KB

PRODUCTION CASING

STRING: 1 CSG SIZE: 5 1/2" GRADE: K-55

WEIGHT: 15.5# LENGTH: 5714'

DEPTH LANDED: 5725'KB

HOLE SIZE: 7 7/8" CEMENT DATA: 226 sx Lilift &

400 sx Class - G

CEMENT TOP AT:

PERFORATIONS

Schlumberger

4658'-4666' 4 holes 4672'-4676' 2 holes

4814'-4824' 6 holes

ACID JOB

4814'-4824' Spot 250 gal 15% HCl Acid, BD @ 2300,

Avg. 5.5 STBPM @ 1690psig, ISIP @ 740psig.

4658'-4676' Spot 250 gal 15% HCl Acid w/10 ball sealers, BD @ 4550, 5.5 BPM @ 1800psig,

Good ball action, ISIP @ 950psig.

FRAC JOB

Frac w/Western on 11-28-92.

Avg. 32 BPM @ 2900psig, ISIP @ 1850psig,

5 min @ 1550psig, 10 min @ 1340psig, 15 min

BeFore Rework

100000000 seek to 12-2-2-2

NW SE Sec. 6,T95,R17E Lease No. U-020252A Monument Butte Field Duchesne County, Utah Jonah Unit

SURFACE CASING

8 5/8",K-55,24#
Landed @ 260' KB
Cemented W/250 sx,Class-G,3% CaCl.
Cemented to surface.
Hole Size @ 12 1/4"

PRODUCTION CASING

5 1/2",K-55,15.5#
Landed @ 5580' KB
Cement Data:
250 sx Hifill w/10#/sx Gilsonite
tailed w/180 sx 50-50 poz w/0.3%
CFR-3,1/4#/sx Flocele,0.5% Halad-24
& 10% Salt.
Cemented to surface.
Hole Size @ 7 7/8"

INJECTION	LENGTH	SETTING DEPTH
EOUIPMENT & SIZE	FT.	(W/11'KB)FT.
1)150 jts J-55 tbg 2 7/8	4621.85	11'
2) 2 7/8" pump SN	1.10'	4632.851
3) Arrowsnap 2 packer	3.35'	- 4633.95¹
4) 2 7/8 x 2 3/8 x-over	.40'	4637.30'
5) 2 jts j-55 2 7/8 tbg	62.77'	4637.70'
6) KBMM side pckt mndrl	6.35'	4700.47'
7) 2 jts 2 3/8 j-55 tbg	62.30'	4706.82'
8)5 1/2x2 3/8 Arrowset 1	6.20'	4769.12'
9) 2 jts 2 3/8 j-55 tbg	62.64'	4775.32'
10) KBMM side pckt mndrl	6.35'	4837.96'
11) 1 jt 2 3/8 j-55 tbg	31.60'	4844.31'
12) 2 3/8 X-H Bull Plug	1.50'	4875.91'

١.

INJECTION HORIZONS

Red 1 @ 4658'-4676'KB Red 5 @ 4814'-4824'KB

BeFore Rework

- Uintah Formation Surface to 1400 ft.

PERFORATIONS

Schlumberger 4658'-4666' 4 holes 4672'-4676' 2 holes 4814'-4824' 6 holes

- Green River Formation 1400 to 4100 ft.
- Arrow Packers Set @ 4637' & 4775' KB.

- Douglas Creek Member 4100 to 5350 ft. - Wasatch Fm. Transition 5350 to 6000 ft.

AND SHOULD AND ARRANGED AND AND ARRANGED ARRANGED AND ARRANGED AND ARRANGED ARRANGED AND ARRANGED ARRANGED AND ARRANGED ARRANGED AND ARRANGED ARRANGED ARRANGED AND ARRANGED ARRANGED AND ARRANGED ARRANGED ARRANGED AND ARRANGED ARRANG

PBTD @ 5693' KB TD @ 5740'KB

- Wasatch Formation 6000 ft.

Balcron Monument Federal #33-6 NW SE Sec. 6,798,R17E Lease No. U-020252A Monument Butte Field Duchesne County, Utah Jonah Unit

Injection Well Completion Diagram

SURFACE CASING 8 5/8",K-55,24# Landed @ 260' KB Cemented W/250 sx,Class-G,3% CaCl. Cemented to surface. Hole Size @ 12 1/4* 260' KB PRODUCTION CASING ------5 1/2*, K-55, 15.5# Landed @ 5580' KB - Uintah Formation Surface t Cement Data: 250 sx Hifill w/10#/sx Gilsonite tailed w/180 sx 50-50 poz w/0.3% CFR-3,1/4#/sx Flocele,0.5% Halad-24 & 10% Salt. Cemented to surface. Hole Size @ 7 7/8* INJECTION EQUIPMENT & SIZE LENGTH SETTIG DEPTH 11' KB 2-7/8" 8rd EUE TBG 148 Jts 2-7/8" Seating Nipple 2-7/8"x1.10' 2-3/8"x2-7/8" Cross Over 0.36' 4574.78' KB 4575.88' KB 4576.24' KB (Top of PKR) Arrow Set-1 PKR 7.40' 4583.64' KB (Bottom of PKR) RE-WORK PROCEDURE: POOH w/ injection PKR's and injection mandrels. TIH w/ casing scraper. POOH w/ bit & scraper & TIH with PKR. Acidize tbg and perforations w/ 1500 gal 15% HCL. Swab back load & POOH w/ PKR. TIH with Arrow Set-1 packer & set @ 4576' KB. PERFORATIONS PACKER FLUID: 55 gal Champion Cortron 2383 PKR fluid. mixed w/ 60 bbl 2% KCL water. Schlumberger 4658'-4666' 4 hole 4672'-4676' 2 hole 4814'-4824' 6 hole MIT RECORD: - Green River Formation 1400 Arrow Set-1 Packer set @ 4576' KB 4658'-4666' 4672'-4676' 4814'-4824' - Douglas Creek Member - Wasatch Fm. Transition 535 PBTD @ 5693' KB TD @ 5740'KB After Rework - Wasatch Formation 6000 ft.

CONTRACTOR OF A PROPERTY OF A

FORM 9

STATE OF UTAH DIVISION OF OIL, GAS AND MINING

21101011 01 010, 010 7,140 1411411	144	
		5. Lease Designation and Serial Number:
		See Attached 6. If Indian, Allottee or Tribe Name:
SUNDRY NOTICES AND REPORTS	ON WELLS	n/a
Do not use this form for proposals to drill new wells, deepen existing wells, or to reent	er plugged and abandoned wells.	7. Unit Agreement Name:
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for a	uch proposals.	See Attached
1. Type of Well: OIL 🔯 GAS 🗌 OTHER:	DECEMED	8. Well Name and Number: See Attached
2. Name of Operator: Inland Production Company	OCT_1_3_1997	9. API Well Number: See Attached
3. Address and Telephone Number:	1/1/: 2 11/2/2	10. Field and Pool, or Wildcat:
475 - 17th Street, Suite 1500, Den	ver, CO 80202	See Attached
4. Location of Well		
Footages: See Attached Exhibit		County:
OQ, Sec.,T.,R,M.:		State:
11. CHECK APPROPRIATE BOXES TO INDICATE N	ATURE OF NOTICE, REPOR	T, OR OTHER DATA
NOTICE OF INTENT (Submit in Duplicate)	- · ·	JENT REPORT Iginal Form Only)
☐ Abandon ☐ New Construction	Abandon •	☐ New Construction
☐ Repair Casing ☐ Pull or Alter Casing	Repair Casing	☐ Pull or Alter Casing
Change of Plans	Change of Plans	☐ Reperforate
☐ Convert to Injection ☐ Reperforate	Convert to Injection	☐ Vent or Flare
☐ Fracture Treat or Acidize ☐ Vent or Flare	☐ Fracture Treat or Acidize	☐ Water Shut-Off
☐ Multiple Completion ☐ Water Shut-Off	Tractice Treat of Acidize	
☑ Other <u>Change of Operator</u>	Change of oper	acor
	Date of work completion9-3	0-97'
Approximate date work will start	Report results of Multiple Completions and COMPLETION OR RECOMPLETION REPORT	Recompletions to different reservoirs on WELL T AND LOG form.
	Must be accompanied by a cement verification.	on report.
 DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and givertical depths for all markers and zones pertinent to this work.) 	e pertinent dates. If well is directionally drilled, g	live subsurface locations and measured and true
Effective September 30, 1997, Inland Productivells on the attached list. The previous ope	on Company will take o	ver operations of the
The previous ope		urces Energy Company
	1601 Lewis Ave	
	<u>.</u>	59102
Effective Sentember 30 1007 Inland Dreducti		
Effective September 30, 1997, Inland Producti and conditions of the leases for operations of	conducted on the leased	ole under the terms
thereof under State of Utah Statewide Bond No	9. 4471291.	iding of a polition
		OCT 1 (1997)
	a	
13. Name & Signature: CHRIS	A. POTTER, ATTORNEY-IN-FA	ACT Date: 9/30/97

This space for State use only)

RECEIVED

OCT 1 0 1997

DECEINED

TRANSFER OF AUTHORITY TO INJECT - UIC FORM 5

OCT 1 3 1997

Well name and number: See Attached	**JONAH (GREEN RIVER) UNIT
Field or Unit name: See Attached	API no. See Attached
Well location: QQ section towns	nip range county
See Attached Effective Date of Transfer:September	30, 1997
CURRENT OPERATOR	
Transfer approved by:	·
Name David M. McCoskery	Company Equitable Resources Energy Co.
Signature All Milly	Address 1601 Lewis Avenue
Title Director of Operations & Engineering	Billings, MT 59102
Date <u>9-30-97</u>	Phone (406) 259-7860'
Comments:	
· · · · · · · · · · · · · · · · · · ·	, <u></u>
NEW OPERATOR	
Transfer approved by:	
Name Christ Potter	Company Inland Production Company
	Address 475 - 17th Street, Suite 1500
Title CHRIS A. POTTER, ATTORNEY-IN-FACT	Denver, CO 80202
Date <u>9-30-97</u>	Phone (303) 292–0900
Comments:	
(State use only) Transfer approved by	Title Envisor Maugen
Approval Date 1-20-98	(AUST # 728-2
	UK\ act 26 1997

(3/89)

Injection wells

1 .

Injection Wells for Inland Change of O							
WELL NAME	LOCATION	COUNTY	ST	FIELD NAME	API NUMBER	LEASE NO.	AGREEMENT NO.
AMERADA GUINAND #1	C)A/A A 7.00 055	LUNITALL		COVOTE DACIN	10.047.00045.00	11711040074)/	UT1170005A
	SWNW 7 8S 25E	UINTAH		COYOTE BASIN	43-047-20245-00	UTU016271V	UTU72085A
COYOTE BASIN #42-6X	SENE 6 8S 25E	UINTA		COYOTE BASIN	43-047-32346-00	UTU017439B	UTU72085A
EAST RED WASH FED. #4-6	SWSE 6 8S 25E	UINTAH		COYOTE BASIN	43-047-20261-00	UTU020309D	UTU72085A
ÉAST RED WASH #2-5	NWNW 58S 25E	UINTA	UT	COYOTE BASIN	43-047-20252-00	UTU063597A	UTU72085A
ÁLLEN FEDERAL #1	SESE 6 9S 17E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-15779-00	UTU020252A	UTU72086A
ALLEN FEDERAL #13-6	NWSW 69S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-30918-00	UTU020252A	UTU72086A
ALLEN FEDERAL #22-6	SENW 69S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-30919-00	UTU020252A	UTU72086A
ALLEN FEDERAL #31-6	LOT2 6 9S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31195-00	UTU020252A	UTU72086A
MONUMENT BUTTE FED. #11-6	NWNW 69S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31362-00	UTU020252A	UTU72086A
MONUMENT FEDERAL #11-7J	NW NW 7 9S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31492-00	UTU44426	UTU72086A
MONUMENT BUTTE #13-5	NWSW 59S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31370-00	01044420	UTU72086A
MONUMENT BUTTE #22-5	SENW 5 9S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31384-00	UTU020252	UTU72086A
MONUMENT BUTTE #24-5	SESW 5 9S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31375-00	UTU020252	UTU72086A
MONUMENT BUTTE FED. #24-6	SESW 6 9S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31363-00	UTU020252A	UTU72086A
MONUMENT BUTTE #31-7	NWNE 7 9S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31405-00	UTU72106	UTU72086A
MONUMENT BUTTE FED. #33-6	NWSE 6 9S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31361-00	UTU020252A	UTU72086A
MONUMENT BUTTE FED. #42-6	SENE 6 9S 17E	DUCHESNE		MONUMENT BUTTE (J)			
MONUMENT BUTTE FED. #12-11	SWNW 119S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31364-00 43-013-31417-00	UTU020252A	UTU72086A
MONUMENT BUTTE FED. #14-11	SWSW 119S 16E	DUCHESNE		MONUMENT BUTTE (J)		UTU096550	UTU72086A
MONUMENT BUTTE #12-12	SWNW 129S 16E	DUCHESNE			43-013-31374-00	UTU096547	UTU72086A
MONUMENT BUTTE #12-12	SWSW 129S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31410-00	UTU096550	UTU72086A
MONUMENT BUTTE #21-14	NENW 149S 16E			MONUMENT BUTTE (J)	43-013-31411-00		UTU72086A
MONUMENT BUTTE #21-14		DUCHESNE		MONUMENT BUTTE (J)	43-013-31421-00		UTU72086A
	NESW 119S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31369-00	UTU096550	UTU72086A
MONUMENT BUTTE FED. #23-15 MONUMENT BUTTE #32-11	NESW 159S 17E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31373-00	UTU017985	UTU72086A
	SWNE 119S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31386-00		UTU72086A
MONUMENT BUTTE #32-12	SWNE 129S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31419-00		UTU72086A
MONUMENT BUTTE #41-14	NENE 149S 16E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-31408-00	UTU096550	UTU72086A
MONUMENT BUTTE #43-11	NESE 119S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31002-00	UTU096550	UTU72086A
MONUMENT BUTTE FED. #32-15	SWNE 159S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31368-00	UTU017985	UTU72086A
MONUMENT BUTTE FED. #34-10	SWSE 109S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31416-00	UTU017985	UTU72086A
MONUMENT BUTTE FED. #41-15	NENE 159S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31367-00	UTU017985	UTU72086A
MONUMENT BUTTE FED. #42-1	SENE 1 9S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31404-00	UTU40652	UTU72086A
MONUMENT BUTTE FED. #44-1J	SESE 1 9S 16E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-31415-00	UTU44426	UTU72086A
C&O GOV'T #4	NESW 129S 16E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-30742-00	UTU035521A	UTU72086A
MONUMENT BUTTE FED. #1-13	NWSW 1 9S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-30702-00	UTU18399	UTU72086A
MONUMENT BUTTE FED. #1-33	NWSE 1 9S 16E	DUCHESNE	UT	MONUMENT BUTTE (J)	43-013-30735-00	UTU52013	UTU72086A
MONUMENT BUTTE #1-24	SESW 1 9S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-30701-00	UTU18399	UTU72086A
WALTON FEDERAL #34-11	SWSE 119S 16E	DUCHESNE		MONUMENT BUTTE (J)	43-013-31003-00	UTU096550	UTU72086A
MONUMENT STATE #11-2-9-17CD	NW NW 2 9S 17E	DUCHESNE		MONUMENT BUTTE (CD)	43-013-42685	ML 45555	

11422

11426

11438 1143 i (406) 259-7860 Telephone (406) 245-1361 Fax

December 10, 1997

Lisha
State of Utah
Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, UT 84114-5801

Dear Lisha:

RE: Equitable Sale of Utah Properties

Effective September 30, 1997, Equitable Resources Energy Company sold all of its Utah properties to Inland Production Company.

Please feel free to contact me if you require additional information.

Sincerely,

Molly Conrad

Agent for Equitable Resources

Energy Company

/mc



Crazy Mountain Oil & Gas Services P.O. Box 577 Laurel, MT 59044 (406) 628-4164 (406) 628-4165

TO: Lishar St of Wan.

FROM.

Molly Conrad

Crazy Mountain Oil & Gas Services

(406) 628-4164

Pages Attached - Including Cover Sheet 2.

NOTE: Here is the letter you requested. Callief you need anything further.



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office P.O. Box 45155 Salt Lake City, UT 84145-0155 1/ 1/ 1/ 1/4 1998

IN REPLY REFER TO UT-931

January 13, 1998

Inland Production Company 475 17th Street, Suite 1500 Denver, Colorado 80202

Re:

Jonah (Green River) Unit

Duchesne County, Utah

Gentlemen:

On January 13, 1998, we received an indenture dated November 17, 1997, whereby Equitable Resources Energy Company resigned as Unit Operator and Inland Production Company was designated as Successor Unit Operator for the Jonah (Green River) Unit, Duchesne County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective January 13, 1998. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under Jonah (Green River) Unit Agreement.

Your statewide (Utah) oil and gas bond No. 0056 will be used to cover all operations within the Jonah (Green River) Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Robert A. Henricks

Robert A. Henricks Chief, Branch of Fluid Minerals

Enclosure

: District Manager - Vernal (w/enclosure)

Division of Oil Gas & Mining /

Minerals Adjudication Group U-932

File - Jonah (Green River) Unit (w/enclosure)

MMS - Data Management Division

Agr. Sec. Chron

Fluid Chron

U-931:TAThompson:tt:1/13/98

Page No. 01/13/98

WELL STATUS REPORTS UTAH STATE OFFICE

STATUS

INSPECTION ITEM API NO. WELL QTQT SEC TWN RNG WELL LEASE NAME OPERATOR

NUMBER

** INSPECTION	ITEM UTU72086A	IONAH	(GR) SECO	MU A D V	V DECO	VEDY	IINTT		
UTU72086A	430131511100s1		NWSW	12 9		16E	POW	UTU035521A	EQUITABLE RESOURCES ENERG
UTU72086A	430131578000\$1		NWNW	5 9		17E	POW	UTU020252	EQUITABLE RESOURCES ENERG
UTU72086A	430131577900s1		SESE	6 9	-	17E	WIW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430131578900\$1		SESW	11 9	_	16E	POW	UTU096547	EQUITABLE RESOURCES ENERG
UTU72086A	430131579200s1		SESE	11 9		16E	POW	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133070200\$1		NWSW	1.9		16E	WIW	UTU18399	EQUITABLE RESOURCES ENERG
UTU72086A	430133070300s1		SWSW	1 9	_	16E	POW	UTU18399	EQUITABLE RESOURCES ENERG
UTU72086A	430133064600\$1		NESW	1.9	_	16E	POW	UTU18399	EQUITABLE RESOURCES ENERG
UTU72086A	430133070100\$1		SESW	1 9	_	16E	WIW	UTU18399	EQUITABLE RESOURCES ENERG
UTU72086A	430133073500s1		NWSE	1 9		16E	WIW	UTU52013	EQUITABLE RESOURCES ENERG
UTU72086A	430133073600s1		SWSE	1.5	_	16E	POW	UTU52013	EQUITABLE RESOURCES ENERG
UTU72086A	430133073400\$1		NESE	1 9	es '	16E	POW	UTU52013	EQUITABLE RESOURCES ENERG
UTU72086A	430133136200\$1	11-6	L4	6 9	s '	17E	WIW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430133149200s1	11-7J	NUNU	7 9	es '	17E	WIW	UTU44426	EQUITABLE RESOURCES ENERG
UTU72086A	430133088900s1	12-1	NWNE	12 9	os '	16E	POW	UTU44426	EQUITABLE RESOURCES ENERG
UTU72086A	430133141700s1	12-11J	SWNW	11 9	s :	16E	WIW	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133141000s1	12-12J	SWNW	12 9	s 1	16E	WIW	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133061100s1	12-5	SWNW	5 9	PS 1	17E	POW	UTU020252	EQUITABLE RESOURCES ENERG
UTU72086A	430133058200s1	12-6	SWNW	6 9	PS 1	17E	POW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430133149300s1	12-7J	SWNW	7 9	s 1	17E	POW	UTU44426	EQUITABLE RESOURCES ENERG
UTU72086A	430131579000s1	13-11J	NUSU	11 9	s 1	16E	POW	UTU096547	EQUITABLE RESOURCES ENERG
UTU72086A	430133137000s1	13-5	NUSU	5 9	s 1	17E	WIW	UTU020252	EQUITABLE RESOURCES ENERG
UTU72086A	430133091800s1	13-6	NWSW	6 9)s 1	17E	WIW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430133137400s1	14-11	SWSW	11 9)s 1	16E	WIW	UTU096547	EQUITABLE RESOURCES ENERG
UTU72086A	430133141100\$1	14-12J	SWSW	12 9	9 S 1	16E	WIW	UTU035521A	EQUITABLE RESOURCES ENERG
UTU72086A	430133138500\$1	14-5	SWSW	5 9	PS 1	17E	POW	UTU020252	EQUITABLE RESOURCES ENERG
UTU72086A	43013151120081	2	NWSE	12 9	9 S 1	16E	POW	UTU035521	EQUITABLE RESOURCES ENERG
UTU72086A	430131579300s1	2	NWNE	14 9	PS 1	16E	POW	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133060300s1	2-1	L1	1 9)s 1	16E	POW	UTU33992	EQUITABLE RESOURCES ENERG
UTU72086A	430133140600X1	21-12J	NENW -	12-9	'S1	16E	-ABD	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133142100\$1	21-14J	NENW	14 9)s 1	16E	WIW	UTU096547	EQUITABLE RESOURCES ENERG
UTU72086A	430133142200x1	21-15J	NENW	15-9	3 1	lóE -	ABD	UTU017985	-EQUITABLE RESOURCES ENERG
UTU72086A	430133061200s1	21-5	NENW	5 9	' S 1	17E	POW	UTU020252	EQUITABLE RESOURCES ENERG
UTU72086A	430133058400s1	21-6	L3	6 9	rs 1	17E	POW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430131579600\$2	22-12J		12 9		16E	POW	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	43013306340081		SENW	15 9		16E	POW	UTU01 798 5	EQUITABLE RESOURCES ENERG
UTU72086A	430133138400s1		SENW	5 9	PS 1	17E	WIW	UTU020252	EQUITABLE RESOURCES ENERG
UTU72086A	430133091900s1		SENW	6 9		17E	WIW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430133136900\$1		NESW	11 9		16E	WIW	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133137300s1		NESW	15 9		16E	WIW	UTU017985	EQUITABLE RESOURCES ENERG
UTU72086A	430133138300s1		NESW	5 9		17E	POW	UTU020252	EQUITABLE RESOURCES ENERG
UTU72086A	430133055800\$1		NESW	6 9		17E	POW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430133140900\$1		SESW	12 9		16E	POW	UTU035521A	EQUITABLE RESOURCES ENERG
UTU72086A	43013306310081		SESW	15 9		16E	POW	UTU017985	EQUITABLE RESOURCES ENERG
UTU72086A	430133137500\$1		SESW	5 9		17E	WIW	UTU020252	EQUITABLE RESOURCES ENERG
UTU72086A	430133136300\$1		SESW	6 9		17E	WIW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430131579100\$1		WWW	14 9		16E	POW	UTU096547	EQUITABLE RESOURCES ENERG
UTU72086A	430133061300s1	51-15	NWNE	15 9	צי 1	16E	POW	UTU017985	EQUITABLE RESOURCES ENERG


Page No. 01/13/98 2

WELL STATUS REPORTS UTAH STATE OFFICE

INSPECTION ITEM	API NO.	WELL Number	QTQT	SEC	TWN	RNG	WELL STATUS	LEASE NAME	OPERATOR
UTU72086A	430133141300s1	31-1J	L2	1	9s	16E	POW	UTU33992	EQUITABLE RESOURCES ENERG
UTU72086A	430133119500s1	31-6	L2	6	9s	17E	WIW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430133140500s1	31-7J	NWNE	7	9s	17E	WIW	UTU44426	EQUITABLE RESOURCES ENERG
UTU72086A	430133138600s1	32-11	SWNE	11	9 S	16E	WIW	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133141900s1	32-12J	SWNE	12	9 S	16E	WIW	UTU035521	EQUITABLE RESOURCES ENERG
UTU72086A	430133136800s1	32-15	SWNE	15	98	16E	WIW	UTU017985	EQUITABLE RESOURCES ENERG
UTU72086A	430133141400s1	32-1J	SWNE	1	98	16E	POW	UTU33992	EQUITABLE RESOURCES ENERG
UTU72086A	430133055900s1	32-6	SWNE	6	98	17E	POW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430133145100s1	33-11J	NWSE	11	9 S	16E	OSI	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133063200s1	33-15	NWSE	15	9S	16E	POW	UTU017985	EQUITABLE RESOURCES ENERG
UTU72086A	430133136100s1	33-6	NWSE	6	9 S	17E	WIW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	43013314160081	34-10J	SWSE	10	9\$	16E	WIW	UTU017985	EQUITABLE RESOURCES ENERG
UTU72086A	430133100300s1	34-11	SWSE	11	9 S	16E	WIW	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133058600s1	34-6	SWSE	6	9s	17E	POW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430133074200s1	4	NESW	12	9s	16E	WIW	UTU035521A	EQUITABLE RESOURCES ENERG
UTU72086A	430131579500s1	4	SENW	11	9s	16E	PO₩	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133148700s1	41-12J	NENE	12	9s	16E	POW	UTU44426	EQUITABLE RESOURCES ENERG
UTU72086A	430133140800\$1	41-14J	NENE	14	9s	16E	WIW	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133136700s1	41-15	NENE	15	9s	16E	WIW	UTU017985	EQUITABLE RESOURCES ENERG
UTU72086A	430133058100s1	41-6	NENE	6	9s	17E	POW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430133006600s1	42-11J	SENE	11	9s	16E	POW	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133148600s1	42-12J	SENE	12	9 s	16E	POW	UTU035521	EQUITABLE RESOURCES ENERG
UTU72086A	430133063300s1	42-15	SENE	15	9s	16E	POW	UTU017985	EQUITABLE RESOURCES ENERG
UTU72086A	430133140400s1	42-1J	SENE	1	9s	16E	WIW	UTU40652	EQUITABLE RESOURCES ENERG
UTU72086A	430133136400s1	42-6	SENE	6	9s	17E	WIW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	43013310020081	43-11J	NESE	11	9s	16E	WIW	UTU096550	EQUITABLE RESOURCES ENERG
UTU72086A	430133058300\$1	43-6	NESE	6	9 S	17E	POW	UTU020252A	EQUITABLE RESOURCES ENERG
UTU72086A	430133063000s1	44-10	SESE	10	9 S	16E	POW	UTU017985	EQUITABLE RESOURCES ENERG
UTU72086A	430133141500s1	44-1J	SESE	1	9s	16E	WIW	UTU44426	EQUITABLE RESOURCES ENERG
UTU72086A	430133092600s1	7-A	NENE	7	9 S	17E	POW	UTU44426	EQUITABLE RESOURCES ENERG
UTU72086A	430133096100s1	7-C	NENW	7	9s	17E	POW	UTU44426	EQUITABLE RESOURCES ENERG

JONAH (GREEN RIVER) UNIT DUCHESNE COUNTY, UTAH

EFFECTIVE: JULY 1, 1993



16E

UNIT OUTLINE (UTU72086A)

4,221.61 ACRES

SECONDARY ALLOCATION FEDERAL 100.00% Division of Oil, Gas and Mining

OPERATOR CHANGE WORKSHEET

Attach all documentation received by the division regarding this change. Initial each listed item when completed. Write N/A if item is not applicable.

Routing:	W/
1-IlpCfic	GVACE
2-04-11	7-KAS
3-DT8213	8-SI V
4-VLD	9-FILE
5-JPR	
. /	

										L5_JP#		
		nge of Operato	•	d)		gnation of ator Name	•	Only				-
The	ope	rator of the we	ll(s) listed	below has ch	anged, ef	ffective: _	9-30-9	7				
TO	: (ne	(address) _ - - I	PO BOX 1 ROOSEVEL	T UT 84066 01)722-5103	5	FROM:	` •	erator) (address)	PO BOY LAURE C/O CY Phone	X 577	9044 N O&G)628-	
WE	LL(S) attach addition	nal page if ne	eded:		*JONAH	(GREEN	RIVER)	UNIT	-		
Name Name Name Name Name Name		**SEE ATTACH		API: API:	<u>, -3i3k</u>	Entity: Entity: Entity: Entity: Entity:		S S	Г Г Г	R 1 R 1 R 1	Lease: Lease: Lease: Lease: Lease: Lease:	
OPI Lec	1. 2.	(r649-8-10) S form). (factorial) form). (factorial)	Sundry or or or or or or or or	her legal docu	ımentatio							
HA PLA	3.4.	FOR INDIAN note of BLM changes shouthrough 9 be	I. Is the co 	mpany regist DERAL WE comments sec	ered wit LLS ON ction of t	h the state LY. The Finis form.	e? (yes/ BLM has BLM ap	no)s been cor pproval o	If yes, so tacted reference of the second se	show cor egarding I and In	npany this cl dian v	file number: nange. Makewell operator
Je je	5.6.	Changes have (1-14-98) Cardex file h		red in the Oil #\n fn 1-14-9 dated for each	l and Ga g & Ui h well lis	s Informa C/DB≻ / sted above.	tion Sys -14-98	stem (327	(0) for ea	ch well l	isted a	ibove.
Lec Lec	7. 8.	Well file labe Changes have to Trust Land	els have be been inclu	en updated fo	or each wo	ell listed al	bove.	and Acco				
120	9.	A folder has reference duri	been set u	p for the Op	erator C	Change file original de	e, and a	copy of	this page	e has bee	en pla	ced there for

Division of Oil, Gas and Mining

OPERATOR CHANGE WORKSHEET

Attach all documentation received by the division regarding this change. Initial each listed item when completed. Write N/A if item is not applicable.

Routing:	V
1-1100	Gline
2-04-11	7-KAS
3-DT8213	8-SI √
4-VLD	9-FILE
5-JPB	

			L5_JD28	
		hange of Operator (well sold) Designation of Agent Operator Name Change Only		
The	ope	perator of the well(s) listed below has changed, effective: 9-30-97		
то	: (ne	(address) PO BOX 1446 (address) PO ROOSEVELT UT 84066 LAU	ITABLE RESOURCES DESCRIPTION OF THE PROPERTY O	
		Phone: (801) 722–5103	one: (406)628-4164 count no. N9890	
WE	LL(L(S) attach additional page if needed: *JONAH (GREEN RIVER) UNIT		
Name Name Name Name Name Name		**SEE ATTACHED** API: 43-013-313c/ Entity: S T API: Entity: S T	R Lease: R Lease:	
OPI	1. 2.	 ATOR CHANGE DOCUMENTATION (r649-8-10) Sundry or other legal documentation has been received from the FO form). (fee / 12-10-97) (r649-8-10) Sundry or other legal documentation has been received from the form). (fee / 10-13-97) 		
ᄱᄱ	3.	. The Department of Commerce has been contacted if the new operator above wells in Utah. Is the company registered with the state? (yes/no) If yes		
Jec jec	4.	FOR INDIAN AND FEDERAL WELLS ONLY. The BLM has been contacted note of BLM status in comments section of this form. BLM approval of Federal changes should ordinarily take place prior to the division's approval, and befer through 9 below.	eral and Indian well	operator
Le uc	5.6.	Changes have been entered in the Oil and Gas Information System (3270) for (1-14-98) * U(C/Que 4π βπ 1-14-98 * U(C/DBese 1-14-98). Cardex file has been updated for each well listed above.	each well listed above	e.
Jec Jec	7.	Well file labels have been updated for each well listed above.		
Lec	8.	Changes have been included on the monthly "Operator, Address, and Account C to Trust Lands, Sovereign Lands, UGS, Tax Commission, etc. (1-14-98)	hanges" memo for dis	tribution
Yec —	9.	A folder has been set up for the Operator Change file , and a copy of this preference during routing and processing of the original documents.	page has been placed t	there for

Page No. 4 06/16/97

STATE OF UTAH INVENTORY OF INJECTION WELLS

******** ****** ****** ****** *** ***	COUNT
CONCERT OIL 42 012 2022	****
COACTAL OIL 43-013-30337 G. HANSON #2 02S 03W 4 INJD Y	
CONCERN OFF 42 012 20251 TRICE 025 04W 25 INOD Y	
CONCENT OIL 42 012 20201 ENDER 2 020 04W 32 INOD	
CONCENT OIL 42 012 20240 TREE TIE 02B USW II INOD Y	
CONCENT OTT 42 04F 21005	
COCUDANTE DEC. 42 027 20015	
COCUDAND DDC 42 025 23 20 CO	
COCUDAND DIG 42 029 21145	
COCUDAND DEG. 42 025 24551	
COCHDANE DEC 42 027 20762 2 06	
CDOCC CDEEN 42 027 16060 CONTENT TOWN	
CDOCC CDEBY 42 025 00115 20115 116 201 5 INOD	
CDOCC CDEDY 42 025 COLCA THE TID ZOE 5 INOD	
ENCEDOU EVDI 42 012 21000 FTTTTTTTTTTTTTTTTTTTTTTTTTTTTTTTTTT	
ENCEDCII EVDI 42 012 21040 EDEBER 11 5 000 101 55 110W N	
ENCEDCH DVDI 42 012 210 CO TODATA 15 5 000 10E 55 INOW N	
PHOTDOH PURI 42 040 240 2 100 100 100 55 INOW	
ENSERCH EXPL 43-013-31225 FEDERAL 14-3 08S 16E 34 INJW N	
ENSERCH EXPL 43-013-31272 FEDERAL 21-4 09S 16E 4 INJW N	
ENSERCH EXPL 43-013-31205 FEDERAL 41-5 09S 16E 5 INJW N	
ENSERCH EXPL 43-013-30670 FEDERAL 32-5 09S 16E 5 INJW N	
ENSERCH EXPL 43-013-30913 44-5H 09S 17E 5 INJW N	
ENSERCH EXPL 43-013-30678 42-8H 09S 17E 8 INJW N	
ENSERCH EXPL 43-013-31457 22-8H 09S 17E 8 INJW N	
ENSERCH EXPL 43-013-30679 31-8H 09S 17E 8 INJW N	
ENSERCH EXPL 43-013-31049 22-9H 09S 17E 9 INJW N	
ENSERCH EXPL 43-013-30887 11-9H 09S 17E 9 INJW N	
ENSERCH EXPL 43-013-31108 33-9H 09S 17E 9 INJW N	
ENSERCH EXPL 43-013-30682 24-9H 09S 17E 9 INJW N	
ENSERCH EXPL 43-013-30656 13-9H 09S 17E 9 INJW N	
EQUITABLE RE 43-013-31364 FEDERAL 42-6 09S 17E 6 INJW Y	
EQUITABLE RE 43 013-31361 FEDERAL 33-6 09S 17E 6 INJW Y	
EQUITABLE RE 43-013-15779 FEDERAL 1-6 09S 17E 6 INJW Y	
EQUITABLE RE 43-013-31362 FEDERAL 11-6 09S 17E 6 INJW Y	
EQUITABLE RE 43-013-30919 FEDERAL 22-6 09S 17E 6 INJW Y	
EQUITABLE RE 43-013-31363 FEDERAL 24-6 09S 17E 6 INJW Y	
EQUITABLE RE 43-013-30918 FEDERAL 13-6 09S 17E 6 INJW Y	
EQUITABLE RE 43-047-15681 PARIETTE BEN 09S 19E 7 INJD Y	
EQUITABLE RE 43-013-30735 FEDERAL 1-33 09S 16E 1 INTW N	
EQUITABLE RE 43-013-30702 FEDERAL 1-13 09S 16E 1 INTW N	
EQUITABLE RE ~43-013-30701 : 1-24 09S 16E 1 INJW N	
EQUITABLE RE 43-013-31404 42-1J 09S 16E 1 INJW Y	
EQUITABLE RE ~43-013-3141 5	
EQUITABLE RE 🛂3-013-31416 34-10J 09S 16E 10 INTW N	
EQUITABLE RE 43-013-31002 43-11J 09S 16E 11 INJW N	
EQUITABLE RE 43-013-31369 23-11J 09S 16E 11 INTW N	
EQUITABLE RE 13-013-31417 12-11J 09S 16E 11 INJW N	
EQUITABLE RE 43-013-31386 32-11J 09S 16E 11 INJW N	
EQUITABLE RE 43-013-31374 14-11J 09S 16E 11 INJW N	
EQUITABLE RE 43-013-31003 FEDERAL 34-1 09S 16E 11 INJW N	
EQUITABLE RE 43-013-31419 32-12J 09S 16E 12 INJW N	
EQUITABLE RE 43-013-31411 14-12J 09S 16E 12 INJW N	
EQUITABLE RE 43-013-30742 GOVT C&O #4 09S 16E 12 INJW N	




April 30, 1998

Mr. Dan Jarvis
State of Utah
Division of Oil, Gas & Mining
P. O. Box 145801
Salt Lake City, Utah 84114-5801

RE:

Mechanical Integrity Test

Monument #33-6 Sec 6-T9S-R17E Duchesne County, Utah



Dear Mr. Jarvis:

Please find attached, Form 3160-5, Sundry Notice and Report on Wells, for work performed on the above referenced well. Should you have any questions, please contact me at (303) 382-4434.

Sincerely,

Debbie E. Knight

Manager, Regulatory Compliance

Whie Knight

cc: Mr. Edwin Forsman, BLM

FORM 3160-5 (June 1990)

UNITED STATES MENT OF THE INTERIOR

_	FORM APPROVEI
	Budget Bureau No.
	Expires: March 31


FORM APPROVED				
Budget Bureau No. 1004-0135				
Evnires: March 31 1993				

	Expires:	March 31, 1993
5	Lease Design	ation and Serial No

BUREAU OF	LAND MANAGEMENT	Expires: March 31, 1993
		5. Lease Designation and Serial No.
SUNDRY NOTICES AN	D REPORTS ON WELLS	U-020252-A
Do not use this form for proposals to drill or to de	epen or reentry a different reservoir.	6. If Indian, Allottee or Tribe Name
	OR PERMIT -" for such proposals	l NA
		7. If Unit or CA, Agreement Designation
	TRIPLICATE	NA NA
1. Type of Well Oil Gas		8. Well Name and No.
Well Well X Other	WIW	MONUMENT 33-6
wen onler		9. API Well No.
2. Name of Operator		43-013-31361
INLAND PRODUCTION COMPANY		10. Field and Pool, or Exploratory Area
3. Address and Telephone No.		MONUMENT BUTTE
475 17TH STREET, SUITE 1500, DENVE	R, COLORADO 80202 (303) 292-0900	11. County or Parish, State
4. Location of Well (Footage, Sec., T., R., m., or Survey Description)	<u> </u>	
1832 FSL 1829 FEL NW/SE Section	n 6, T09S R17E	DUCHESNE COUNTY, UTAH
	,	
) TO INDICATE NATURE OF NOTICE, REPO	RT, OR OTHER DATA
TYPE OF SUBMISSION	TYPE OF	ACTION
Notice of Intent X Subsequent Report Final Abandonment Notice	Abandonment Recompletion Plugging Back Casing Repair Altering Casing X Other MIT	Change of Plans New Construction Non-Routine Fracturing Water Shut-Off Conversion to Injection Dispose Water (Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)
• • • • • • • • • • • • • • • • • • • •		3-12-98. Casing was pressured

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct Signed Lehlue Xmyht	Title	Manager, Regulatory Compliance	Date	4/30/98
(This space for Federal or State office use) Approved by	Title		Date	
Conditions of approval, if any: CC: UTAH DOGM				





February 28, 2000

State of Utah
Division of Oil, Gas & Mining
Attn: Dan Jarvis
1594 West North Temple - Suite 1210
P.O. Box 145801
Salt Lake City, Utah 84114-5801

RE: Step-Rate Test Jonah #33-6

Dear Dan:

Please find enclosed Step-Rate Tests (SRT) results on the Jonah #33-6 injection well in the Jonah Unit. Inland Production Company conducted the SRT on February 25, 2000. Due to the results of the SRT Inland is requesting a change in the maximum allowable injection pressure from 2200 psi to 2165 psi for this well.

Thank you for your assistance. If you have any questions or need further information, please call me at (435) 646-3721.

Sincerely.

Brad Mecham


Operations Manager

/bm


STATE OF UTAH

(Do not ase this form for proposals to delity to deepen or plug back to a different receivoir. Out "APPLICATION FOR PERSHE". For each proposals.) OIL GAS JOHN STREET NOT PERSHET. IN SECTION OIL OAT AGREEMENT NAME JONAH NAME OF OPERATOR ROUTE #3 BOX 3630, MYTON, UTAH 84052 (435) 646-3721 LOCATION OF WELL (Report beginned userly and in secondance with any State requirements.* LOCATION OF WELL (Report beginned userly and in secondance with any State requirements.* NW/SE 1832 FSL 1829 FEL 18 C. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data NOTICE OF INTERVION TO. WATER SULCOT BASE SUBSECUENT REPORT OF REPORT OF SURFACE ARABON.* SUBSECUENT REPORT OF REPORT OF REPORT OF SURFACE ARABON.* SUBSECUENT REPORT OF SURF	DEPARTMENT OF NATURAL RESOURCES			
SUNDRY NOTICES AND REPORTS ON WELLS (Do not use this form for proposals to drill or to deepen or plag back to a different reservoir. (De "APPLICATION FOR PERMIT—" for such proposals. (Do not use this form for proposals to drill or to deepen or plag back to a different reservoir. (De "APPLICATION FOR PERMIT—" for such proposals. (Do not use this form for proposals to drill or to deepen or plag back to a different reservoir. (De "APPLICATION FOR PERMIT—" for such proposals. (DO not use this form for proposals to drill or to deepen or plag back to a different reservoir. (DO not use this form for proposals to drill or to deepen or plag back to a different reservoir. (DO not use this form for proposals to drill or to deepen or plag back to a different reservoir. (DO not use this form for proposals to drill or to deepen or plag back to a different reservoir. (DO not use this form for proposals to drill or to deepen or plag back to a different reservoir. (DO not use this form for proposals to drill or to deepen or plag back to a different reservoir. (DO not use this form for proposals to drill or to deepen or plag back to a different reservoir. (DO NOT PERMITTION TO COMPARY) (DO NOT PERM	DIVISION OF OIL, GAS, AND MINING			
(Do not ace this form for proposals to dells or a despen or plug back to a different receivals. Out APPLICATION FOR PRIMATE—for such proposals. OUT ASSESS OF OPERATOR NUMBER ON THE ABOUTE TO SHADOR PRIMATE—for such proposals. OUT BY A DO OFFICE ATOR ROUTE AS 30 AS 3630, MYTON, UTAH \$4052 (435) 646-3721 LOCATION OF WELL (Report beasines deathy and in accordance with any State requirements.* A DO NUMBER A DO NUMBER 1832 FSL 1829 FEL INWISE 1832 FSL 1829 FEL OTHER AND FOOL OR WELCATO SHEVEY OR AREA NOVICE OF INTERPRETATION 10. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data NOTICE OF INTERPRETATION 10. THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF BASE OF ACTIONS (Show whether OF, RT, CR, etc.) THE WATER SHUT OF THE ACTION (SHOW WHITE OF ACTION (SHO	SUNDRY NOTICES AND REPORTS	ON WELLS		
NAME OF OFFERATOR INLAND PRODUCTION COMPANY ADDRESS OF OFFERATOR ROUTE #3 BOX 3630, MYTON, UTAH 84052 (435) 646-3721 LOCATION OF PELL (Report beating clearly and in accordance with any State requirements.* See also against 7 below) At curies: NW/SE 1832 FSL 1829 FEL 15. ELEVATIONS (Show whether DF, RT, GR, etc.) \$1. SEC, T.A., S., COR RILL AND SURVEY OR MARK NOVIMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK NOVIMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK NOVIMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK NOVIMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK NOVIMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK NOVIMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK NOVIMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK NOVIMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK NOVIMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK NOVIMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK NOVIMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK NOVIMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK NOVIMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK NOVIMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK NOVIMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK NOVIMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK NOVIMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK NOVIMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK MONUMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK MONUMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK MONUMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK MONUMENT BUT12. 11. SEC, T.A., S., COR RILL AND SURVEY OR MARK MONUMENT BUT12. 12. SECOND RILL AND SURVEY OR MARK MONUMENT BUT12. 13. SEC, T.A., S., COR RILL AND SURVEY OR MARK MONUMENT BUT12. 14. SEC, T.A., S., COR RILL AND SURVEY OR MARK MONUMENT BUT12. 15. SEC, T.A., S., COR RILL AND SURVEY OR MARK MONUMENT BUT12. 16. SECOND	(Do not use this form for proposals to drill or to deepen or plug back to a diffe			
NAME OF OFERATOR NAME OF OFERATOR ROUTE #3 BOX 3630, MYTON, UTAH 84052 (3435 64-63721 LOCATION OF WELL (Report beating clearly and in accordance with any State requirements.* See also agent of bloom.) At ourse NW/SE 1832 FSL 1829 FEL 15. ELEVATIONS (Show whether DF, RT, CR, ce.) SURVYOR AREA NW/SE Section 6, T09S R17E 4 AP NUMBER 4 AP NUMBER 43-013-31361 15. ELEVATIONS (Show whether DF, RT, CR, ce.) SURVYOR AREA NOTICE OF INTENTION TO. 15. ELEVATIONS (Show whether DF, RT, CR, ce.) SURVYOR AREA NOTICE OF INTENTION TO. 15. ELEVATIONS (Show whether DF, RT, CR, ce.) SUBSSOURST REPORT OF. WATER SITUL-OFF BEFARING WELL PUT ATERING CASING ABANDONY SHOOTING OR ACIDIZE ABANDONNENT PRACTURE TREAT MALTIPLE COMPLETE FRACTURE TREAT MALTIPLE COMPLETE FRACTURE TREAT MALTIPLE COMPLETE FRACTURE TREAT TO AREA (STEED) SHOOTING OR ACIDIZEDS ABANDONNENT SHOOTING OR ACIDIZEDS NOTICE OF RECENTIVE OPERATIONS. (Charly size all perminent details, and one pompletion of Recompletion or Recompletion Report and Loc form.) 7 DESCRIBE PROPOSED OR COMPLETE DOPERATIONS. (Charly size all perminent details, and one pompletion of Recompletion or Recompletion Report and Loc form.) ON February 2.5, 2000 Inland Production Company conducted a Step-Rate Test (SRT) on the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is requesting approvise of the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is requesting approvise of the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is requesting approvise of the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is requesting approvise of the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is requesting approvise of the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is requesting the Jonah Unit. Due to the results			7. UNIT AGREEMENT NAME	
INLAND PRODUCTION COMPANY ADDRESS OF OPERATION ROUTE #3 BOX 3630, MYTON, UTAH 84052 (435) 646-3721 LOCATION OF WELL ROOP DECident clearly and in secondance with any State requirements.* See also grace #17 Electron Decident clearly and in secondance with any State requirements.* See also grace #17 Electron Decident clearly and in secondance with any State requirements.* See also grace #17 Electron Decident clearly and in secondance with any State requirements.* See also grace #17 Electron Decident clearly and in secondance with any State requirements.* See also grace #18 Electron Decident Clearly state in a property of the PILL OR AILER CASING INSTITUTE TO THE NUMBER #3-013-31361 SEE ELEVATIONS (Show whether DF, RT, GR, etc.) TEST WATER SHUT-OFF			JONA	Н
ROUTE 43 BOX 3630, MYTON, UTAH 84052 (435) 646-3721 LOCATION OF WELL (Report leading clearly and in accordance with any State requirements.* See also appace 17 below.) Attentice NW/SE 1832 FSL 1829 FEL 11. SEC., T. R. M. OR BLK. AND SURVEY CRA. AND S	2. NAME OF OPERATOR INLAND PRODUCTION COMPANY			NT 33-6
AT EACTURE TREAT NOTICE NOW NOTICE OF INTENTION NOTICE OF			3	33-6
NW/SE 1832 FSL 1829 FEL U. SEC. T.R. M. OR RIK AND SURVEYOR AREA NW/SE Section 6, T09S R17E 4 API NUMBER 43-013-31361 15. ELEVATIONS (Show whether DF. RT. GR. etc.) 5268 GR DUCHESNE UT 6. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data NOTICE OF INTEXTION TO: SUBSEQUENT REPORT OF: WATER SHUT-OFF REPAIRING WELL FRACTURE TREAT MULTIPLE COMPLETE FRACTURE TREAT MULTIPLE COMPLETE FRACTURE TREAT MULTIPLE COMPLETE FRACTURE TREAT (OTHER) SHOOTING OR ACIDIZEN (Note: Report results of multiple completion on Well Completion or Recompletion Report and Loc form.) 7 DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly suse all pertnent details, and circy-primer dates, including estimated date of sarring any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical or his work.) On February 25, 2000 Inland Production Company conducted a Step-Rate Test (SRT) on the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is 'requesting approvate of the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is 'requesting approvate of the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is 'requesting approvate of the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is 'requesting approvate of the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is 'requesting approvate Maximum Allowable Injection Utah Division of Oil, Gas and Mining Date: JUAN DATE OF Federal or State office use		uirements.*	10. FIELD AND POOL, OR WILDCAT	
A API NUMBER 43-013-31361 15. ELEVATIONS (Show whether DF, RT, GR, etc.) 12. COUNTY OR PARISH 19. STATE UT	At sarface		MONUMENT	BUTTE
43-013-31361 5268 GR DUCHESNE UT 6. Check Appropriate Box To Indicate Nature of Notice. Report, or Other Data NOTICE OF INTENTION TO: SUBSEQUENT REPORT OF: WATER SHUT-OFF PULL OR ALTER CASING PRACTURE TREAT MULTIPLE COMPLETE FRACTURE TREATMENT ALTERING CASING SHOOTING OR ACIDIZENG ABANDON' SHOOTING OR ACIDIZENG ABANDONMENT OTHER (OTHER) (Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.) 7 DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all perment details, and un-op-rument dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical d-ophs for all markers and zones perment to this work.)* On February 25, 2000 Inland Production Company conducted a Step-Rate Test (SRT) on the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is requesting appropriate of high symmethy Maximum Allowable Injection Pressure from 2200 psi to 2165 psi on this well. Utah Division of Oil, Gas and Mining Date: 3 1 100 COPY SENT TO CHESTOR Operations Manager Date 2/28/00 (This space for Federal or State office use)			SURVEY OR AREA	, T09S R17E
NOTICE OF INTENTION TO: SUBSEQUENT REPORT OF: WATER SHUT-OFF REPAIRING WELL PRACTURE TREATMENT ALTERNG CASING SHOOT OR ACIDIZE ABANDON* SHOOT OR ACIDIZE ABANDON* SHOOTING OR ACIDIZING ABANDONMENT* (OTHER) Step-Rate test X Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.) 7 DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all pertinent details, and the pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical displies for all markers and zones pertinent to this work.)* On February 25, 2000 Inland Production Company conducted a Step-Rate Test (SRT) on the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is requesting approvaled the proposed was maximum. Allowable Injection Pressure from 2200 psi to 2165 psi on this well. Utah Division of Oil, Gas and Mining Date: 3 Utah Division of Oil, Gas and Mining Date: 3 Onte: 3 Onte: 3 Title Operations Manager Date 2/28/00 (This space for Federal or State office use)		GR, etc.)		ŀ
PULL OR ALTER CASING WATER SHUT-OFF REPAIRING WELL FRACTURE TREAT MULTIPLE COMPLETE FRACTURE TREATMENT ALTERING CASING SHOOT OR ACIDIZE ABANDON* SHOOT OR ACIDIZE ABANDON* SHOOTING OR ACIDIZING ABANDONMENT* (OTHER) Step-Rate test X (OTHER) (Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.) 7 DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all perminent details, and the pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical d-pths for all markers and zones pertinent to this work.)* On February 25, 2000 Inland Production Company conducted a Step-Rate Test (SRT) on the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is requesting approvate the proposed Maximum Allowable Injection Pressure from 2200 psi to 2165 psi on this well. Utah Division of Oil, Gas and Mining Date: 3 Local Inlands: CHU. By: On Federal or State office use)	16. Check Appropriate Box To Indicate Nature of No	tice. Report, or Other Data		
SHOOT OR ACIDIZE ABANDON* SHOOTING OR ACIDIZING ABANDONMENT* (OTHER) Step-Rate test (OTHER) Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.) 7 DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all pertinent details, and the pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical disprise for all markers and zones pertinent to this work.)* On February 25, 2000 Inland Production Company conducted a Step-Rate Test (SRT) on the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is requesting approving charge true. On February 25, 2000 psi to 2165 psi on this well. Utah Division of Oil, Gas and Mining Date: 3 1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	NOTICE OF INTENTION TO:	SUBSEQ	UENT REPORT OF:	
SHOOT OR ACIDIZE ABANDON* SHOOTING OR ACIDIZING ABANDONMENT* (OTHER) (Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.) 7 DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all pertinent details, and use pertinent date, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)* On February 25, 2000 Inland Production Company conducted a Step-Rate Test (SRT) on the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is requesting approving this proposed warmum Allowable Injection Pressure from 2200 psi to 2165 psi on this well. Utah Division of Oil, Gas and Mining Date: 3 1600 D	TEST WATER SHILT-OFF PULL OR ALTER CASING	WATER SHUT-OFF	REPAIRING WELL	
(OTHER) (Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.) 7 DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all pertinent details, and are pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical dupths for all markers and zones pertinent to this work.)* On February 25, 2000 Inland Production Company conducted a Step-Rate Test (SRT) on the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is requesting appropriate the proposed Maximum Allowable Injection Pressure from 2200 psi to 2165 psi on this well. Utah Division of Oil, Gas and Mining Date: 3 100 points of the Step Patter of	FRACTURE TREAT MULTIPLE COMPLETE	FRACTURE TREATMENT	ALTERING CASING	
On February 25, 2000 Inland Production Company conducted a Step-Rate Test (SRT) on the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is requesting approvise the strain and Division of Oil, Gas and Mining Date: 3-6-00 Initions. The Operation Manager Date 2/28/00 8 I bereby certify that the foregoing is true and correct Stoned. TITLE Operations Manager DATE 2/28/00 (This space for Federal or State office use)	SHOOT OR ACIDIZE ABANDON*	SHOOTING OR ACIDIZING	ABANDONMENT*	
Completion or Recompletion Report and Log form.) 7 DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all pertinent details, and awe pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)* On February 25, 2000 Inland Production Company conducted a Step-Rate Test (SRT) on the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is requesting approvised hardward Maximum Allowable Injection Pressure from 2200 psi to 2165 psi on this well. Utah Division of Oil, Gas and Mining Date: 3 16-60 By: Ones: 3 16-60 By: Operations Manager DATE 2/28/00 (This space for Federal or State office use)	REPAIR WELL	(OTHER) Step-Rate ter	st	X
On February 25, 2000 Inland Production Company conducted a Step-Rate Test (SRT) on the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is requesting approving high system. Utah Division of Oil, Gas and Mining Date: Ones San to Care Interest of Federal or State office use) Title Operations Manager Date 2/28/00 (This space for Federal or State office use)	(OTHER)	(Note: Report resul	its of multiple completion on Well	
On February 25, 2000 Inland Production Company conducted a Step-Rate Test (SRT) on the Jonah #33-6 injection well in the Jonah Unit. Due to the results of the attached SRT Inland is requesting provide the production of Pressure from 2200 psi to 2165 psi on this well. Utah Division of Oil, Gas and Mining COPY SENT TO CHERCE Date: SIGNED TITLE Operations Manager DATE 2/28/00 (This space for Federal or State office use)				
Jonah Unit. Due to the results of the attached SRT Inland is requesting provided honge the Maximum Allowable Injection Pressure from 2200 psi to 2165 psi on this well. Utah Division of Oil, Gas and Mining Date: Jinition: By: Operations Manager DATE 2/28/00 (This space for Federal or State office use)	•	•		
SIGNED TITLE Operations Manager DATE 2/28/00 (This space for Federal or State office use)	Jonah Unit. Due to the results of the attached SRT Inland is Pressure from 2200 psi to 2165 psi on this well. COPY SENT TO COPY SENT T	requesting approving the Utah Division Oil, Gas and Date: 314,00	ந்தை இதிக்கில்	
	18 I hereby certify that the foregoing is true and correct SIGNED TITLE	Operations Manager	DATE	2/28/00
ADDROVED BY TITLE DATE	•			

CONDITIONS OF APPROVAL, IF ANY:



Jonah 33-6 Step Rate Test February 25, 2000



ISIP: 2230 psi

Fracture pressure: 2165 psi

FG: 0.900

Step	Rate(bpd)	Pressure(psi)
1	50	1795
2	100	1815
3	150	1855
4	200	1905
5	250	1950
6	300	2005
7	350	2055
8	400	2105
9	450	2150
10	500	2190
11	550	2220
12	600	2255

INJECTION WELL - PRESSURE TEST

Well Name Bolchon MONTED	733-6 API Numb	er <u>43-013-31361</u>
Otr/Otr: NW/SE Sect	ion: 6 Township:	Range 17E
	1. 00000001011	2000
		!
Lease: State	FeeFedera	Indian
Inspector / / /	In war Date [7/05/01
7		
nitial Conditions:		
Tubing - Rate:	Press	sure psi
Casing/Tubing Annulus - Pre	essure $\frac{\sqrt{\delta}}{\sqrt{\delta}}$ psi	
Conditions During Test:		
Time (Minutes)	Annulus Pressure	Tubing Pressure
0	1050	725
5	_/050	725
10	1050	
15	_/050	725
20	1050	725
25		725
30	1050	725
Results: Pass/Fail		
Conditions After Test:		
Tubing Pressure:) S psi	
Casing/Tubing Annulus	Pressure 1030 p	SI (
COMMENTS Istul because	a of newly Perfed in yes	from loner. 1 of Injen
Duch test Tim	file 11:00 Am +	Sword on Chif
733		
	/	
Hon Mark		
Operator Representative		

STATE OF UTAH

DEPARTM	MENT OF NATURAL RESOURCES			
DIVISIO	N OF OIL, GAS, AND MINING		5. LEASE DESIGNATION AND SERIAL U-020252-A	NO.
SUNDRY NO	TICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBAL N	AME
	sposals to drill or to deepen or plug back to a diffe	rent reservoir.	N/A	
OIL GAS]		7. UNIT AGREEMENT NAME	
WELL OTHER X	Injection		JONAH	
2. NAME OF OPERATOR INLAND PRODUC	CTION COMPANY		8. FARM OR LEASE NAME MONUMENT 33-6-9	-17
3. Address of Operator Rt. 3 Box 3630, My 435-646-3721	yton Utah 84052		9. WELL NO. MONUMENT 33-6-9	-17
LOCATION OF WELL (Report local See also space 17 below.)	tion clearly and in accordance with any State requ	irements.*	10. FIELD AND POOL, OR WILDCAT	
At surface NW/SE Section (6 T00S P17F		MONUMENT BUTT	E
1832 FSL 1829 F			III. SEC., T., R., M., OR BLK, AND SURVEY OR AREA NW/SE Section 6, T0	9S R17E
14 API NUMBER 43-013-31361	15. ELEVATIONS (Show whether DF, RT, GF 5268 GR	R, etc.)	12. COUNTY OR PARISH DUCHESNE	13. STATE UT
•	l propriate Box To Indicate Nature of No	1		1
NOTICE OF INTEN	TION TO:	SUBSEQ	UENT REPORT OF:	
TEST WATER SHUT-OFF PUL	L OR ALTER CASING	WATER SHUT-OFF	REPAIRING WELL	
FRACTURE TREAT MU	LTIPLE COMPLETE	FRACTURE TREATMENT	ALTERING CASING	
SHOOT OR ACIDIZE ABA	ANDON*	SHOOTING OR ACIDIZING	ABANDONMENT*	
REPAIR WELL		(OTHER)	X Recompletion	
(OTHER)		•	ults of multiple completion on Well completion Report and Log form.)	
	LETED OPERATIONS. (Clearly state all pertine ally drilled, give subsurface locations and measure			
• •	well was recompleted in the			er interval
	B-6 4164' 4188 ' w/ 4 jspf fo			V. 111101 · U.
	n Wisner w/ EPA was contac			
	is Ingram w/ State DOGM w			
	ssure loss charted in the 1/2		ram was there to witnes	s the test.
The Well is shut in an	d waiting on permission to in	iject.		
18 I hereby certify that the foregoing is t	true and correct			
SIGNED Krisha Russell	ussel TITLE	Production Clerk	DATE	7/6/01
cc: BLM		Approved by the	3	
(This space for Federal or State office use		Utah Division of		- A.M
APPROVED BY	TITLE C	il, Gas and Mini	ng DATE	
CONDITIONS OF APPROVAL. IF ANY	Date:	07-30-011	1111	
17-21	. 7	ZIMAIK	VV	

* See Instructions On Reverse Side

Mechanical Integrity Test

U.S. Environmental Protection Agency
Underground Injection Control Program, UIC Direct Implementation Program 8P.W-GW
999 18th Street, Suite 500 Denver, CO 80202-2466


EPA Witness: None			D	، د میر	
Test conducted by: Ron Shuc	K		Date: $\frac{7}{1}$	5101	
Others present: Mr. Densis	ENgram	1//	A)		
	1	- Hanne	May		
Well Name: Monument Federal	33-6-9-1	7 -	ATT CIVE		
Field: Jona & # 117	7027 21		ER SWD	Status: AC	
Location: NW/SE Sec: 6 T Operator: INland Product	9 N/S	0072 D /7/2011	. C	,	
Operator: INland Product	lion	RW	County: Duc.	Arswe_Stat	e: <u>U</u> T
Last MIT:/ /	Maximum	Allowable Pre			
		Mowable Fic	35u1c		PSIG
Is this a regularly scheduled test?	[] Yes	[X] No			
Initial test for permit?	. ,	[·X] No			
Test after well rework?		[] No			
Well injecting during test?	[] Yes	[X] No	If Yes, rate: _		bpd
Pre-test casing/tubing annulus pressure		10	psig		

MIT DATA TABLE	Test #1		
TUBING	PRESSURE	Test #2	Test #3
Initial Pressure			
Fnd of test pressure	750 psig 750 psig	psig	psig
C4SING / TUBING	ANNULUS	PRESSURE psig	nsig '
//:07 0 minutes	1050 psig	psig	
5 minutes	1050 psig	psig	psig i
10 minutes	1050 psig	psig	psig
15 minutes	1050 osia	psig	psig -
20 minutes	1050 psig	psig	psig
25 minutes	1050 psig	psig	psig
//:3 7 30 minutes	1050 psig	psig	psig
minutes	psig	psig	psig
minutes RESULT	nein nein	nsig	psig
TODODI.	Pass Fail	[] Pass []Fail	Pass Fail

Does the annulus pressure build back up and

Lieunanical Integrity Test

in Inland Production Had This wellow Injection and wanted to Add some perferations. The tast was after The Rig work. The well is shutin waiting on approval to start Injecting again.	• ·.
The Rig work. The well is shuting waiting on approval	•
to Start Injecting again.	•
	-
	-
	-
	-
	-
	-
	-
	•
	•
	•
	•
	•
	•
	•
OFFICE USE ONLY - COMPLIANCE FOLLOWUP Staff Date	
Do you agree that the well pagged/Faired the beats file for	
TAMBLEL OF OMIGIBIED: YES I MA OTT	No.
The state of the s	No.
Possible violation identified? [] Yes [] No If YES - Followup initiated? [] Yes []	
[]	No
[] Data Entry [] Compliance Staff [] 2nd Data Entry [] Hard Copy]	



Corporations Section P.O.Box 13697 Austin, Texas 78711-3697





Office of the Secretary of State

The undersigned, as Secretary of State of Texas, does hereby certify that the attached is a true and correct copy of each document on file in this office as described below:

Newfield Production Company Filing Number: 41530400

Articles of Amendment

September 02, 2004

In testimony whereof, I have hereunto signed my name officially and caused to be impressed hereon the Seal of State at my office in Austin, Texas on September 10, 2004.





Secretary of State

ARTICLES OF AMENDMENT TO THE ARTICLES OF INCORPORATION OF INLAND PRODUCTION COMPANY

In the Office of the Secretary of State of Texas

SEP 02 2004

Corporations Section

Pursuant to the provisions of Article 4.04 of the Texas Business Corporation Act (the "TBCA"), the undersigned corporation adopts the following articles of amendment to the articles of incorporation:

ARTICLE 1 - Name

The name of the corporation is Inland Production Company.

ARTICLE 2 - Amended Name

The following amendment to the Articles of Incorporation was approved by the Board of Directors and adopted by the shareholders of the corporation on August 27, 2004.

The amendment alters or changes Article One of the Articles of Incorporation to change the name of the corporation so that, as amended, Article One shall read in its entirety as follows:

"ARTICLE ONE - The name of the corporation is Newfield Production Company."

ARTICLE 3 - Effective Date of Filing

This document will become effective upon filing.

The holder of all of the shares outstanding and entitled to vote on said amendment has signed a consent in writing pursuant to Article 9.10 of the TBCA, adopting said amendment, and any written notice required has been given.

IN WITNESS WHEREOF, the undersigned corporation has executed these Articles of Amendment as of the 1st day of September, 2004.

INLAND RESOURCES INC.

By: Susan G. Riggs, Treasurer

071572A 16535 62848 73089 76787 065914 16539 63073B 73520A 76808 16544 63073D 74805 76954 63073X 17424 63073O 74806 76956 63098A 18048 64917 74807 77233 68528A UTU- 18399 64379 74808 77234 72086A 19267 64380 74389 77235 72613A 02458 26026A 64381 74390 77337 73520X 03563 30096 64805 74391 77338 74477X 03563A 30103 64806 74392 77339 75023X 04493 31260 64917 74393 77357 76188X 05843 33992 65207 74398 77359 76331X 07978 34173 65210 74399 77365 76788X 09803 34346 65635 74400 77369 <th>TIMOT</th> <th>15055</th> <th>(1050</th> <th>#2000</th> <th></th> <th></th>	TIMOT	15055	(1050	#2000		
065914 16539 63073B 73520A 76808 16544 63073D 74108 76813 17036 63073E 74805 76954 63073X 17424 63073O 74806 76956 63098A 18048 64917 74807 77233 68528A UTU- 18399 64379 74808 77234 72086A 19267 64380 74389 77235 72613A 02458 26026A 64381 74390 77337 73520X 03563A 30096 64805 74391 77338 74477X 03563A 30103 64806 74391 77337 73520X 04493 31260 64917 74393 77357 76189X 05843 33992 65207 74398 77359 7631X 07978 34173 65210 74399 77365 76788X 09803 34346 65635 74400 77370 77107X <td>UTSL-</td> <td>15855</td> <td>61052</td> <td>73088</td> <td>76561</td> <td></td>	UTSL-	15855	61052	73088	76561	
16544 63073D						
17036	065914					
17424	·					
18048						
UTU- 18399 64379 74808 77234 72086A 19267 64380 74389 77235 72613A 02458 26026A 64381 74389 77337 73520X 03563 30096 64805 74391 77338 74477X 03563A 30103 64806 74392 77339 75023X 04493 31260 64917 74393 77357 76189X 05843 33992 65207 74398 77359 76331X 09803 34346 65635 74400 77369 77098X 017439B 36442 65967 74404 77370 77107X 017985 36846 65969 74405 77546 77236X 017991 38411 65970 74406 77553 7376X 017992 38428 66184 74411 77554 78560X 018073 38429 66185 74805 78022 79485X <tr< td=""><td></td><td></td><td></td><td></td><td></td><td></td></tr<>						
19267					77233	68528A
02458 26026A 64381 74390 77337 73520X 03563 30096 64805 74391 77338 74477X 03563A 30103 64806 74392 77339 75023X 04493 31260 64917 74393 77357 76189X 05843 33992 65207 74398 77359 76331X 07978 34173 65210 74399 77365 76788X 09803 34346 65635 74400 77369 77098X 017439B 36442 65967 74404 77370 77107X 017991 38411 65970 74406 77553 77376X 017992 38428 66184 74411 77554 78560X 018073 38429 66185 74805 78022 79485X 019222 38431 66191 74806 79013 79641X 020252 39713 67168 74826 79014 802	UTU-			74808	77234	72086A
03563 30096 64805 74391 77338 74477X 03563A 30103 64806 74392 77339 75023X 04493 31260 64917 74393 77357 76189X 05843 33992 65207 74398 77359 76331X 07978 34173 65210 74399 77365 76788X 09803 34346 65635 74400 77369 77098X 017439B 36442 65967 74404 77370 77107X 017985 36846 65969 74405 77546 77236X 017991 38411 65970 74406 77553 77376X 017992 38428 66184 74411 77554 78560X 018073 38429 66185 74805 78022 79485X 019222 38431 66191 74806 79013 7861X 020252A 39714 67170 74827 79015 813				74389	77235	
03563A 30103 64806 74392 77339 75023X 04493 31260 64917 74393 77357 76189X 05843 33992 65207 74398 77359 76331X 07978 34173 65210 74399 77365 76788X 09803 34346 65635 74400 77369 77098X 017439B 36442 65967 74404 77370 77107X 017985 36846 65969 74405 77546 77236X 017991 38411 65970 74406 77553 77376X 017992 38428 66184 74411 77554 78560X 018073 38429 66185 74805 78022 79485X 019222 38431 66191 74806 79013 79641X 020252 39713 67168 74826 79014 80207X 020254 40026 67208 74835 79016				74390	77337	73520X
04493 31260 64917 74393 77357 76189X 05843 33992 65207 74398 77359 76331X 07978 34173 65210 74399 77365 76788X 09803 34346 65635 74400 77369 77098X 017439B 36442 65967 74404 77370 77107X 017985 36846 65969 74405 77546 77236X 017991 38411 65970 74406 77553 77376X 017992 38428 66184 74411 77554 78560X 018073 38429 66185 74805 78022 79485X 019222 38431 66191 74806 79013 79641X 020252 39713 67168 74826 79014 80207X 020254 40026 67208 74835 79016 020254 40026 67549 74868 79017 020309D					77338	74477X
05843 33992 65207 74398 77359 76331X 07978 34173 65210 74399 77365 76788X 09803 34346 65635 74400 77369 77098X 017439B 36442 65967 74404 77370 77107X 017985 36846 65969 74405 77546 77236X 017991 38411 65970 74406 77553 77376X 017992 38428 66184 74411 77554 78560X 018073 38429 66185 74805 78022 79485X 019222 38431 66191 74806 79013 79641X 020252 39713 67168 74826 79014 80207X 020252A 39714 67170 74827 79015 81307X 020254 40026 67208 74835 79016 020255 40652 67549 74868 79017 02268				74392	77339	75023X
07978 34173 65210 74399 77365 76788X 09803 34346 65635 74400 77369 77098X 017439B 36442 65967 74404 77370 77107X 017985 36846 65969 74405 77546 77236X 017991 38411 65970 74406 77553 77376X 017992 38428 66184 74411 77554 78560X 018073 38429 66185 74805 78022 79485X 019222 38431 66191 74806 79013 79641X 020252 39713 67168 74826 79014 80207X 020252A 39714 67170 74827 79015 81307X 020254 40026 67208 74835 79016 020255 40652 67549 74868 79017 020309D 40894 67586 74869 79831 022684A 41		31260	64917	74393	77357 [.]	76189X
09803 34346 65635 74400 77369 77098X 017439B 36442 65967 74404 77370 77107X 017985 36846 65969 74405 77546 77236X 017991 38411 65970 74406 77553 77376X 017992 38428 66184 74411 77554 78560X 018073 38429 66185 74805 78022 79485X 019222 38431 66191 74806 79013 79641X 020252 39713 67168 74826 79014 80207X 020252A 39714 67170 74827 79015 81307X 020254 40026 67208 74835 79016 79017 79020309D 40894 67586 74868 79017 79831 79641X 79832 79833 79016 79831 79832 79833 79834 79832 79833 79917 79833 79834 79833			65207	74398	77359	76331X
017439B 36442 65967 74404 77370 77107X 017985 36846 65969 74405 77546 77236X 017991 38411 65970 74406 77553 77376X 017992 38428 66184 74411 77554 78560X 018073 38429 66185 74805 78022 79485X 019222 38431 66191 74806 79013 79641X 020252 39713 67168 74826 79014 80207X 020252A 39714 67170 74827 79015 81307X 020254 40026 67208 74835 79016 020255 40652 67549 74868 79017 020309D 40894 67586 74869 79831 022684A 41377 67845 74870 79832 027345 44210 68105 74872 79833 034217A 44426 68548 74970 79831 035521A 45431 69060 75037 <t< td=""><td></td><td>34173</td><td>65210</td><td>74399</td><td>77365</td><td>76788X</td></t<>		34173	65210	74399	77365	76788X
017985 36846 65969 74405 77546 77236X 017991 38411 65970 74406 77553 77376X 017992 38428 66184 74411 77554 78560X 018073 38429 66185 74805 78022 79485X 019222 38431 66191 74806 79013 79641X 020252 39713 67168 74826 79014 80207X 020252A 39714 67170 74827 79015 81307X 020254 40026 67208 74835 79016 020255 40652 67549 74868 79017 020309D 40894 67586 74869 79831 022684A 41377 67845 74870 79832 027345 44210 68105 74872 79833 034217A 44426 68548 74970 79831 035521A 45431 69060 75037 80450 038797 47171 69061 75038 80915	09803	34346	65635	74400	77369	77098X
017991 38411 65970 74406 77553 77376X 017992 38428 66184 74411 77554 78560X 018073 38429 66185 74805 78022 79485X 019222 38431 66191 74806 79013 79641X 020252 39713 67168 74826 79014 80207X 020252A 39714 67170 74827 79015 81307X 020254 40026 67208 74835 79016 020255 40652 67549 74868 79017 020309D 40894 67586 74869 79831 022684A 41377 67845 74870 79832 027345 44210 68105 74872 79833 034217A 44426 68548 74970 79831 035521A 45431 69060 75037 80450 038797 47171 69061 75038 80915 058149 49930 70821 75075 075174 49	017439B	36442	65967	74404	77370	77107X
017992 38428 66184 74411 77554 78560X 018073 38429 66185 74805 78022 79485X 019222 38431 66191 74806 79013 79641X 020252 39713 67168 74826 79014 80207X 020252A 39714 67170 74827 79015 81307X 020254 40026 67208 74835 79016 020255 40652 67549 74868 79017 020309D 40894 67586 74869 79831 022684A 41377 67845 74870 79832 027345 44210 68105 74872 79833 034217A 44426 68548 74970 79831 035521 44430 68618 75036 79834 03579A 47171 69061 75038 80915 058149 49092 69744 75039 81000 063597A 49430 70821 75078 096547 50376 721	017985	36846	65969	74405	77546	77236X
018073 38429 66185 74805 78022 79485X 019222 38431 66191 74806 79013 79641X 020252 39713 67168 74826 79014 80207X 020252A 39714 67170 74827 79015 81307X 020254 40026 67208 74835 79016 020255 40652 67549 74868 79017 020309D 40894 67586 74869 79831 022684A 41377 67845 74870 79832 027345 44210 68105 74872 79833 034217A 44426 68548 74970 79831 035521A 45431 69060 75037 80450 038797 47171 69061 75038 80915 058149 49902 69744 75039 81000 063597A 49430 70821 75075 096547 50376 72104 75089 096550 50385 72105 75090	017991	38411	65970	74406	77553·	77376X
019222 38431 66191 74806 79013 79641X 020252 39713 67168 74826 79014 80207X 020252A 39714 67170 74827 79015 81307X 020254 40026 67208 74835 79016 020255 40652 67549 74868 79017 020309D 40894 67586 74869 79831 022684A 41377 67845 74870 79832 027345 44210 68105 74872 79833 034217A 44426 68548 74970 79831 035521 44430 68618 75036 79834 035521A 45431 69060 75037 80450 038797 47171 69061 75038 80915 058149 49430 70821 75075 075174 49950 72103 75078 096547 50376 72104 75089 096550 50385 72105 75090 50750 72107 </td <td>017992</td> <td>38428</td> <td>66184</td> <td>74411</td> <td>77554</td> <td>78560X</td>	017992	38428	66184	74411	77554	78560X
020252 39713 67168 74826 79014 80207X 020252A 39714 67170 74827 79015 81307X 020254 40026 67208 74835 79016 020255 40652 67549 74868 79017 020309D 40894 67586 74869 79831 022684A 41377 67845 74870 79832 027345 44210 68105 74872 79833 034217A 44426 68548 74970 79831 035521 44430 68618 75036 79834 035521A 45431 69060 75037 80450 038797 47171 69061 75038 80915 058149 49092 69744 75039 81000 063597A 49430 70821 75075 075174 49950 72103 75078 096547 50376 72104 75089 096550 50385 72105 75090 50750 72107 75238 </td <td>018073</td> <td>38429</td> <td>66185</td> <td>74805</td> <td>78022</td> <td>79485X</td>	018073	38429	66185	74805	78022	79485X
020252A 39714 67170 74827 79015 81307X 020254 40026 67208 74835 79016 020255 40652 67549 74868 79017 020309D 40894 67586 74869 79831 022684A 41377 67845 74870 79832 027345 44210 68105 74872 79833 034217A 44426 68548 74970 79831 035521 44430 68618 75036 79834 035521A 45431 69060 75037 80450 038797 47171 69061 75038 80915 058149 49092 69744 75039 81000 063597A 49430 70821 75075 075174 49950 72103 75078 096547 50376 72104 75089 096550 50385 72105 75090 50376 72106 75234 50750 72107 75238 10760 51081	019222	38431	66191	74806	79013 ⁻	79641X
020254 40026 67208 74835 79016 020255 40652 67549 74868 79017 020309D 40894 67586 74869 79831 022684A 41377 67845 74870 79832 027345 44210 68105 74872 79833 034217A 44426 68548 74970 79831 035521 44430 68618 75036 79834 035521A 45431 69060 75037 80450 038797 47171 69061 75038 80915 058149 49092 69744 75039 81000 063597A 49430 70821 75075 075174 49950 72103 75078 096547 50376 72104 75089 096550 50385 72105 75090 50376 72106 75234 50750 72107 75238 10760 51081 72108 76239 11385 52013 73086 76240	020252	39713	67168	74826	79014	80207X
020255 40652 67549 74868 79017 020309D 40894 67586 74869 79831 022684A 41377 67845 74870 79832 027345 44210 68105 74872 79833 034217A 44426 68548 74970 79831 035521 44430 68618 75036 79834 035521A 45431 69060 75037 80450 038797 47171 69061 75038 80915 058149 49092 69744 75039 81000 063597A 49430 70821 75075 075174 49950 72103 75078 096547 50376 72104 75089 096550 50385 72105 75090 50376 72106 75234 50750 72107 75238 10760 51081 72108 76239 11385 52013 73086 76240	020252A	39714	67170	74827	79015	81307X
020309D 40894 67586 74869 79831 022684A 41377 67845 74870 79832 027345 44210 68105 74872 79833 034217A 44426 68548 74970 79831 035521 44430 68618 75036 79834 035521A 45431 69060 75037 80450 038797 47171 69061 75038 80915 058149 49092 69744 75039 81000 063597A 49430 70821 75075 075174 49950 72103 75078 096547 50376 72104 75089 096550 50385 72105 75090 50376 72106 75234 50750 72107 75238 10760 51081 72108 76239 11385 52013 73086 76240	020254	40026	67208	74835	79016	
022684A 41377 67845 74870 79832 027345 44210 68105 74872 79833 034217A 44426 68548 74970 79831 035521 44430 68618 75036 79834 035521A 45431 69060 75037 80450 038797 47171 69061 75038 80915 058149 49092 69744 75039 81000 063597A 49430 70821 75075 075174 49950 72103 75078 096547 50376 72104 75089 096550 50385 72105 75090 50376 72106 75234 50750 72107 75238 10760 51081 72108 76239 11385 52013 73086 76240	020255	40652	67549	74868	79017	
027345 44210 68105 74872 79833 034217A 44426 68548 74970 79831 035521 44430 68618 75036 79834 035521A 45431 69060 75037 80450 038797 47171 69061 75038 80915 058149 49092 69744 75039 81000 063597A 49430 70821 75075 075174 49950 72103 75078 096547 50376 72104 75089 096550 50385 72105 75090 50376 72106 75234 50750 72107 75238 10760 51081 72108 76239 11385 52013 73086 76240	020309D	40894	67586	74869	79831	
034217A 44426 68548 74970 79831 035521 44430 68618 75036 79834 035521A 45431 69060 75037 80450 038797 47171 69061 75038 80915 058149 49092 69744 75039 81000 063597A 49430 70821 75075 075174 49950 72103 75078 096547 50376 72104 75089 096550 50385 72105 75090 50376 72106 75234 50750 72107 75238 10760 51081 72108 76239 11385 52013 73086 76240	022684A	41377	67845	74870	79832	
035521 44430 68618 75036 79834 035521A 45431 69060 75037 80450 038797 47171 69061 75038 80915 058149 49092 69744 75039 81000 063597A 49430 70821 75075 075174 49950 72103 75078 096547 50376 72104 75089 096550 50385 72105 75090 50376 72106 75234 50750 72107 75238 10760 51081 72108 76239 11385 52013 73086 76240	027345	44210	68105	74872	79833 [,]	
035521A 45431 69060 75037 80450 038797 47171 69061 75038 80915 058149 49092 69744 75039 81000 063597A 49430 70821 75075 075174 49950 72103 75078 096547 50376 72104 75089 096550 50385 72105 75090 50376 72106 75234 50750 72107 75238 10760 51081 72108 76239 11385 52013 73086 76240	034217A	44426	68548	74970	79831	
038797 47171 69061 75038 80915 058149 49092 69744 75039 81000 063597A 49430 70821 75075 075174 49950 72103 75078 096547 50376 72104 75089 096550 50385 72105 75090 50376 72106 75234 50750 72107 75238 10760 51081 72108 76239 11385 52013 73086 76240	035521	44430	68618	75036	79834	
058149 49092 69744 75039 81000 063597A 49430 70821 75075 075174 49950 72103 75078 096547 50376 72104 75089 096550 50385 72105 75090 50376 72106 75234 50750 72107 75238 10760 51081 72108 76239 11385 52013 73086 76240	035521A	45431	69060	75037	80450	
063597A 49430 70821 75075 075174 49950 72103 75078 096547 50376 72104 75089 096550 50385 72105 75090 50376 72106 75234 50750 72107 75238 10760 51081 72108 76239 11385 52013 73086 76240	038797	47171	69061	75038	80915	
075174 49950 72103 75078 096547 50376 72104 75089 096550 50385 72105 75090 50376 72106 75234 50750 72107 75238 10760 51081 72108 76239 11385 52013 73086 76240	058149	49092	69744	75039	81000	
096547 50376 72104 75089 096550 50385 72105 75090 50376 72106 75234 50750 72107 75238 10760 51081 72108 76239 11385 52013 73086 76240	063597A	49430	70821	75075		
096550 50385 72105 75090 50376 72106 75234 50750 72107 75238 10760 51081 72108 76239 11385 52013 73086 76240	075174	49950	72103	75078		
50376 72106 75234 50750 72107 75238 10760 51081 72108 76239 11385 52013 73086 76240	096547	50376	72104	75089		
50750 72107 75238 10760 51081 72108 76239 11385 52013 73086 76240	096550	50385	72105	75090		
10760 51081 72108 76239 11385 52013 73086 76240		50376	72106	75234		
10760 51081 72108 76239 11385 52013 73086 76240		50750	72107	75238		
11385 52013 73086 76240	10760	51081		76239		
·	11385					
13703 34010 /300/ /0441	13905	52018	73087	76241		
15392 58546 73807 76560						



United States Department of the Interior



BUREAU OF LAND MANAGEMENT Utah State Office P.O. Box 45155 Salt Lake City, UT 84145-0155 http://www.blm.gov

IN REPLY REFER TO: 3106 (UT-924)

September 16, 2004

Memorandum

To:

Vernal Field Office

From:

Acting Chief, Branch of Fluid Minerals

Subject:

Merger Approval

Attached is an approved copy of the name change recognized by the Utah State Office. We have updated our records to reflect the merger from Inland Production Company into Newfield Production Company on September 2, 2004.

Milas Lloathans

Michael Coulthard Acting Chief, Branch of Fluid Minerals

Enclosure

1. State of Texas Certificate of Registration

cc:

MMS, Reference Data Branch, James Sykes, PO Box 25165, Denver CO 80225 State of Utah, DOGM, Attn: Earlene Russell, PO Box 145801, SLC UT 84114

Teresa Thompson Joe Incardine Connie Seare

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING

UIC FORM 5

	d Number	UTHORITY TO	
See Attach	 		API Number
Footage :		County:	Floid or Unit Name See Attached List
QQ, Section	ı, Township, Range:	State: UTAH	Lease Designation and Number
FFECTIVE	DATE OF TRANSFER: 9/1/2004		
URRENT O	PERATOR		
Company:	Inland Production Company	Name;	Brian Harris
Address:	1401 17th Street Suite 1000	Signature:	Bono Jan
	city Denver state Co zip 80202	Title:	Engineering Tech.
Phone:	(303) 893-0102	Date:	9/15/2004
Comments:		Date.	371072004
Company:	Newfield Production Company	Name;	Brian Harris
Company: Address:	Newfield Production Company 1401 17th Street Suite 1000	Name; Signature:	Brian Harris The Hom
Company: Address:	Newfield Production Company	Signature:	K ~ //
Company: Address: Phone:	Newfield Production Company 1401 17th Street Suite 1000	Signature:	Ima from
Company: Address: Phone: Comments:	Newfield Production Company 1401 17th Street Suite 1000	Signature:	Tima Hom- Engineering Tech.
Company: Address: Phone:	Newfield Production Company 1401 17th Street Suite 1000 city Denver state Co zip 80202	Signature:	Tima Hom- Engineering Tech.
Company: Address: Phone: Comments: space for Sta	Newfield Production Company 1401 17th Street Suite 1000 city Denver state Co zip 80202 the use only) roved by: A Land	Signature: Title: Date: Approval Date	Engineering Tech. 9/15/2004
Company: Address: Phone: Comments: space for Sta	Newfield Production Company 1401 17th Street Suite 1000 city Denver state Co zip 80202	Signature: Title: Date: Approval Date	Engineering Tech. 9/15/2004

(5/2000)

RECEIVED SEP 2 0 2004

Division of Oil, Gas and Mining

OPERATOR CHANGE WORKSHEET

1. GLH

2. CDW 3. FILE

Change of Operator (Well Sold)

Designation of Agent/Operator

X Operator Name Change

Merger

The operator of the well(s) listed below	w has changed	, effect	ive:			9/1/2004		
FROM: (Old Operator): N5160-Inland Production Company Route 3 Box 3630 Myton, UT 84052		-		Myton,	ld Production Box 3630 UT 84052	on Company	,	
Phone: 1-(435) 646-3721				Phone: 1-(435)		ONAH (G	DEEN DE	(/ED)
	CA No.			Unit:		ONAH (G	REEN KI	VEK)
WELL(S) NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
MON FED 42-1J	01	090S	160E	4301331404	11492	Federal	WI	A
MON FED 43-11J	11	090S	160E	4301331002	11492	Federal	WI	A
WALTON FED 34-11	11	090S	160E	4301331003	11492	Federal	WI	A
MON FED 23-11J	11	090S	160E	4301331369	11492	Federal	WI	Α
MON FED 14-11J	11	090S	160E	4301331374	11492	Federal	WI	A
MON FED 32-11J	11	090S	160E	4301331386	11492	Federal	WI	A
MON FED 41-15	15	090S	160E	4301331367	11492	Federal	WI	A
MON FED 32-15J	15	090S	160E	4301331368	11492	Federal	WI	A
MON FED 23-15	15	090S	160E	4301331373	11492	Federal	WI	A
MON FED 13-5	05	090S	170E	4301331370	11492	Federal	WI	Α
MON FED 24-5	05	090S	170E	4301331375	11492	Federal	WI ·	A
MONUMENT FED 23-5J	05	090S	170E	4301331383	11492	Federal	ow	P
MON FED 22-5	05	090S	170E	4301331384	11492	Federal	WI	A
MONUMENT FED 14-5	05	090S	170E	4301331385	11492	Federal	OW	P
ALLEN FED 31-6	06	090S	170E	4301331195	11492	Federal	WI	Α
MONUMENT 33-6	06	090S	170E	4301331361	11492	Federal	WI	Α
MON FED 11-6	06	090S	170E	4301331362	11492	Federal	WI	A
MON FED 24-6	06	090S	170E	4301331363	11492	Federal	WI	A
MON FED 42-6	06	090S	170E	4301331364	11492	Federal	WI	Α
GETTY 7C	07_	090S	170E	4301330961	11492	Federal	OW	P

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

(R649-8-10) Sundry or legal documentation was received from the FORMER operator on: 9/15/2004
 (R649-8-10) Sundry or legal documentation was received from the NEW operator on: 9/15/2004

3. The new company was checked on the Department of Commerce, Division of Corporations Database on: 2/23/2005

4. Is the new operator registered in the State of Utah: YES Business Number: 755627-0143

5. If NO, the operator was contacted contacted on:

6a. (R649-9-2)Waste Management Plan has been received on:	IN PLACE		
6b. Inspections of LA PA state/fee well sites complete on:	waived		
7. Federal and Indian Lease Wells: The BLM and or 1	the BIA has appro	oved the merger,	name change,
or operator change for all wells listed on Federal or Indian lea	ises on:	BLM	BIA
8. Federal and Indian Units:			
The BLM or BIA has approved the successor of unit operat	or for wells listed on	: <u>n/a</u>	<u> </u>
 Federal and Indian Communization Agreement The BLM or BIA has approved the operator for all wells lis 	` '	na/	
10. Underground Injection Control ("UIC") The Inject, for the enhanced/secondary recovery unit/project for the inject, for the enhanced secondary recovery unit/project for the inject, for the enhanced secondary recovery unit/project for the inject, for the enhanced secondary recovery unit/project for the inject, for the enhanced secondary recovery unit/project for the inject, for the enhanced secondary recovery unit/project for the inject, for the enhanced secondary recovery unit/project for the inject, for the enhanced secondary recovery unit/project for the enhanced secondary recovery re			ansfer of Authority to 2/23/2005
DATA ENTRY:			
1. Changes entered in the Oil and Gas Database on:	2/28/2005		
2. Changes have been entered on the Monthly Operator Chang	ge Spread Sheet on:	2/28/200	<u>05</u>
3. Bond information entered in RBDMS on:	2/28/2005		
4. Fee/State wells attached to bond in RBDMS on:	2/28/2005		
5. Injection Projects to new operator in RBDMS on:	2/28/2005		
6. Receipt of Acceptance of Drilling Procedures for APD/New of	on:	waived	
FEDERAL WELL(S) BOND VERIFICATION: 1. Federal well(s) covered by Bond Number:	UT 0056		
INDIAN WELL(S) BOND VERIFICATION:			
1. Indian well(s) covered by Bond Number:	61BSBDH2912		
FEE & STATE WELL(S) BOND VERIFICATION	•		,
1. (R649-3-1) The NEW operator of any fee well(s) listed cover		61BSBDH2	2919 —
2. The FORMER operator has requested a release of liability from The Division sent response by letter on:	om their bond on: n/a	n/a*	
LEASE INTEREST OWNER NOTIFICATION:			
3. (R649-2-10) The FORMER operator of the fee wells has been of their responsibility to notify all interest owners of this change.		med by a letter fromn/a	the Division
COMMENTS:			
*Bond rider changed operator name from Inland Production Com	pany to Newfield Pro	oduction Company -	received 2/23/05

STATE OF UTAH

	DEPARTMENT OF NATURAL RI	ESOURCES	,	5. LEASE DESIGNATION AND SERIAL NUMBER:			
	DIVISION OF OIL, GAS ANI	D MINING		UTU020252A			
SUNDRY	NOTICES AND REPO	ORTS ON	WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
o not use this form for proposals to drill nev to drill horizontal late	7. UNIT OF CA AGREEMENT NAME: JONAH UNIT						
1. TYPE OF WELL: OIL WELL	GAS WELL OTHER Inje	ection well		8. WELL NAME and NUMBER:			
	MONUMENT 33-6 9. API NUMBER:						
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPA	4301331361						
3. ADDRESS OF OPERATOR:	10. FIELD AND POOL, OR WILDCAT:						
Route 3 Box 3630 CIT	Monument Butte						
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 1832 FSL 1	COUNTY: Duchesne						
OTR/OTR, SECTION, TOWNSHIP, RANGE, I	MERIDIAN: NW/SE, 6, T9S, R17E			STATE: Utah			
11. CHECK APPROP	PRIATE BOXES TO INDICATE			RT, OR OTHER DATA			
·	TYP]	E OF ACTION					
TYPE OF SUBMISSION		TY	PE OF ACTION				
☐ NOTICE OF INTENT	ACIDIZE	DEEPEN		REPERFORATE CURRENT FORMATION			
(Submit in Duplicate)	ALTER CASING	FRACTURE T	TREAT	SIDETRACK TO REPAIR WELL			
Approximate date work will	CASING REPAIR	NEW CONST	RUCTION	TEMPORARITLY ABANDON			
	CHANGE TO PREVIOUS PLANS	OPERATOR O	CHANGE	TUBING REPAIR			
	CHANGE TUBING	PLUG AND A	ABANDON	VENT OR FLAIR			
X SUBSEQUENT REPORT	CHANGE WELL NAME	■ PLUG BACK		WATER DISPOSAL			
(Submit Original Form Only)	CHANGE WELL STATUS	PRODUCTIO	N (START/STOP)	WATER SHUT-OFF			
Date of Work Completion:	COMMINGLE PRODUCING FORMATIONS	RECLAMATI	ION OF WELL SITE	X OTHER: - 5 Year MIT			
06/28/2006	CONVERT WELL TYPE	RECOMPLET	TE - DIFFERENT FORMATION	_			
12 DESCRIBE PROPOSED OR CO	MPLETED OPERATIONS. Clearly show a	all pertinent details	s including dates, depths, vo	lumes, etc.			
On 6/20/06 Nahtan Wiser with that time to perform the test on pressure loss. The well was in	the EPA was contacted concerning 6/27/06. On 6/27/06 the csg was piecting during the test. The tbg presents the test. EPA# UT 20642-0373	the 5-year MI pressured up to ssure was 210 6 API# 43-013	T on the above listed won 1070 psig and charter 0 psig during the test31361	rell. Permission was given at d for 30 minutes with no			
Accepted by the Utah Division of Utah Division of Oil, Gas and Mining FOR RECORD ONLY							
NAME (PLEASE PRINT) Callie Duncan			TITLE Production Clerk				

(This space for State use only)

RECEIVED
JUN 2 9 2006

Mechanical Integrity Test Casing or Annulus Pressure Mechanical Integrity Test U.S. Environmental Protection Agency


U.S. Environmental Protection Agency Underground Injection Control Program 999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness:				6 128	12006		
Test conducted by:	Horrock	5					
Others present:							
Well Name: Monument Field: Monument Butte Location: Nw/se Sec Operator: Newherd Last MIT: / Is this a regularly scheduled Initial test for permit? Test after well rework?	Fectoral 33 Lenah und G T 9 Max d test? [X]	Yes [Yes [X	Type: ER SWD Able Pressure: No No No	Duckesn 2120]	PSIG	
Well injecting during test?	[X]	Yes [No If Yes,	rate:	21	bpd	
Pre-test casing/tubing annulu	is pressure:	0	ps	sig			
MIT DATA TABLE	Test #1		Test #2		Te	st #3	
TUBING	PRESSURE						
Initial Pressure	2100	psig		psig			psig
End of test pressure	2100	psig		psig			psig
CASING / TUBING	ANNULUS		PRESSURE				
0 minutes	1070	psig		psig			psig
5 minutes	1070	psig		psig			psig
10 minutes	1070	psig		psig			psig
15 minutes	1070	psig		psig			psig
20 minutes	1070	psig		psig			psig
25 minutes	1070	psig		psig			psig
30 minutes	1070	psig		psig			psig
minutes	1010	psig		psig			psig
minutes		psig		psig			psig
RESULT	∠ Pass	[]Fail	[] Pass	[]Fail	Pass]Fail

Does the annulus pressure build back up after the test? [] Yes [XNo MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness:	



STATE OF UTAH

DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING			5. LEASE DESIGNATION AND SERIAL NUMBER: USA UTU-020252-A
SUNDRY	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:		
	Il new wells, significantly deepen existing wells be al laterals. Use APPLICATION FOR PERMIT TO		7. UNIT or CA AGREEMENT NAME: JONAH UNIT
1. TYPE OF WELL: OIL WELL	GAS WELL OTHER		8. WELL NAME and NUMBER:
	OAS WEEL CITIEN		MONUMENT 33-6
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COM	IDANV		4301331361
3. ADDRESS OF OPERATOR:	L'ANT	PHONE NUMBER	10. FIELD AND POOL, OR WILDCAT:
Route 3 Box 3630	CITY Myton STATE UT	ZIP 84052 435.646.3721	MONUMENT BUTTE
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 1832 FSL 1		·	COUNTY: DUCHESNE
OTR/OTR, SECTION, TOWNSHIP, RANGE,	MERIDIAN: NWSE, 6, 198, R1/E		STATE: UT
11. CHECK APPROF	PRIATE BOXES TO INDICATE	E NATURE OF NOTICE, REPO	ORT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
□ NOTICE OF INTENT	ACIDIZE	DEEPEN	REPERFORATE CURRENT FORMATION
(Submit in Duplicate)	☐ ALTER CASING	FRACTURE TREAT	SIDETRACK TO REPAIR WELL
Approximate date work will	CASING REPAIR	NEW CONSTRUCTION	TEMPORARITLY ABANDON
	CHANGE TO PREVIOUS PLANS	OPERATOR CHANGE	TUBING REPAIR
	CHANGE TUBING	PLUG AND ABANDON	VENT OR FLAIR
X SUBSEQUENT REPORT	CHANGE WELL NAME	PLUG BACK	WATER DISPOSAL
(Submit Original Form Only)	CHANGE WELL STATUS	PRODUCTION (START/STOP)	WATER SHUT-OFF
Date of Work Completion:	COMMINGLE PRODUCING FORMATIONS	RECLAMATION OF WELL SITE	OTHER: - Five Year MIT
11/12/2009	CONVERT WELL TYPE	RECOMPLETE - DIFFERENT FORMATION	_
12. DESCRIBE PROPOSED OR CO	MPLETED OPERATIONS. Clearly show a	all pertinent details including dates, depths, v	olumes, etc.
that time to perform the tes pressure loss. The well wa	with the EPA was contacted concert on 11-12-09. On 11-12-09 the cases not injecting during the test. The witness the test. EPA# UT 20642-0	sing was pressured up to 1370 psig a tubing pressure was 200 psig during	and charted for 30 minutes with no
	Accepted by Utah Division Oil, Gas and FOR RECOR	Mining	
NAME (PLEASE PRINT) LUCY Chavez-N	laupoto	TITLE Production Clerk	

(This space for State use only)

RECEIVED NOV 1 6 2009

Mechanical Integrity Test Casing or Annulus Pressure Mechanical Integrity Test U.S. Environmental Protection Agency Underground Injection Control Program 999 18th Street, Suite 500 Denver, CO 80202-2466


EPA Witness: Test conducted by: Others present:		- bibbh	Date: _	11 / 12	/ 09	
Well Name: Monument But Field: Monument But Location: 33 Se Operator: New Field,	tte c: <u>6</u> T <u>9</u> I Soe Pippy	V (S) R 17	<u>(</u> Ê/W County	: Duchesn		tah
Last MIT: / Is this a regularly schedule Initial test for permit? Test after well rework? Well injecting during test? Pre-test casing/tubing annulation.	ed test? [] [] [×]	Yes [XYes [Yes [Yes [XYes [XYe] No] No (] No If Ye	s, rate:	PSI	
MIT DATA TABLE TUBING	Test #1 PRESSURE	_	Test #2		Test	#3
Initial Pressure	1370	psig		psig		psig
End of test pressure	1370	psig		psig		psig
CASING / TUBING	ANNULUS		PRESSURE			
0 minutes	1370	psig		psig		psig
5 minutes	1370	psig		psig		psig
10 minutes	1370	psig		psig		psig
15 minutes	1370	psig		psig		psig
20 minutes	1370	psig		psig		psig
25 minutes	1370	psig		psig		psig
30 minutes	1370	psig		psig		psig
minutes	10 /	psig		psig		psig
minutes		psig		psig		psig
RESULT	[X] Pass	[]Fail	Pass	[]Fail	Pass	[]Fail

Does the annulus pressure build back up after the test? [] Yes [X] No

MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness:
organical control of the control of



STATE OF UTAH

(This space for State use only

DEPARTMENT OF NATURAL RESOURCES 5. LEASE DESIGNATION AND SERIAL NUMBER: DIVISION OF OIL, GAS AND MINING USA UTU-020252-A 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: SUNDRY NOTICES AND REPORTS ON WELLS 7. UNIT or CA AGREEMENT NAME: Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged JONAH UNIT wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals 8. WELL NAME and NUMBER: 1. TYPE OF WELL: OIL WELL 🔽 GAS WELL 🔲 OTHER **MONUMENT 33-6** 9. API NUMBER: 2. NAME OF OPERATOR: 4301331361 NEWFIELD PRODUCTION COMPANY 3. ADDRESS OF OPERATOR: PHONE NUMBER 10. FIELD AND POOL, OR WILDCAT: MONUMENT BUTTE Route 3 Box 3630 CITY Myton STATE UT ZIP 84052 435.646.3721 4. LOCATION OF WELL: COUNTY: DUCHESNE FOOTAGES AT SURFACE: 1832 FSL 1829 FEL OTR/OTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSE, 6, T9S, R17E STATE: UT CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA 11. TYPE OF SUBMISSION TYPE OF ACTION ACIDIZE DEEPEN REPERFORATE CURRENT FORMATION ■ NOTICE OF INTENT FRACTURE TREAT SIDETRACK TO REPAIR WELL (Submit in Duplicate) ALTER CASING CASING REPAIR NEW CONSTRUCTION TEMPORARITLY ABANDON Approximate date work will CHANGE TO PREVIOUS PLANS OPERATOR CHANGE TUBING REPAIR CHANGE TUBING PLUG AND ABANDON VENT OR FLAIR SUBSEQUENT REPORT PLUG BACK WATER DISPOSAL CHANGE WELL NAME (Submit Original Form Only) PRODUCTION (START/STOP) WATER SHUT-OFF CHANGE WELL STATUS Date of Work Completion: COMMINGLE PRODUCING FORMATIONS OTHER: - MIT RECLAMATION OF WELL SITE 11/12/2009 CONVERT WELL TYPE RECOMPLETE - DIFFERENT FORMATION 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The above subject well had workover procedures performed (injection leak), attached is a daily status report. On 11-11-09 Nathan Wiser with the EPA was contacted concerning the MIT on the above listed well. Permission was given at that time to perform the test on 11-12-09. On 11-12-09 the csg was pressured up to 1370 psig and charted for 30 minute with no pressure loss. The well was not injecting during the test. The tbg pressure was 200 psig during the test. There was not an EPA representative available to witness the test. EPA UT 20642-03736 API# 43-013-31361 Accepted by the Utah Division of Amended Oil, Gas and Mining FOR RECORD ONLY TITLE Production Clerk NAME (PLEASE PRINT) Lucy Chavez-Naupoto 11/18/2009

RECEIVED

NOV 1 9 2009

Mechanical Integrity Test Casing or Annulus Pressure Mechanical Integrity Test U.S. Environmental Protection Agency Underground Injection Control Program 999 18th Street, Suite 500 Denver, CO 80202-2466


Test conducted by:Neu	rfield, Joe	S. P. PPY	Date:	11 / 12	109	
Others present:		·				
Well Name: Monument			Type: ER SV	VD Stat	us: AC TA	UC
Field: Monument But	<u>te</u>	- A D 17	Amo	Dudman	2 Ctatas	11106
Location: 33 Secondary Sec		N (2) R_11	_(E)/ W Count	y: <u>Vuchesne</u>	zstate:	MEDY
Last MIT:/		imum Allow	able Pressure: _	2120	P	SIG
Last IVIII.	Wax	muni 7 mow	abic i icasure	4.40		
Is this a regularly schedule	d test? []	Yes [X] No			
Initial test for permit?		Yes [
Test after well rework?	[×]	Yes [] No			
Well injecting during test?	[]	Yes $[\times]$] No If Ye	es, rate:		bpd
Pre-test casing/tubing annulu	ic precente.	O lagon		neig		
1 10 tost casing tuoing annuit	is pressure			Pore		
MIT DATA TABLE	Test #1		Test #2		Tes	t #3
TUBING	PRESSURE					
Initial Pressure	1370	psig		psig		psig
End of test pressure	1370	psig		psig		psig
CASING / TUBING	ANNULUS		PRESSURE			
0 minutes	1370	psig		psig		psig
5 minutes	1370	psig		psig		psig
10 minutes	1370	psig		psig		psig
15 minutes	1370	psig		psig		psig
20 minutes	1370	psig		psig		psig
25 minutes	1370	psig		psig		psig
30 minutes	1370	psig		psig		psig
minutes	1 4 1 -	psig		psig		psig
minutes		psig		psig		psig
RESULT	[X] Pass	[]Fail	[] Pass	[]Fail	[] Pass	[]Fail

Does the annulus pressure build back up after the test? [] Yes [X] No

MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness:	





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY REGION 8

1595 Wynkoop Street
DENVER, CO 80202-1129
Phone 800-227-8917
http://www.epa.gov/region08

Ref: 8ENF-UFO

DEC = 2 2009

<u>CERTIFIED MAIL 7005-1160-0005-3396-8558</u> RETURN RECEIPT REQUESTED Accepted by the Utel Colon of Oil, Gas and Mining FOR RECORD ONLY

Mike Guinn, District Manager Newfield Production Company Route 3, Box 3630 Myton, Utah 84052

43 013 31361 95 17E 6

Re:

Underground Injection Control (UIC) Permission To Resume Injection Monument Federal #33-6-9-17 Well EPA Permit #UT20642-03736

Jonah Oil Field

Duchesne County, Utah

Dear Mr. Guinn:

On November 30, 2009, EPA received information from Newfield Production Company on the above referenced well concerning the workover to address its leaking tubing and packer and the followup mechanical integrity test (MIT) conducted on November 12, 2009. The data submitted shows that the well passed the required MIT. Therefore, pursuant to Title 40 of the Code of Federal Regulations Section 144.51(q)(2) (40 C.F.R. §144.51(q)(2)), permission to resume injection is granted. Under continuous service, the next MIT will be due on or before November 12, 2014.

Pursuant to 40 C.F.R. §144.52(a)(6), if the well is not used for a period of at least two (2) years ("temporary abandonment"), it shall be plugged and abandoned unless EPA is notified and procedures are described to EPA ensuring the well will not endanger underground sources of drinking water ("non-endangerment demonstration") during its continued temporary abandonment. A successful MIT is an acceptable non-endangerment demonstration and would be necessary every two (2) years the well continues in temporary abandonment.

Failure to comply with a UIC Permit, or the UIC regulations found at 40 C.F.R. Parts 144 through 148 constitute one or more violations of the Safe Drinking Water Act, 42 U.S.C. §300h. Such non-compliance may subject you to formal enforcement by EPA, as codified at 40 C.F.R. Part 22.

RECEIVED
DEC 0 8 2009

DIV. OF OIL, GAS & MINING

If you have any questions concerning this letter, you may contact Nathan Wiser at (303) 312-6211. Please direct all correspondence to the attention of Nathan Wiser at Mail Code 8ENF-UFO.

Sincerely,

C Mark A.R. Chalfant

Director

Technical Enforcement Program

cc: Curtis Cesspooch, Chairman
Uintah & Ouray Business Committee
P.O. Box 190
Fort Duchesne, Utah 84026

Ferron Secakuku, Natural Resources Director Ute Indian Tribe P.O. Box 190 Fort Duchesne, Utah 84026

Gil Hunt Utah Division of Oil, Gas and Mining P.O. Box 145801 Salt Lake City, Utah 84114 Sundry Number: 56706 API Well Number: 43013313610000

	STATE OF UTAH		FORM 9	
DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING			5.LEASE DESIGNATION AND SERIAL NUMBER: UTU-020252A	
SUNDF	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
	oposals to drill new wells, significantly d reenter plugged wells, or to drill horizon n for such proposals.		7.UNIT or CA AGREEMENT NAME: GMBU (GRRV)	
1. TYPE OF WELL Water Injection Well			8. WELL NAME and NUMBER: MONUMENT 33-6	
2. NAME OF OPERATOR: NEWFIELD PRODUCTION CO	OMPANY		9. API NUMBER: 43013313610000	
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT		PHONE NUMBER: Ext	9. FIELD and POOL or WILDCAT: MONUMENT BUTTE	
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1832 FSL 1829 FEL			COUNTY: DUCHESNE	
QTR/QTR, SECTION, TOWNS	HIP, RANGE, MERIDIAN: 06 Township: 09.0S Range: 17.0E Meridia	an: S	STATE: UTAH	
11. CHEC	K APPROPRIATE BOXES TO INDICATE	NATURE OF NOTICE, REPOR	RT, OR OTHER DATA	
TYPE OF SUBMISSION		TYPE OF ACTION		
	ACIDIZE	ALTER CASING	CASING REPAIR	
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME	
Approximate date work will start:	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE	
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN [FRACTURE TREAT	☐ NEW CONSTRUCTION	
10/13/2014	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK	
SPUD REPORT	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION	
Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON	
	_{[-}		WATER DISPOSAL	
DRILLING REPORT	L TUBING REPAIR	☐ VENT OR FLARE ☐		
Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION	
	WILDCAT WELL DETERMINATION	OTHER	OTHER: 5 YR MIT	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. 5 YR MIT performed on the above listed well. On 10/13/2014 the casing was pressured up to 1211 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tbg pressure was 346 psig during the test. There was not an EPA representative available to witness the test. EPA #UT22197-03736 NAME (PLEASE PRINT) PHONE NUMBER TITLE				
Lucy Chavez-Naupoto	435 646-4874	Water Services Technician		
SIGNATURE N/A		DATE 10/14/2014		

Sundry Number: 56706 API Well Number: 43013313610000

Mechanical Integrity Test Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency
Underground Injection Control Program
999 18th Street, Suite 500 Denver, CO 80202-2466

Operator: NEWRIELD Last MIT:	He T 9 1 Maxi	N/S R_/7	Type: ER SWD Status E/W County: Duches No. able Pressure: 1788	-0373(c) s: AC TA UC State: UT
Well Name: Field: Monument By Location: 33 Sec: Operator: New FIELD Last MIT: Is this a regularly scheduled	He T 9 1 Maxi	N/S R_/7	E/W County: Duenes No.	State: UT
Field: Monument By Location: 33 Sec: Operator: NEWEXELT Last MIT: /	L T 9 P Maxi	N/S R <u>/7</u> imum Allowa	E/W County: Duenes No.	State: UT
Field: Monument By Location: 33 Sec: Operator: NEWEXELT Last MIT: /	L T 9 P Maxi	N/S R <u>/7</u> imum Allowa	E/W County: Duenes No.	State: UT
Location: 33 Sec: Operator: NEWEXELT Last MIT:	L T 9 P Maxi	imum Allowa Yes [able Pressure: 1788	
Operator: NEWRIELD Last MIT:	Maxi	imum Allowa Yes [able Pressure: 1788	
Last MIT: /	/ Maxi	Yes [] No	PSIG
ls this a regularly scheduled	test? [\rightharpoonup]	Yes [] No	1 510
	[]	-	5	
	[]	-	5	
Initial test for permit?	ſΊ	Yes [V	j No	
Test after well rework?			No	
Well injecting during test?	[]	Yes [No If Yes, rate:	bpd
re-test casing/tubing annulus	e precente.	0	346TBG psig	
16-162t casm&monts amenda	s pressure.		paig	
MIT DATA TABLE	Test #1		Test #2	Test #3
TUBING	PRESSURE			
Initial Pressure	346	psig	psig	psig
End of test pressure	3.46	psig	psig	psig
CASING / TUBING	ANNULUS		PRESSURE	
0 minutes	1216	psig	psig	psig
5 minutes	1215	psig	psig	psig
10 minutes	1213	psig	psig	psig
15 minutes	1213	psig	psig	psig
20 minutes	1212	psig	psig	psig
25 minutes	1212	psig	psig	psig
30 minutes	1211	psig	psig	psig
minutes		psig	psig	psig
minutes		psig	psig	psig
RESULT	Pass	[]Fail	Pass Fail	Pass Fail

Does the annulus pressure build back up after the test? [] Yes [] No

MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness	

Sundry Number: 56706 API Well Number: 43013313610000

PSI Absolute (psi) / Absolute Pressure -1900 -1700 1600 -1500 -1400 1300 100 C -700 500 300 -200 P23445 Legend 11:36:40 AM 10/13/2014 -06:00 11:28:20 AM 10/13/2014 -06:00 10/13/2014 11:04:21 AM 11:20:00 AM 10/13/2014 -06:00 11:11:40 AM 10/13/2014 -06:00 0 AM 2014 30

Monument Federal 33-6-9-17, 5 year MIT 10-13-14

Spud Date: 10 24 92 Put on Production: 12 1 92

Monument Federal #33-6-9-17

Put on Injection: 1 21 93 GL: 5267' KB: 5277'

Injection

Initial Production: 5 BOPD,

SURFACE CASING CSG SIZE: 8-5 8" GRADE: J-55

WEIGHT: 24st LENGTH: 6 jts. (256.60°)

DEPTH LANDED: 256'

HOLE SIZE:12-1-4" CEMENT DATA: $161 \, sxs \, 75 - 250 \, sw \, 20 \, scl + 1.4 \, sack Celoflake. 10 bbls back and did not fall, down bole.$

PRODUCTION CASING

CSG SIZE: 5-1 2" GRADE: J-55 WEIGHT: 15.5# LENGTH: 125 jts. (5697') DEPTH LANDED: 5713' HOLE SIZE: 7-7.8"

CEMENT DATA: 226 sx hilift + 400 sx Class "G"

CEMENT TOP AT: 1230' per CBL

SIZE GRADE WT.: 2-7 8" J-55 6.5# NO. OF JOINTS, 132 jts (4073.57') SEATING NIPPLE: 2-7 8" (1.10") SN LANDED AT: 4085/83" KB PACKER SET at: 4090.41° TOTAL STRING LENGTH FOT a 4093.83 Wellbore Diagram FRAC JOB 11/28/92 4658'-4824' 6/29/01 4164'-4188' 6/28/06 5-28-08 11-12-09 Packer a 4090.41 EOT ut 4093.83° 4164'-4188' 4658'-4666' D-1 sds 4672"-4676" D-1 sds 4814"-4824" C sds

PBTD a 5691° TD a 5740°

NM MCFD, 5 BWPD

Frac as follows:

610 bbls fluid. Treated a avg press of 2900 psi w avg rate of 32 BPM. ISIP 1850 psi.

Break GB perfs as follows: Spot 2.5 bbls 15% HC1. - 23 bbl wtr across perfs, let sit 30 min., break perfs

u 2300 psi, estab. injection rate u 3-4 bpm at 1100 psi.

5 Year MIT completed and submitted. Zone Stimulation. Tubing details

Tubing leak update rod and tubing.

NEWFIELD

Monument Federal #33-6-9-17 1832' FSL & 1829' FEL NWSE Section 6-T9S-R17E Duchesne Co, Utah API # 43-013-31361; Lease # U-020252-A

PERFORATION RECORD

11 26 92 4658'-4666' 4 holes 11 26 92 4672"-4676" 2 holes 11 26 92 4814"-4824" 6 holes 6 29 01 4164'-4188' 96 holes